

ARKANSAS DEPARTMENT OF TRANSPORTATION

012535

POPE CO. LINE – LITTLE ROCK INTERSTATE SIGN UPGRADES (S)

FEDERAL AID PROJECT NHPP-0076(380)

THE PURPOSE OF THIS PROJECT IS TO REPLACE OVERHEAD/GROUND MOUNTED SIGNS AND FOUR OVERHEAD STRUCTURES IN VARIOUS INTERSTATES IN VARIOUS COUNTIES. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL ITEMS, EARTHWORK, MAINTENANCE OF TRAFFIC, EROSION CONTROL, SIGN ITEMS, AND MISC. ITEMS.

ROUTES: VARIOUS

SECTIONS: VARIOUS

COUNTY: VARIOUS

LENGTH: NO PROJECT LENGTH.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202037	R&D OF BARRIER WALL	161.00	LF
202156	R&D OF OVERHEAD SIGN STRUCTURE	5.00	EACH
210213	UNCLASSIFIED EXCAVATION	100.00	CUYD
210611	COMPACTED EMBANKMENT	100.00	CUYD
601001	MOBILIZATION	1.00	L.S.
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	2,941.00	SQFT
604023	TRAFFIC DRUMS	120.00	EACH
604031	FURN.&INSTL.PRCST.CONC.BARR.	746.00	LF
604036	RELO.PRECAST CONCRETE BARRIER	1,392.00	LF
604051	REMOVABLE CONST.PVMT.MRK.	11,189.00	LF
604061	REMOVAL OF PERM.PVMT.MRK.	11,189.00	LF
604071	ADVANCE WARNING ARROW PANEL	14.00	DAY
604078	PORT.CHANGEABLE MESSAGE SIGN	6.00	WEEK
604160	MOBILE SPEED NOTIFICATION SYSTEM SPECIAL	1.00	EACH
620001	LIME	1.00	TON
620011	SEEDING	0.50	ACRE
620022	MULCH COVER	0.50	ACRE
620030	WATER	51.00	MGAL
621021	SILT FENCE	600.00	LF
621111	SEDIMENT REMOVAL & DISPOSAL	22.00	CUYD
623001	SECOND SEEDING APPLICATION	0.50	ACRE
631042	CONC.BARR.WALL(MEDIAN TYPE SP-1)	143.00	LF
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
708224	ELEC.COND.-IN-CONDUIT(2C/2 AWG,EGC)	600.00	LF
708451	ELECT.COND. FOR LUMINAIRES	50.00	LF
710004	NON-METALLIC CONDUIT (2")	180.00	LF
714728	REM & REINSTALL LIGHTING	1.00	EACH
719502	ENHANCED THERMO. PVMT. MRK. WH (6")	3,935.00	LF
719505	ENHANCED THERMO. PVMT. MRK. WH (12")	771.00	LF
719602	ENHANCED THERMO. PVMT. MRK. YL (6")	2,520.00	LF
721002	RAISED PAVEMENT MARKERS-2	146.00	EACH
724027	STEEL O.H.SIGN STRUCTURE (OC-030-60-93)	1.00	EACH
724028	STEEL O.H.SIGN STRUCTURE (OC-430-60-60)	1.00	EACH
724029	STEEL O.H.SIGN STRUCTURE (OC-630-60-63)	1.00	EACH
724030	STEEL O.H.SIGN STRUCTURE (OH-030-60-94)	1.00	EACH

724034	STEEL O.H.SIGN STRUCTURE (OH-030-60-95)	1.00	EACH
724069	BARRIER WALL PEDESTAL MOUNT	13.00	EACH
724503	MOD.OF EXIST.OVHD.SIGN STR.	3.00	EACH
725003	G.SIGN-ROADSIDE MOUNT(DMNTBL)	6,362.00	SQFT
725103	G.SIGN-OVERHEAD MOUNT(DEMOUNT)	1,692.00	SQFT
726002	STANDARD SIGN	2,707.00	SQFT
727004	EXIT NO.PANEL(TYPE A)	630.00	SQFT
727005	EXIT NO.PANEL(TYPE B)	73.00	SQFT
729015	CHANNEL POST SIGN SUP-U 1	76.00	EACH
730499	OMNI-DIR.BRKAWAY SIGN SUPPORT-TYPE G-1	30.00	EACH
730500	OMNI-DIR.BRKAWAY SIGN SUPPORT-TYPE G-2	9.00	EACH
730502	OMNI-DIR.BRKAWAY SIGN SUPPORT-TYPE G2-1	70.00	EACH
730503	OMNI-DIR.BRKAWAY SIGN SUPPORTS-TYPE G2-2	7.00	EACH
730505	OMNI-DIR.BRKAWAY SIGN SUPPORT-TYPE G2-4	10.00	EACH
730506	OMNI-DIR.BRKAWAY SIGN SUPPORT-TYPE G2-5	4.00	EACH
731061	TEMP. IMPACT ATTEN. BARR.	2.00	EACH
731062	TEMP. IMPACT ATTEN. BARRIER (REPAIR)	6.00	EACH
731065	TEMP. IMPACT ATTENUATION BARRIER (RELO)	4.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHIN ONE HUNDRED NINETY (190) CALENDAR DAYS.