

ARKANSAS DEPARTMENT OF TRANSPORTATION

020853

YANCOPIN RD. SURFACING (DESHA CO.) (S)

STATE JOB

THE PURPOSE OF THIS PROJECT IS TO CONSTRUCT SUBGRADE AND SURFACE APPROXIMATELY 3.388 MILE OF COUNTY ROAD 41 IN DESHA COUNTY. THIS PROJECT CONSISTS OF CLEARING AND GRUBBING, REMOVAL AND DISPOSAL OF PIPE CULVERTS, SHAPING ROADWAY SECTION, AGGREGATE BASE COURSE, ACHM SURFACE COURSE, MAINTENANCE OF TRAFFIC, MINOR DRAINAGE STRUCTURES, EROSION CONTROL, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: CR 41

COUNTY: DESHA

LENGTH: 3.388 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

201011	CLEARING	1.00	STA
201111	GRUBBING	1.00	STA
202096	R&D OF PIPE CULVERTS	1.00	EACH
213011	SHAPING ROADWAY SECTION	181.00	STA
303117	AGGR.BASE COURSE(CLASS 7)	15,438.00	TON
401011	TACK COAT	45.00	GAL
407162	MA IN ACHM SURFACE(1/2")	4,252.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	267.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	339.00	SQFT
604041	CONST.PAVEMENT MARKINGS	35,904.00	LF
605601	18" R.C.PIPE CULVERTS(CL.3)	36.00	LF
605856	18" FES R.C.PIPE CLVT.	2.00	EACH
606994	SELECTED PIPE BEDDING	30.00	CUYD
606996	SELECTED PIPE BACKFILL	10.00	CUYD
620001	LIME	6.00	TON
620011	SEEDING	3.00	ACRE
620022	MULCH COVER	6.00	ACRE
620030	WATER	367.30	MGAL
621001	TEMPORARY SEEDING	3.00	ACRE
621031	SAND BAG DITCH CHECKS	800.00	BAG
623001	SECOND SEEDING APPLICATION	3.00	ACRE
624001	SOLID SODDING	10.00	SQYD
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
718001	REFL.PAINT PVMT.MRK.WH(4")	35,904.00	LF
718101	REFL.PAINT PVMT.MRK.YL(4")	35,904.00	LF
726002	STANDARD SIGN	29.00	SQFT
729003	CHANNEL POST SIGN SUPPORT-C	9.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.