

ARKANSAS DEPARTMENT OF TRANSPORTATION

050439

HWY. 25 STR. & APPRS. (INDEPENDENCE CO.) (S)

FEDERAL AID PROJECT NHPP-0032(44)

THE PURPOSE OF THIS PROJECT IS TO REPLACE ONE BRIDGE ON HIGHWAY 25 IN INDEPENDENCE COUNTY. THIS PROJECT CONSISTS OF CLEARING AND GRUBBING, REMOVAL AND DISPOSAL ITEMS, EARTHWORK, AGGREGATE BASE COURSE, ACHM BINDER, AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, APPROACH SLAB AND GUTTERS, MAINTENANCE OF TRAFFIC, GUARDRAIL, EROSION CONTROL, RUMBLE STRIPES, CONSTRUCT ONE BRIDGE NO. 07721 (196.00'), AND MISC. ITEMS.

ROUTES: 25

SECTIONS: 5

COUNTY: INDEPENDENCE

LENGTH: 0.434 mile in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

201011	CLEARING	24.00	STA
201111	GRUBBING	24.00	STA
202011	R&D OF FENCE	3,276.00	LF
202017	R&D OF GATES	8.00	EACH
202062	R&D OF CONCRETE DRIVEWAYS	47.00	SQYD
202096	R&D OF PIPE CULVERTS	5.00	EACH
202132	R&D OF GUARDRAIL	450.00	LF
205011	REMOV.EXIST.BR.STR.(SITE 1)	1.00	L.S.
210213	UNCLASSIFIED EXCAVATION	6,839.00	CUYD
210611	COMPACTED EMBANKMENT	30,684.00	CUYD
210702	SOIL STABILIZATION	100.00	TON
303117	AGGR.BASE COURSE(CLASS 7)	7,284.00	TON
401011	TACK COAT	1,412.00	GAL
406161	M.A. IN ACHM BINDER(1")	2,312.00	TON
406412	A.B.(PG70-22)ACHM BINDER(1")	114.00	TON
407162	MA IN ACHM SURFACE(1/2")	1,985.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	124.00	TON
412002	COLD MILLING ASPHALT PVMT.	489.00	SQYD
414011	ASPH.CONC.PATCH-MAINT.	10.00	TON
415011	ACHM PATCH.EXIST.RDWY.	10.00	TON
504031	APPROACH SLABS	150.40	CUYD
504264	APPROACH GUTTERS	16.80	CUYD
505011	P.C.CONCRETE DRIVEWAY	88.73	SQYD
601001	MOBILIZATION	1.00	L.S.
602011	FURNISHING FIELD OFFICE	1.00	EACH
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	472.00	SQFT
604013	BARRICADES	32.00	LF
604023	TRAFFIC DRUMS	60.00	EACH
604031	FURN.&INSTL.PRCST.CONC.BARR.	1,092.00	LF
604036	RELO.PRECAST CONCRETE BARRIER	426.00	LF
604041	CONST.PAVEMENT MARKINGS	10,040.00	LF
604051	REMOVABLE CONST.PVMT.MRK.	784.00	LF
604083	VERTICAL PANELS	22.00	EACH

605012	CONC.DITCH PAVING(TYPE B)	160.00	SQYD
606703	18" SIDE DRAIN	250.00	LF
606994	SELECTED PIPE BEDDING	20.00	CUYD
611008	4" PIPE UNDERDRAINS	500.00	LF
611013	UNDERDRAIN OUTLET PROTECTORS	2.00	EACH
617005	GUARDRAIL (TYPE A)	450.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	4.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	4.00	EACH
619027	WIRE FENCE (TYPE C)	3,280.00	LF
619332	16' STEEL GATES	8.00	EACH
620001	LIME	9.00	TON
620011	SEEDING	4.73	ACRE
620022	MULCH COVER	22.02	ACRE
620030	WATER	836.10	MGAL
621001	TEMPORARY SEEDING	17.29	ACRE
621021	SILT FENCE	5,876.00	LF
621111	SEDIMENT REMOVAL & DISPOSAL	260.00	CUYD
621151	ROCK DITCH CHECKS	66.00	CUYD
621169	FILTER SOCK (18")	351.00	LF
621173	WATTLE (20")	180.00	LF
623001	SECOND SEEDING APPLICATION	4.73	ACRE
624001	SOLID SODDING	71.00	SQYD
626003	EROSION CONTROL MATTING-3	471.00	SQYD
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
636001	BRIDGE CONSTRUCTION CONTROL	1.00	L.S.
637001	MAILBOXES	2.00	EACH
637017	MAILBOX SUPPORTS (SINGLE)	2.00	EACH
642102	CENTERLINE RUMBLE STRIPES IN ASPH. RDWYS	2,046.00	LF
719002	THERMO.PVMT.MARK.WH(6")	4,884.00	LF
719102	THERMO.PVMT.MARK.YL(6")	4,880.00	LF
721002	RAISED PAVEMENT MARKERS-2	31.00	EACH
731071	TEMP. IMPACT ATTEN. BARR.	3.00	EACH
731072	TEMP. IMPACT ATTEN. BARRIER (REPAIR)	3.00	EACH
801001	UNCLASS.EXCAV.FOR STRS-BR	475.00	CUYD
802112	CLASS 5 CONCRETE-BRIDGE	276.90	CUYD
802122	CLASS S(AE) CONCRETE-BRIDGE	359.70	CUYD
802599	PRESTRESSED CONC. BEAMS (TYPE III)	967.50	LF
803004	CLASS 2 PROTECTIVE SURFACE TREATMENT	1,052.60	SQYD
804003	REINF.STEEL-ROADWAY (GR 60)	19,160.00	LB
804013	REINF.STEEL-BRIDGE (GR 60)	45,030.00	LB
804023	EPOXY COAT.REINF.STEEL-GR 60	82,920.00	LB
805022	STEEL PILING (HP 12X53)	470.00	LF
805504	PREBORING	318.00	LF
808002	ELASTOMERIC BEARINGS	9,653.00	CUIN
812004	BRIDGE NAME PLATE (TYPE D)	1.00	EACH
816003	FILTER BLANKET	919.00	SQYD
816111	DUMPED RIPRAP	580.00	CUYD

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHIN FIVE HUNDRED TWENTY (520) CALENDAR DAYS.