

ARKANSAS DEPARTMENT OF TRANSPORTATION

061748

MILL CREEK STR. & APPRS. (S)

FEDERAL AID PROJECT BFPO-0026(47)

THE PURPOSE OF THIS PROJECT IS TO REPLACE ONE BRIDGE ON HIGHWAY 600 IN GARLAND COUNTY. THIS PROJECT CONSISTS OF CLEARING AND GRUBBING, REMOVAL AND DISPOSAL ITEMS, EARTHWORK, AGGREGATE BASE COURSE, ACHM BINDER AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, MINOR DRAINAGE, EROSION CONTROL, PAVEMENT MARKING, CONSTRUCT ONE CONTINUOUS R.C. SLAB (105'), AND MISC. ITEMS.

ROUTES: 600

SECTIONS: 21

COUNTY: GARLAND

LENGTH: 0.028 mile in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

201011	CLEARING	3.00	STA
201111	GRUBBING	3.00	STA
202084	R&D OF SIGN FOUNDATIONS	5.00	EACH
202191	R&D OF SIGNS	3.00	EACH
205011	REMV.EXIST.BR.STR.(SITE 1)	1.00	L.S.
210213	UNCLASSIFIED EXCAVATION	160.00	CUYD
210611	COMPACTED EMBANKMENT	900.00	CUYD
210672	REMOVING AND REPLACING TOPSOIL	90.00	CUYD
210702	SOIL STABILIZATION	50.00	TON
303117	AGGR.BASE COURSE(CLASS 7)	300.00	TON
401011	TACK COAT	77.00	GAL
406161	M.A. IN ACHM BINDER(1")	14.00	TON
406402	A.B.(PG64-22)ACHM BINDER(1")	1.00	TON
407162	MA IN ACHM SURFACE(1/2")	96.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	6.00	TON
412002	COLD MILLING ASPHALT PVMT.	400.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	5.00	TON
504264	APPROACH GUTTERS	8.40	CUYD
601001	MOBILIZATION	1.00	L.S.
602011	FURNISHING FIELD OFFICE	1.00	EACH
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	206.00	SQFT
604013	BARRICADES	32.00	LF
605012	CONC.DITCH PAVING(TYPE B)	20.00	SQYD
611008	4" PIPE UNDERDRAINS	100.00	LF
611013	UNDERDRAIN OUTLET PROTECTORS	2.00	EACH
617312	GUARDRAIL TERMINAL (TYPE 2)	4.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	4.00	EACH
620001	LIME	1.00	TON
620015	SPECIAL SEEDING	0.39	ACRE
620023	SPECIAL MULCH COVER	0.78	ACRE
620030	WATER	47.90	MGAL
621021	SILT FENCE	715.00	LF
621111	SEDIMENT REMOVAL & DISPOSAL	46.00	CUYD

621151	ROCK DITCH CHECKS	9.00	CUYD
621169	FILTER SOCK (18")	200.00	LF
621202	SPECIAL TEMPORARY SEEDING	0.39	ACRE
623006	SPECIAL SECOND SEEDING APPLICATION	0.39	ACRE
624001	SOLID SODDING	13.00	SQYD
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
636001	BRIDGE CONSTRUCTION CONTROL	1.00	L.S.
718002	REFL.PAINT PVMT.MRK.WH(6")	700.00	LF
718102	REFL.PAINT PVMT.MRK.YL(6")	700.00	LF
721002	RAISED PAVEMENT MARKERS-2	5.00	EACH
801001	UNCLASS.EXCAV.FOR STRS-BR	233.00	CUYD
802111	CLASS S CONCRETE-BRIDGE	129.40	CUYD
802122	CLASS S(AE) CONCRETE-BRIDGE	242.90	CUYD
802229	ARCHITECTURAL FINISH	1,772.00	SQFT
802231	STAINING CONCRETE SURFACES	2,371.00	SQFT
803004	CLASS 2 PROTECTIVE SURFACE TREATMENT	303.40	SQYD
804003	REINF.STEEL-ROADWAY (GR 60)	420.00	LB
804013	REINF.STEEL-BRIDGE (GR 60)	19,720.00	LB
804023	EPOXY COAT.REINF.STEEL-GR 60	92,140.00	LB
805022	STEEL PILING (HP 12X53)	200.00	LF
805504	PREBORING	190.00	LF
812004	BRIDGE NAME PLATE (TYPE D)	1.00	EACH
816003	FILTER BLANKET	724.00	SQYD
816111	DUMPED RIPRAP	401.00	CUYD

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHIN TWO HUNDRED FORTY (240) CALENDAR DAYS.