

ARKANSAS DEPARTMENT OF TRANSPORTATION

061921

HWYS. 10 & 365 PED. IMPVTS. (PULASKI CO.) (S)

FEDERAL AID PROJECT VRU-9315(72)

THE PURPOSE OF THIS PROJECT IS TO CONSTRUCT CROSSWALKS, PEDESTRIAN, AND ADA IMPROVEMENTS ON HIGHWAYS 10 AND 365 IN PULASKI COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL ITEMS, EARTHWORK, ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, EROSION CONTROL, TRAFFIC ITEMS, LIGHTING ITEMS, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 10 & 365

SECTIONS: 8 & 11

COUNTY: PULASKI

LENGTH: 1.438 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202003	R&D OF CURB AND GUTTER	1,374.00	LF
202047	R&D OF CONCRETE ISLANDS	210.00	SQYD
202062	R&D OF CONCRETE DRIVEWAYS	13.00	SQYD
202072	R&D OF WALKS	722.00	SQYD
202191	R&D OF SIGNS	3.00	EACH
210213	UNCLASSIFIED EXCAVATION	150.00	CUYD
210611	COMPACTED EMBANKMENT	150.00	CUYD
309505	P.C.CONCRETE BASE-5"	388.00	SQYD
401011	TACK COAT	361.00	GAL
407162	MA IN ACHM SURFACE(1/2")	378.00	TON
407452	AB(PG76-22)ACHM SURF(1/2")	20.00	TON
412002	COLD MILLING ASPHALT PVMT.	3,840.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	25.00	TON
601001	MOBILIZATION	1.00	L.S.
602011	FURNISHING FIELD OFFICE	1.00	EACH
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	1,521.00	SQFT
604013	BARRICADES	160.00	LF
604023	TRAFFIC DRUMS	302.00	EACH
604026	TRAFFIC CONE	51.00	EACH
604051	REMOVABLE CONST.PVMT.MRK.	53.00	LF
604055	REMOVAL OF CONST.PVMT.MRK.	53.00	LF
604061	REMOVAL OF PERM.PVMT.MRK.	1,625.00	LF
604083	VERTICAL PANELS	77.00	EACH
620030	WATER	1.90	MGAL
621021	SILT FENCE	900.00	LF
621031	SAND BAG DITCH CHECKS	198.00	BAG
621111	SEDIMENT REMOVAL & DISPOSAL	48.00	CUYD
621168	FILTER SOCK (12")	144.00	LF
624001	SOLID SODDING	150.00	SQYD
632011	CONCRETE ISLAND	374.00	SQYD
633011	CONCRETE WALKS	433.00	SQYD
634201	CC CURB & GUTTER-A (1'6")	1,346.00	LF
634291	CC CURB & GUTTER-C (1'6")	49.00	LF

635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
640021	MODIFYING DROP INLETS	2.00	EACH
641020	WHEELCHAIR RAMPS (TYPE 3)	65.00	SQYD
641022	WHEELCHAIR RAMPS (TYPE 5)	123.00	SQYD
641023	WHEELCHAIR RAMPS (TYPE 6)	326.00	SQYD
641500	SURFACE-APPLIED DETECT. WARNING PANELS	261.00	SQFT
701227	SYS.LOCAL CNTRL.TS 2-TY.2,E-NET(8 PHASE)	1.00	EACH
701401	TRAF.SIG.CNTRL.(MOD.)	6.00	EACH
701722	ETHERNET SWITCH, T100 HARDENED (8-PORT)	1.00	EACH
701751	E-NET CABLE (EXTERIOR CAT 5E)	58.00	LF
702304	LOCAL RADIO (E-NET 5.8) WITH ANTENNA	1.00	EACH
703031	RRFB - AC	7.00	EACH
706039	TRAF.SIG.HEAD,LED,(3SEC.,1WAY)	6.00	EACH
707006	CENTRAL CONTROL UNIT	6.00	EACH
707007	POLE MOUNTED ASSEMBLY	43.00	EACH
707015	COUNTDOWN PED.SIG.HEAD,LED	42.00	EACH
708007	TRAFFIC SIGNAL CABLE (5C/12)	7,519.00	LF
708008	TRAFFIC SIGNAL CABLE (5C/14)	7,649.00	LF
708022	TRAFFIC SIGNAL CABLE (12C/14)	985.00	LF
708038	TRAFFIC SIGNAL CABLE (20C/14)	649.00	LF
708207	ELEC.COND.-IN-CONDUIT(1C/8 AWG, EGC)	4,832.00	LF
708211	ELEC.COND.-IN-CONDUIT(1C/12 AWG,EGC)	270.00	LF
708217	ELEC.COND.-IN-CONDUIT(2C/6 AWG)	30.00	LF
708219	ELEC.COND.-IN-CONDUIT(2C/8 AWG)	572.00	LF
708221	ELEC.COND.-IN-CONDUIT (2C/10 AWG)	642.00	LF
708451	ELECT.COND. FOR LUMINAIRES	270.00	LF
709004	GALV. STEEL CONDUIT (2")	180.00	LF
710004	NON-METALLIC CONDUIT (2")	508.00	LF
710005	NON-METALLIC CONDUIT (3")	2,143.00	LF
711004	CONCRETE PULL BOX (TYPE 2)	13.00	EACH
711005	CONCRETE PULL BOX (TYPE 3)	3.00	EACH
711105	CONCRETE PULL BOX (TYPE 2 HD)	16.00	EACH
711106	CONCRETE PULL BOX (TYPE 3 HD)	1.00	EACH
714026	T.S.M.ARM & POLE W/FND(26)	2.00	EACH
714048	T.S.M.ARM & POLE W/FND(48)	1.00	EACH
714770	R.I. POLE (160W, BREAKAWAY BASE, 30')	6.00	EACH
715011	TRAFFIC SIGNAL PED. POLE W/ FND	32.00	EACH
715120	PEDESTAL TY SERV POINT ASSEM (6 CIRUIT)	3.00	EACH
715704	REMOV.L. TRAFFIC SIG.EQUIPMENT	1.00	L.S.
718004	REFL.PAINT PVM.T.MRK.WH(10")	130.00	LF
718104	REFL.PAINT PVM.T.MRK.YL(10")	480.00	LF
719002	THERMO.PVM.T.MARK.WH(6")	120.00	LF
719006	THERMO.PVM.T.MARK.WH(24")	3,711.00	LF
719102	THERMO.PVM.T.MARK.YL(6")	480.00	LF
719200	THERMO.PVM.T.MARK.(YIELD LINE)	116.00	LF
719201	THERMO.PVM.T.MARK.(WORD)	2.00	EACH
719202	THERMO.PVM.T.MARK.(ARROW)	2.00	EACH
726002	STANDARD SIGN	120.00	SQFT
729005	CHANNEL POST SIGN SUP-U 1	5.00	EACH
729006	CHANNEL POST SIGN SUP-U 2	6.00	EACH
733005	VIDEO DETECTOR ROTATION	8.00	EACH
733035	VIDEO CABLE (EXTERIOR CAT 5E)	50.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHIN TWO HUNDRED SIXTY-SIX (266) CALENDAR DAYS.