

ARKANSAS DEPARTMENT OF TRANSPORTATION

061938

DISTRICT 6 INTERSTATE GUARDRAIL IMPVTS. (S)

FEDERAL AID PROJECT HSIP-9253(129)

THE PURPOSE OF THIS PROJECT IS TO PLACE GUARDRAILS ALONG VARIOUS INTERSTATES IN PULASKI COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL ITEMS, EARTHWORK, AGGREGATE BASE COURSE, ACHM SURFACE COURSE, APPROACH GUTTER, MAINTENANCE OF TRAFFIC, GUARDRAIL, EROSION CONTROL, AND MISC. ITEMS.

ROUTES: VARIOUS

SECTIONS: VARIOUS

COUNTY: PULASKI

LENGTH: NO PROJECT LENGTH.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202052	R&D OF APPROACH GUTTERS	80.00	EACH
202132	R&D OF GUARDRAIL	27,740.00	LF
202143	R&D OF IMPACT ATTEN.BARRIER	3.00	EACH
202144	R&D OF CONCRETE PIER PROTECTION	190.00	LF
210213	UNCLASSIFIED EXCAVATION	1,741.00	CUYD
303117	AGGR.BASE COURSE(CLASS 7)	6,762.00	TON
401011	TACK COAT	500.00	GAL
407162	MA IN ACHM SURFACE(1/2")	1,458.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	90.00	TON
414011	ASPH.CONC.PATCH-MAINT.	250.00	TON
504264	APPROACH GUTTERS	489.21	CUYD
601001	MOBILIZATION	1.00	L.S.
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	7,046.00	SQFT
604013	BARRICADES	128.00	LF
604023	TRAFFIC DRUMS	433.00	EACH
604031	FURN.&INSTL.PRCST.CONC.BARR.	4,019.00	LF
604036	RELO.PRECAST CONCRETE BARRIER	71,738.00	LF
604051	REMOVABLE CONST.PVMT.MRK.	945.00	LF
604061	REMOVAL OF PERM.PVMT.MRK.	700.00	LF
604071	ADVANCE WARNING ARROW PANEL	90.00	DAY
604078	PORT.CHANGEABLE MESSAGE SIGN	108.00	WEEK
604160	MOBILE SPEED NOTIFICATION SYSTEM SPECIAL	1.00	EACH
617005	GUARDRAIL (TYPE A)	29,550.00	LF
617105	TERMINAL ANCHOR POSTS (TYPE 1)	26.00	EACH
617312	GUARDRAIL TERMINAL (TYPE 2)	86.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	104.00	EACH
620001	LIME	66.00	TON
620011	SEEDING	32.93	ACRE
620022	MULCH COVER	65.86	ACRE
620030	WATER	4,030.70	MGAL
621001	TEMPORARY SEEDING	32.93	ACRE
621021	SILT FENCE	5,620.00	LF
621168	FILTER SOCK (12")	1,500.00	LF
621173	WATTLE (20")	954.00	LF
631054	CONC.BARR.WALL(PIER PROT.TYPE A)	190.00	LF
719505	ENHANCED THERMO. PVMT. MRK. WH (12")	700.00	LF

719602	ENHANCED THERMO. PVMT. MRK. YL (6")	245.00	LF
721002	RAISED PAVEMENT MARKERS-2	60.00	EACH
731071	TEMP. IMPACT ATTEN. BARR.	3.00	EACH
731072	TEMP. IMPACT ATTEN. BARRIER (REPAIR)	36.00	EACH
731075	TEMP. IMPACT ATTENUATION BARRIER (RELO)	106.00	EACH
804003	REINF.STEEL-ROADWAY (GR 60)	51,671.00	LB

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHIN EIGHT HUNDRED TEN (810) CALENDAR DAYS.

THE NUMBER OF TRAINEES REQUIRED FOR THIS PROJECT IS 2.