

ARKANSAS DEPARTMENT OF TRANSPORTATION

061950

CENTRAL OFFICE PARKING LOT RESURFACING (S)

STATE JOB

THE PURPOSE OF THIS PROJECT IS TO RESURFACE AND UPDATE PAVEMENT MARKING OF THE PARKING LOTS AT THE ARDOT CENTRAL OFFICE IN PULASKI COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL ITEM, ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: N/A

SECTIONS: N/A

COUNTY: PULASKI

LENGTH: NO PROJECT LENGTH.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202216	R&D OF CONCRETE STOPBLOCK	26.00	EACH
401011	TACK COAT	2,018.00	GAL
407161	MA IN ACHM SURFACE(3/8")	3,117.00	TON
407431	AB(PG64-22)ACHM SURF(3/8")	164.00	TON
412002	COLD MILLING ASPHALT PVMT.	36,706.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	100.00	TON
601001	MOBILIZATION	1.00	L.S.
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
719001	THERMO.PVMT.MARK.WH(4")	16,258.00	LF
719005	THERMO.PVMT.MARK.WH(12")	776.00	LF
719101	THERMO.PVMT.MARK.YL(4")	1,682.00	LF
719204	THERMO.PVMT.MARK.(WHLCHR)	23.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHIN FIFTY-SIX (56) CALENDAR DAYS.