

ARKANSAS DEPARTMENT OF TRANSPORTATION

110716

HWYS 185 & 318 STRS. & APPRS. (S)

FEDERAL AID PROJECT NHPP-0054(27)

THE PURPOSE OF THIS PROJECT IS TO REPLACE THREE STRUCTURES ON HIGHWAYS 185 AND 318 IN PHILLIPS COUNTY. THIS PROJECT CONSISTS OF CLEARING AND GRUBBING, REMOVAL AND DISPOSAL OF PIPE CULVERTS, STONE BACKFILL, EARTHWORK, AGGREGATE BASE COURSE, ACHM BINDER AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, MAINTENANCE OF TRAFFIC, MINOR DRAINAGE, EROSION CONTROL, PAVEMENT MARKING, CONSTRUCT THREE R.C. BOX CULVERTS (TOTAL LENGTH 128.50'), AND MISC ITEMS.

ROUTES: 185 & 318

SECTIONS: 1, 2 & 3

COUNTY: PHILLIPS

LENGTH: 0.195 mile in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

201011	CLEARING	11.00	STA
201111	GRUBBING	11.00	STA
202096	R&D OF PIPE CULVERTS	3.00	EACH
205011	REMOV.EXIST.BR.STR.(SITE 1)	1.00	L.S.
205012	REMOV.EXIST.BR.STR.(SITE 2)	1.00	L.S.
205013	REMOV.EXIST.BR.STR.(SITE 3)	1.00	L.S.
207011	STONE BACKFILL	2,256.00	TON
210213	UNCLASSIFIED EXCAVATION	11,520.00	CUYD
210611	COMPACTED EMBANKMENT	7,342.00	CUYD
210702	SOIL STABILIZATION	100.00	TON
303117	AGGR.BASE COURSE(CLASS 7)	2,632.00	TON
401011	TACK COAT	323.00	GAL
406161	M.A. IN ACHM BINDER(1")	404.00	TON
406412	A.B.(PG70-22)ACHM BINDER(1")	20.00	TON
407162	MA IN ACHM SURFACE(1/2")	750.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	49.00	TON
412002	COLD MILLING ASPHALT PVMT.	1,644.00	SQYD
601001	MOBILIZATION	1.00	L.S.
602011	FURNISHING FIELD OFFICE	1.00	EACH
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	235.00	SQFT
604013	BARRICADES	64.00	LF
606704	24" SIDE DRAIN	166.00	LF
606994	SELECTED PIPE BEDDING	20.00	CUYD
611008	4" PIPE UNDERDRAINS	500.00	LF
611013	UNDERDRAIN OUTLET PROTECTORS	2.00	EACH
616006	24" AUTOMATIC FLOODGATES	1.00	EACH
620001	LIME	9.00	TON
620011	SEEDING	4.34	ACRE
620022	MULCH COVER	10.69	ACRE
620030	WATER	573.90	MGAL
621001	TEMPORARY SEEDING	6.35	ACRE
621021	SILT FENCE	601.00	LF
621031	SAND BAG DITCH CHECKS	110.00	BAG

621071	SEDIMENT BASIN	133.00	CUYD
621101	OBLITERATION OF SEDIMENT BASIN	133.00	CUYD
621111	SEDIMENT REMOVAL & DISPOSAL	163.00	CUYD
621151	ROCK DITCH CHECKS	21.00	CUYD
623001	SECOND SEEDING APPLICATION	4.34	ACRE
624001	SOLID SODDING	139.00	SQYD
626003	EROSION CONTROL MATTING-3	916.00	SQYD
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
718002	REFL.PAINT PVMT.MRK.WH(6")	3,260.00	LF
718102	REFL.PAINT PVMT.MRK.YL(6")	3,260.00	LF
721002	RAISED PAVEMENT MARKERS-2	21.00	EACH
801101	UNCLASS.EXCAV.FOR STRS-RDWY.	412.00	CUYD
802012	CLASS S CONCRETE-ROADWAY	842.64	CUYD
804013	REINF.STEEL-BRIDGE (GR 60)	105,580.00	LB

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHIN FIVE HUNDRED EIGHTY (580) CALENDAR DAYS.