

ARKANSAS DEPARTMENT OF TRANSPORTATION

A00095

POINSETT CO. LINE – HWY. 158 (S)

FEDERAL AID PROJECT STPR-0016(105)

THE PURPOSE OF THIS PROJECT IS TO PLACE ULTRATHIN BONDED WEARING COURSE ON APPROXIMATELY 4.003 MILES OF HIGHWAY 135 IN CRAIGHEAD COUNTY. THIS PROJECT CONSISTS OF ACHM SURFACE COURSE, ULTRATHIN BONDED WEARING COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, RUMBLE STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 135

SECTIONS: 2

COUNTY: CRAIGHEAD

LENGTH: 4.003 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401011	TACK COAT	12,862.00	GAL
407161	MA IN ACHM SURFACE(3/8")	3,907.00	TON
407441	AB(PG70-22)ACHM SURF(3/8")	254.00	TON
407905	ULTRATHIN BONDED WEARING CRS (5/8"-TY B)	2,984.00	TON
412002	COLD MILLING ASPHALT PVMT.	1,293.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	20.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	594.00	SQFT
604041	CONST.PAVEMENT MARKINGS	85,114.00	LF
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642011	RUMBLE STRIPES IN ASPHALT SHOULDERS	38,338.00	LF
642102	CENTERLINE RUMBLE STRIPES IN ASPH. RDWYS	21,278.00	LF
718002	REFL.PAINT PVMT.MRK.WH(6")	42,557.00	LF
718004	REFL.PAINT PVMT.MRK.WH(10")	180.00	LF
718102	REFL.PAINT PVMT.MRK.YL(6")	42,557.00	LF
721002	RAISED PAVEMENT MARKERS-2	267.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.