

DESIGNED BY: S-303(3)  
DATE: 11/5/2 4 76

SUMMARY OF BRIDGE QUANTITIES JOB NO. 11512 (CODE X020)

ITEM NO.	ITEM	UNIT	BRIDGE NO. 3033				BRIDGE NO. 3034				BRIDGE NO. 3035				BRIDGE NO. 3036				TOTALS JOB NO. 11512
			BENTS 1-4	BENTS 2-3	SPANS 1-3	TOTALS	BENTS 1-6	BENTS 2-5	SPANS 1-5	TOTALS	BENTS 1-4	BENTS 2-3	SPANS 1-3	TOTALS	BENTS 1-5	BENTS 2-4	SPANS 1-4	TOTALS	
SP-1052-1	Excavation for Structures	Cu Yd	60			60	60			60	60			60	60			60	240
SP-1052-2	Precast Sub-Curb Units	Each			6	6			10	10			6	6			8	8	30
SP-1052-3	Precast Slab-Interior Units	Each			15	15			25	25			15	15			20	20	75
SP-1052-4	Clear S. Concrete for Bridges	Cu Yd	13.64	10.78		24.42	13.64	21.56		35.20	13.64	10.78		24.42	13.64	16.17		29.81	113.85
SP-1052-5	Reinforcing Steel	Lb.	1905	1660		3565	1905	3320		5225	1905	1660		3565	1905	2490		4395	16750
SP-1052-6	Concrete Piling (16" Octagonal)	Lin. Ft.	150	185		335	180	395		575	150	155		305	210	410		620	1835
SP-1052-7	Steel Plate Guard. (10Gq)	Lin. Ft.			119	119			195	195			119	119			157	157	590
SP-1052-8	Bridge Guard Plates (Type C)	Each	1			1	1			1	1			1	1			1	4
SP-1052-9	Removal of Existing Bridge Structures and Maintenance of Traffic.	Complets. Item.				23%				25%				18%				23%	89%*

\*For Remainder of Item SP-1052-9 see Roadway Quantities.

SUMMARY OF BRIDGE QUANTITIES  
HICKORY RIDGE - CHERRY VALLEY  
CROSS COUNTY  
ROUTE 42 SEC. 2  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARK.  
DRAWN BY: E. S. B. DATE: 11-22-55  
TRACED BY: DATE: 11-22-55  
CHECKED BY: J. H. DATE: 5-1-56  
SCALE: \_\_\_\_\_  
BRIDGE NO. \_\_\_\_\_  
DRAWING NO. 8916