

ARKANSAS DEPARTMENT OF TRANSPORTATION

A10059

HWY. 49 – HWY. 44 (S)

FEDERAL AID PROJECT STPR-0054(38)

THE PURPOSE OF THIS PROJECT IS TO PLACE CHIP SEAL AND FOG SEAL APPROXIMATELY 9.670 MILES OF HIGHWAY 85 IN PHILLIPS COUNTY. THIS PROJECT CONSISTS OF EARTHWORK, TRENCHING AND SHOULDER PREPARATION, AGGREGATE BASE COURSE, FOG SEAL, ASPHALT SURFACE TREATMENT, ACHM BINDER AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, APPROACH GUTTERS, MAINTENANCE OF TRAFFIC, GUARDRAIL, EROSION CONTROL, RUMBLE STRIPS AND STRIPES, LOOP WIRING, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 85

SECTIONS: 1

COUNTY: PHILLIPS

LENGTH: 9.67 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

210213	UNCLASSIFIED EXCAVATION	2.00	CUYD
215011	TRENCH.AND SHOULDER PREP.	482.00	STA
303117	AGGR.BASE COURSE(CLASS 7)	5,067.00	TON
401005	FOG SEAL (TYPE 2)	18,081.00	GAL
401011	TACK COAT	11,923.00	GAL
402111	MINERAL AGGR.IN A.S.T.(CL1)	2,782.00	TON
402202	POLY.MOD.CAT.EMULS.ASPH(CRS2P)	55,634.00	GAL
406161	M.A. IN ACHM BINDER(1")	7,610.00	TON
406412	A.B.(PG70-22)ACHM BINDER(1")	342.00	TON
407162	MA IN ACHM SURFACE(1/2")	6,341.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	376.00	TON
412002	COLD MILLING ASPHALT PVMT.	444.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	300.00	TON
504264	APPROACH GUTTERS	25.20	CUYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	1,008.00	SQFT
604023	TRAFFIC DRUMS	20.00	EACH
604041	CONST.PAVEMENT MARKINGS	180,150.00	LF
604061	REMOVAL OF PERM.PVMT.MRK.	522.00	LF
617005	GUARDRAIL (TYPE A)	325.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	4.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	4.00	EACH
620011	SEEDING	0.01	ACRE
620022	MULCH COVER	0.01	ACRE
620030	WATER	10.00	MGAL
621021	SILT FENCE	1,000.00	LF
621031	SAND BAG DITCH CHECKS	20.00	BAG
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642001	RUMBLE STRIPS IN ASPHALT SHOULDERS	2,585.00	LF
642011	RUMBLE STRIPES IN ASPHALT SHOULDERS	79,107.00	LF
701603	PORTABLE TRAFFIC SIGNAL SYSTEM-ACTUATED	6.00	WEEK
704036	LOOP WIRING CLASS III (1C/16 A.W.G.)	210.00	LF
719002	THERMO.PVMT.MARK.WH(6")	96,308.00	LF
719006	THERMO.PVMT.MARK.WH(24")	20.00	LF

719102	THERMO.PVMT.MARK.YL(6")	41,350.00	LF
719201	THERMO.PVMT.MARK.(WORD)	2.00	EACH
721002	RAISED PAVEMENT MARKERS-2	602.00	EACH
804003	REINF.STEEL-ROADWAY (GR 60)	2,892.00	LB

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.