

ARKANSAS DEPARTMENT OF TRANSPORTATION

A20044

HWY. 165 – HWY. 152 (S)

FEDERAL AID PROJECT STPR-0001(103)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 23.707 MILES OF HIGHWAY 130 IN ARKANSAS COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL OF GUARDRAIL, TRENCHING AND SHOULDER PREPARATION, AGGREGATE BASE COURSE, ACHM BINDER AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, APPROACH GUTTERS, MAINTENANCE OF TRAFFIC, GUARDRAIL, EROSION CONTROL, RUMBLE STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 130

SECTIONS: 6

COUNTY: ARKANSAS

LENGTH: 23.707 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202132	R&D OF GUARDRAIL	1,866.00	LF
215011	TRENCH.AND SHOULDER PREP.	1,196.00	STA
303117	AGGR.BASE COURSE(CLASS 7)	9,472.00	TON
401011	TACK COAT	33,076.00	GAL
406161	M.A. IN ACHM BINDER(1")	12,090.00	TON
406412	A.B.(PG70-22)ACHM BINDER(1")	610.00	TON
407162	MA IN ACHM SURFACE(1/2")	41,909.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	2,533.00	TON
412002	COLD MILLING ASPHALT PVMT.	8,446.00	SQYD
414011	ASPH.CONC.PATCH-MAINT.	625.00	TON
415011	ACHM PATCH.EXIST.RDWY.	800.00	TON
504264	APPROACH GUTTERS	48.54	CUYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	4,139.00	SQFT
604010	CONST PROJ INFO SIGN UPDATE	2.00	EACH
604023	TRAFFIC DRUMS	80.00	EACH
604041	CONST.PAVEMENT MARKINGS	413,168.00	LF
604051	REMOVABLE CONST.PVMT.MRK.	5,599.00	LF
604083	VERTICAL PANELS	80.00	EACH
617005	GUARDRAIL (TYPE A)	3,382.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	26.00	EACH
620001	LIME	23.00	TON
620011	SEEDING	11.50	ACRE
620022	MULCH COVER	23.00	ACRE
620030	WATER	1,407.60	MGAL
621001	TEMPORARY SEEDING	11.50	ACRE
621021	SILT FENCE	2,500.00	LF
621031	SAND BAG DITCH CHECKS	700.00	BAG
621111	SEDIMENT REMOVAL & DISPOSAL	93.00	CUYD
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642011	RUMBLE STRIPES IN ASPHALT SHOULDERS	179,022.00	LF
642102	CENTERLINE RUMBLE STRIPES IN ASPH. RDWYS	111,888.00	LF
701603	PORTABLE TRAFFIC SIGNAL SYSTEM-ACTUATED	21.00	WEEK

718004	REFL.PAINT PVMT.MRK.WH(10")	130.00	LF
718104	REFL.PAINT PVMT.MRK.YL(10")	202.00	LF
719002	THERMO.PVMT.MARK.WH(6")	251,328.00	LF
719006	THERMO.PVMT.MARK.WH(24")	110.00	LF
719102	THERMO.PVMT.MARK.YL(6")	161,840.00	LF
721002	RAISED PAVEMENT MARKERS-2	1,578.00	EACH
734011	BRIDGE END TERMINAL	2.00	EACH
804003	REINF.STEEL-ROADWAY (GR 60)	3,306.00	LB

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.

THE NUMBER OF TRAINEES REQUIRED FOR THIS PROJECT IS 1.