

ARKANSAS DEPARTMENT OF TRANSPORTATION

A30044

TEXAS STATE LINE – EAST (S)

FEDERAL AID PROJECT NHPP-0046(56)

THE PURPOSE OF THIS PROJECT IS TO PERFORM PATCHING AND RE-SEAL JOINTS ON APPROXIMATELY 1.111 MILES OF HIGHWAY 151 IN MILLER COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL OF CONCRETE PAVEMENT FOR PATCHING, CONTINUOUSLY REINFORCED CONCRETE PAVEMENT, PORTLAND CEMENT CONCRETE PAVEMENT PATCHING, JOINT REHABILITATION, MAINTENANCE OF TRAFFIC, RUMBLE STRIPS, CRACK ROUT AND SEAL, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 151

SECTIONS: 0

COUNTY: MILLER

LENGTH: 1.111 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

415011	ACHM PATCH.EXIST.RDWY.	100.00	TON
507002	R & D OF CONCRETE PAVEMENT FOR PATCHING	562.00	SQYD
507013	R&D C.R.CONC.PVMT.FOR PATCH	1,524.00	SQYD
507232	P.C.C.P. PATCH-12"	562.00	SQYD
507310	CONT. R.C. PAVEMENT PATCHING (12" U.T.)	1,524.00	SQYD
509001	JOINT REHAB. (TYPE A)	1,192.00	LF
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	1,209.00	SQFT
604023	TRAFFIC DRUMS	300.00	EACH
604041	CONST.PAVEMENT MARKINGS	4,262.00	LF
604071	ADVANCE WARNING ARROW PANEL	48.00	DAY
604078	PORT.CHANGEABLE MESSAGE SIGN	8.00	WEEK
604160	MOBILE SPEED NOTIFICATION SYSTEM SPECIAL	1.00	EACH
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642002	RUMBLE STRIPS IN P.C.C.SHOULDERS	84.00	LF
719502	ENHANCED THERMO. PVMT. MRK. WH (6")	18,902.00	LF
719505	ENHANCED THERMO. PVMT. MRK. WH (12")	2,602.00	LF
719602	ENHANCED THERMO. PVMT. MRK. YL (6")	17,268.00	LF
721002	RAISED PAVEMENT MARKERS-2	499.00	EACH
802012	CLASS S CONCRETE-ROADWAY	9.34	CUYD
804003	REINF.STEEL-ROADWAY (GR 60)	210.00	LB
916027	CRACK ROUT AND SEAL	26,496.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.