

ARKANSAS DEPARTMENT OF TRANSPORTATION

A30046

TEXARKANA VISITOR CENTER – EAST (PVM.T. REPAIRS) (S)

FEDERAL AID PROJECT NHPP-30-11(1)

THE PURPOSE OF THIS PROJECT IS TO DO A CONCRETE PAVEMENT REPAIR ON INTERSTATE 30 IN MILLER COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL OF CONCRETE PAVEMENT FOR PATCHING, MAINTENANCE OF TRAFFIC, RAISED PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: I-30

SECTIONS: 11

COUNTY: MILLER

LENGTH: 4.20 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

507002	R & D OF CONCRETE PAVEMENT FOR PATCHING	1,550.00	SQYD
507234	P.C.C.P. PATCH-14"	1,550.00	SQYD
509001	JOINT REHAB. (TYPE A)	3,500.00	LF
509002	JOINT REHAB. (TYPE B)	6,500.00	LF
601001	MOBILIZATION	1.00	L.S.
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	732.00	SQFT
604023	TRAFFIC DRUMS	437.00	EACH
604071	ADVANCE WARNING ARROW PANEL	86.00	DAY
604078	PORT.CHANGEABLE MESSAGE SIGN	15.00	WEEK
604160	MOBILE SPEED NOTIFICATION SYSTEM SPECIAL	1.00	EACH
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
719502	ENHANCED THERMO. PVM.T. MRK. WH (6")	900.00	LF
719602	ENHANCED THERMO. PVM.T. MRK. YL (6")	60.00	LF
721002	RAISED PAVEMENT MARKERS-2	4.00	EACH

THIS PROPOSAL CONTAINS THE JOB SPECIAL PROVISION "SITE USE (A+C METHOD)-CALENDAR DAY CONTRACT" FOR BIDDING IN WHICH THE BIDDER WILL DETERMINE THE NUMBER OF CALENDAR DAYS TO COMPLETE THE PROJECT.