

ARKANSAS DEPARTMENT OF TRANSPORTATION

A30049

HWY. 355 – HWY. 278 (S)

FEDERAL AID PROJECT STPR-2931(5)

THE PURPOSE OF THIS PROJECT IS TO MILL AND OVERLAY APPROXIMATELY 18.474 MILES OF HIGHWAY 73 IN HEMPSTEAD AND HOWARD COUNTIES. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL OF GUARDRAIL, AGGREGATE BASE COURSE, ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, GUARDRAIL, EROSION CONTROL, RUMBLE STRIPS, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 73

SECTIONS: 0, 1, & 2

COUNTY: HEMPSTEAD & HOWARD

LENGTH: 18.474 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202132	R&D OF GUARDRAIL	1,736.00	LF
303117	AGGR.BASE COURSE(CLASS 7)	2,380.00	TON
401011	TACK COAT	45,382.00	GAL
407162	MA IN ACHM SURFACE(1/2")	40,816.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	2,467.00	TON
412002	COLD MILLING ASPHALT PVMT.	287,386.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	300.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	2,189.00	SQFT
604023	TRAFFIC DRUMS	46.00	EACH
604041	CONST.PAVEMENT MARKINGS	482,297.00	LF
617005	GUARDRAIL (TYPE A)	1,600.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	16.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	8.00	EACH
621021	SILT FENCE	3,600.00	LF
621111	SEDIMENT REMOVAL & DISPOSAL	133.00	CUYD
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642001	RUMBLE STRIPS IN ASPHALT SHOULDERS	187,969.00	LF
701603	PORTABLE TRAFFIC SIGNAL SYSTEM-ACTUATED	8.00	WEEK
718002	REFL.PAINT PVMT.MRK.WH(6")	195,487.00	LF
718102	REFL.PAINT PVMT.MRK.YL(6")	195,487.00	LF
721002	RAISED PAVEMENT MARKERS-2	1,225.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.