

ARKANSAS DEPARTMENT OF TRANSPORTATION

A40052

I-49 – SCHOOL AVE. (FAYETTEVILLE) (S)

FEDERAL AID PROJECT NHPP-9142(59)

THE PURPOSE OF THIS PROJECT IS TO MILL AND OVERLAY APPROXIMATELY 1.513 MILES OF HIGHWAY 180 IN WASHINGTON COUNTY. THIS PROJECT CONSISTS OF ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 180

SECTIONS: 0

COUNTY: WASHINGTON

LENGTH: 1.513 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401011	TACK COAT	10,416.00	GAL
407162	MA IN ACHM SURFACE(1/2")	6,059.00	TON
407452	AB(PG76-22)ACHM SURF(1/2")	387.00	TON
412002	COLD MILLING ASPHALT PVMT.	49,505.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	500.00	TON
601001	MOBILIZATION	1.00	L.S.
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	892.00	SQFT
604023	TRAFFIC DRUMS	100.00	EACH
604041	CONST.PAVEMENT MARKINGS	26,000.00	LF
604045	CONST.PAVEMENT MARKINGS (WORD)	8.00	EACH
604046	CONST.PAVEMENT MARKINGS (ARROW)	10.00	EACH
604051	REMOVABLE CONST.PVMT.MRK.	2,160.00	LF
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
719002	THERMO.PVMT.MARK.WH(6")	4,980.00	LF
719006	THERMO.PVMT.MARK.WH(24")	540.00	LF
719102	THERMO.PVMT.MARK.YL(6")	19,540.00	LF
719201	THERMO.PVMT.MARK.(WORD)	8.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	10.00	EACH
721002	RAISED PAVEMENT MARKERS-2	890.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.