

ARKANSAS DEPARTMENT OF TRANSPORTATION

A50052

STONE CO. LINE – HWY. 25 (S)

FEDERAL AID PROJECT STPR-0032(45)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 5.996 MILES OF HIGHWAY 14 IN INDEPENDENCE COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL OF CONCRETE ISLANDS, AGGREGATE BASE COURSE, ACHM BINDER AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 14

SECTIONS: 8

COUNTY: INDEPENDENCE

LENGTH: 5.996 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202047	R&D OF CONCRETE ISLANDS	630.00	SQYD
303117	AGGR.BASE COURSE(CLASS 7)	2,944.00	TON
401011	TACK COAT	12,222.00	GAL
406161	M.A. IN ACHM BINDER(1")	227.00	TON
406412	A.B.(PG70-22)ACHM BINDER(1")	11.00	TON
407161	MA IN ACHM SURFACE(3/8")	12,870.00	TON
407441	AB(PG70-22)ACHM SURF(3/8")	822.00	TON
412002	COLD MILLING ASPHALT PVMT.	17,793.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	250.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	456.00	SQFT
604041	CONST.PAVEMENT MARKINGS	63,318.00	LF
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
719002	THERMO.PVMT.MARK.WH(6")	63,912.00	LF
719005	THERMO.PVMT.MARK.WH(12")	535.00	LF
719006	THERMO.PVMT.MARK.WH(24")	15.00	LF
719102	THERMO.PVMT.MARK.YL(6")	63,318.00	LF
719200	THERMO.PVMT.MARK.(YIELD LINE)	30.00	LF
719201	THERMO.PVMT.MARK.(WORD)	2.00	EACH
721002	RAISED PAVEMENT MARKERS-2	441.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.