

ARKANSAS DEPARTMENT OF TRANSPORTATION

A60058

I-30 – GRANT CO. LINE (S)

FEDERAL AID PROJECT NHPP-0030(36)

THE PURPOSE OF THIS PROJECT IS TO MILL, OVERLAY, AND PLACE ULTRATHIN BONDED WEARING COURSE ON APPROXIMATELY 10.115 MILES OF HIGHWAY 270 IN HOT SPRING COUNTY. THIS PROJECT CONSISTS OF AGGREGATE BASE COURSE, ACHM SURFACE COURSE, ULTRATHIN BONDED WEARING COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, RUMBLE STRIPS, LOOP WIRING, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 270

SECTIONS: 8

COUNTY: HOT SPRING

LENGTH: 10.115 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303117	AGGR.BASE COURSE(CLASS 7)	728.00	TON
401011	TACK COAT	34,949.00	GAL
407162	MA IN ACHM SURFACE(1/2")	18,839.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	1,160.00	TON
407905	ULTRATHIN BONDED WEARING CRS (5/8"-TY B)	2,083.00	TON
412002	COLD MILLING ASPHALT PVMT.	154,004.00	SQYD
414011	ASPH.CONC.PATCH-MAINT.	255.00	TON
415011	ACHM PATCH.EXIST.RDWY.	200.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	728.00	SQFT
604041	CONST.PAVEMENT MARKINGS	218,236.00	LF
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642001	RUMBLE STRIPS IN ASPHALT SHOULDERS	65,894.00	LF
704036	LOOP WIRING CLASS III (1C/16 A.W.G.)	1,856.00	LF
719002	THERMO.PVMT.MARK.WH(6")	108,818.00	LF
719003	THERMO.PVMT.MARK.WH(8")	568.00	LF
719006	THERMO.PVMT.MARK.WH(24")	213.00	LF
719102	THERMO.PVMT.MARK.YL(6")	109,418.00	LF
719201	THERMO.PVMT.MARK.(WORD)	5.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	5.00	EACH
721002	RAISED PAVEMENT MARKERS-2	729.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.