

ARKANSAS DEPARTMENT OF TRANSPORTATION

A60063

HWY. 7 IMPVTS. (HOT SPRINGS) (S)

FEDERAL AID PROJECT STPSC-9210(62)

THE PURPOSE OF THIS PROJECT IS TO MILL AND OVERLAY APPROXIMATELY 5.876 MILES OF HIGHWAY 7 IN GARLAND COUNTY. THIS PROJECT CONSISTS OF ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, LOOP WIRING, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 7

SECTIONS: 9

COUNTY: GARLAND

LENGTH: 5.876 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401011	TACK COAT	35,050.00	GAL
407162	MA IN ACHM SURFACE(1/2")	21,207.00	TON
407452	AB(PG76-22)ACHM SURF(1/2")	1,282.00	TON
412002	COLD MILLING ASPHALT PVMT.	204,446.00	SQYD
414011	ASPH.CONC.PATCH-MAINT.	147.00	TON
415011	ACHM PATCH.EXIST.RDWY.	500.00	TON
601001	MOBILIZATION	1.00	L.S.
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	1,567.00	SQFT
604041	CONST.PAVEMENT MARKINGS	106,738.00	LF
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
641500	SURFACE-APPLIED DETECT. WARNING PANELS	2,120.00	SQFT
704036	LOOP WIRING CLASS III (1C/16 A.W.G.)	25,421.00	LF
704041	FEEDER WIRE	14,925.00	LF
710004	NON-METALLIC CONDUIT (2")	1,470.00	LF
711116	CONCRETE PULL BOX (TYPE 1 HD)	19.00	EACH
719002	THERMO.PVMT.MARK.WH(6")	38,108.00	LF
719003	THERMO.PVMT.MARK.WH(8")	1,156.00	LF
719006	THERMO.PVMT.MARK.WH(24")	4,224.00	LF
719102	THERMO.PVMT.MARK.YL(6")	68,630.00	LF
719201	THERMO.PVMT.MARK.(WORD)	42.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	51.00	EACH
719203	THERMO.PVMT.MARK.(RR EMB.)	4.00	EACH
721002	RAISED PAVEMENT MARKERS-2	1,613.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.