

ARKANSAS DEPARTMENT OF TRANSPORTATION

A70042

HWY. 275 – FORDYCE (S)

FEDERAL AID PROJECT STPR-0720(1)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY AND PLACE ULTRATHIN BONDED WEARING COURSE ON APPROXIMATELY 13.680 MILES OF HIGHWAY 274 IN CALHOUN AND DALLAS COUNTIES. THIS PROJECT CONSISTS OF AGGREGATE BASE COURSE, ACHM SURFACE COURSE, ULTRATHIN BONDED WEARING COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, APPROACH GUTTERS, MAINTENANCE OF TRAFFIC, GUARDRAIL, RUMBLE STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 274  
SECTIONS: 3 & 4

COUNTY: CALHOUN & DALLAS  
LENGTH: 13.68 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303117	AGGR.BASE COURSE(CLASS 7)	1,040.00	TON
401011	TACK COAT	24,762.00	GAL
407161	MA IN ACHM SURFACE(3/8")	19,320.00	TON
407431	AB(PG64-22)ACHM SURF(3/8")	16.00	TON
407441	AB(PG70-22)ACHM SURF(3/8")	1,327.00	TON
407905	ULTRATHIN BONDED WEARING CRS (5/8"-TY B)	5,672.00	TON
412002	COLD MILLING ASPHALT PVMT.	26,667.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	332.00	TON
504264	APPROACH GUTTERS	33.44	CUYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	1,004.00	SQFT
604023	TRAFFIC DRUMS	135.00	EACH
604041	CONST.PAVEMENT MARKINGS	292,212.00	LF
617005	GUARDRAIL (TYPE A)	1,800.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	16.00	EACH
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642011	RUMBLE STRIPES IN ASPHALT SHOULDERS	135,664.00	LF
642102	CENTERLINE RUMBLE STRIPES IN ASPH. RDWYS	67,832.00	LF
701603	PORTABLE TRAFFIC SIGNAL SYSTEM-ACTUATED	10.00	WEEK
718002	REFL.PAINT PVMT.MRK.WH(6")	145,604.00	LF
718102	REFL.PAINT PVMT.MRK.YL(6")	146,608.00	LF
718203	REFL.PAINT PVMT.MRK.(RR EMB.)	3.00	EACH
721002	RAISED PAVEMENT MARKERS-2	924.00	EACH
804003	REINF.STEEL-ROADWAY (GR 60)	2,368.00	LB

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.