

ARKANSAS DEPARTMENT OF TRANSPORTATION

A70049

OUACHITA RIVER – NORTH (S)

FEDERAL AID PROJECT NHPP-0007(37)

THE PURPOSE OF THIS PROJECT IS TO MILL AND OVERLAY APPROXIMATELY 3.373 MILES OF HIGHWAY 167 IN CALHOUN COUNTY. THIS PROJECT CONSISTS OF FOG SEAL, ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, MAINTENANCE OF TRAFFIC, RUMBLE STRIPS AND STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 167

SECTIONS: 3

COUNTY: CALHOUN

LENGTH: 3.373 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401005	FOG SEAL (TYPE 2)	4,454.00	GAL
401011	TACK COAT	9,699.00	GAL
407162	MA IN ACHM SURFACE(1/2")	10,061.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	608.00	TON
412002	COLD MILLING ASPHALT PVMT.	96,991.00	SQYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	231.00	SQFT
604041	CONST.PAVEMENT MARKINGS	166,000.00	LF
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642001	RUMBLE STRIPS IN ASPHALT SHOULDERS	35,629.00	LF
642102	CENTERLINE RUMBLE STRIPES IN ASPH. RDWYS	17,814.00	LF
719002	THERMO.PVMT.MARK.WH(6")	46,032.00	LF
719102	THERMO.PVMT.MARK.YL(6")	36,818.00	LF
721002	RAISED PAVEMENT MARKERS-2	690.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.