

ARKANSAS DEPARTMENT OF TRANSPORTATION

A70050

HWY. 67 – HWY. 51 (S)

FEDERAL AID PROJECT STPR-0010(67)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 12.433 MILES OF HIGHWAY 182 IN CLARK COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL OF GUARDRAIL, TRENCHING AND SHOULDER PREPARATION, ACHM BINDER AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, GUARDRAIL, EROSION CONTROL, RUMBLE STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 182

SECTIONS: 0

COUNTY: CLARK

LENGTH: 12.433 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202132	R&D OF GUARDRAIL	312.00	LF
215011	TRENCH.AND SHOULDER PREP.	655.00	STA
303117	AGGR.BASE COURSE(CLASS 7)	2,626.00	TON
401011	TACK COAT	37,282.00	GAL
406161	M.A. IN ACHM BINDER(1")	6,117.00	TON
406412	A.B.(PG70-22)ACHM BINDER(1")	302.00	TON
407162	MA IN ACHM SURFACE(1/2")	29,884.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	1,806.00	TON
412002	COLD MILLING ASPHALT PVMT.	1,161.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	100.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	927.00	SQFT
604041	CONST.PAVEMENT MARKINGS	256,941.00	LF
604083	VERTICAL PANELS	106.00	EACH
611008	4" PIPE UNDERDRAINS	16,000.00	LF
611013	UNDERDRAIN OUTLET PROTECTORS	66.00	EACH
617005	GUARDRAIL (TYPE A)	375.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	4.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	4.00	EACH
621031	SAND BAG DITCH CHECKS	200.00	BAG
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
637001	MAILBOXES	26.00	EACH
637017	MAILBOX SUPPORTS (SINGLE)	26.00	EACH
642011	RUMBLE STRIPES IN ASPHALT SHOULDERS	100,650.00	LF
719002	THERMO.PVMT.MARK.WH(6")	131,504.00	LF
719102	THERMO.PVMT.MARK.YL(6")	115,437.00	LF
721002	RAISED PAVEMENT MARKERS-2	822.00	EACH
726002	STANDARD SIGN	123.00	SQFT
729003	CHANNEL POST SIGN SUPPORT-C	25.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.