

ARKANSAS DEPARTMENT OF TRANSPORTATION

A90050

MISSOURI STATE LINE – HWY. 62 (S)

FEDERAL AID PROJECT STPR-HRRR-0003(59)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 10.552 MILES OF HIGHWAY 101 IN BAXTER COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL ITEMS, EARTHWORK, TRENCHING AND SHOULDER PREPARATION, AGGREGATE BASE COURSE, ACHM BINDER AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, APPROACH GUTTERS, MAINTENANCE OF TRAFFIC, MINOR DRAINAGE STRUCTURES, GUARDRAIL, EROSION CONTROL, MUMBLE STRIPS AND STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 101

SECTIONS: 1

COUNTY: BAXTER

LENGTH: 10.552 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

|        |                                 |            |      |
|--------|---------------------------------|------------|------|
| 202049 | R&D OF PIPE CULVERTS            | 735.00     | LF   |
| 202093 | R&D OF DROP INLETS              | 1.00       | EACH |
| 202097 | R&D OF BOX CULVERTS             | 3.00       | EACH |
| 202132 | R&D OF GUARDRAIL                | 750.00     | LF   |
| 210213 | UNCLASSIFIED EXCAVATION         | 15.00      | CUYD |
| 210611 | COMPACTED EMBANKMENT            | 60.00      | CUYD |
| 215011 | TRENCH.AND SHOULDER PREP.       | 471.00     | STA  |
| 303117 | AGGR.BASE COURSE(CLASS 7)       | 692.00     | TON  |
| 401011 | TACK COAT                       | 29,357.00  | GAL  |
| 406161 | M.A. IN ACHM BINDER(1")         | 3,302.00   | TON  |
| 406412 | A.B.(PG70-22)ACHM BINDER(1")    | 152.00     | TON  |
| 407161 | MA IN ACHM SURFACE(3/8")        | 19,797.00  | TON  |
| 407441 | AB(PG70-22)ACHM SURF(3/8")      | 1,286.00   | TON  |
| 412002 | COLD MILLING ASPHALT PVMT.      | 1,701.00   | SQYD |
| 415011 | ACHM PATCH.EXIST.RDWY.          | 160.00     | TON  |
| 504264 | APPROACH GUTTERS                | 88.92      | CUYD |
| 601001 | MOBILIZATION                    | 1.00       | L.S. |
| 603009 | MAINTENANCE OF TRAFFIC          | 1.00       | L.S. |
| 604003 | SIGNS                           | 1,149.00   | SQFT |
| 604023 | TRAFFIC DRUMS                   | 202.00     | EACH |
| 604041 | CONST.PAVEMENT MARKINGS         | 475,922.00 | LF   |
| 604045 | CONST.PAVEMENT MARKINGS (WORD)  | 2.00       | EACH |
| 604046 | CONST.PAVEMENT MARKINGS (ARROW) | 2.00       | EACH |
| 604049 | TUBULAR MARKERS                 | 11.00      | EACH |
| 604055 | REMOVAL OF CONST.PVMT.MRK.      | 7,054.00   | LF   |
| 604061 | REMOVAL OF PERM.PVMT.MRK.       | 14,108.00  | LF   |
| 605609 | 24" R.C.PIPE CULVERTS(CL.5)     | 872.00     | LF   |
| 605858 | 24" FES R.C.PIPE CLVT.          | 41.00      | EACH |
| 609015 | DROP INLETS (TYPE E)            | 1.00       | EACH |
| 615020 | PVMT.REPAIR O/CLVT.(CONCRETE)   | 138.60     | CUYD |
| 617005 | GUARDRAIL (TYPE A)              | 450.00     | LF   |
| 617312 | GUARDRAIL TERMINAL (TYPE 2)     | 4.00       | EACH |
| 617332 | THRIE BEAM GUARDRAIL TERMINAL   | 4.00       | EACH |
| 620001 | LIME                            | 2.00       | TON  |

|        |                                         |            |      |
|--------|-----------------------------------------|------------|------|
| 620011 | SEEDING                                 | 1.08       | ACRE |
| 620022 | MULCH COVER                             | 1.86       | ACRE |
| 620030 | WATER                                   | 130.30     | MGAL |
| 621001 | TEMPORARY SEEDING                       | 0.78       | ACRE |
| 621021 | SILT FENCE                              | 2,350.00   | LF   |
| 621173 | WATTLE (20")                            | 2,250.00   | LF   |
| 623001 | SECOND SEEDING APPLICATION              | 1.08       | ACRE |
| 624001 | SOLID SODDING                           | 328.00     | SQYD |
| 635011 | ROADWAY CONSTRUCTION CONTROL            | 1.00       | L.S. |
| 637001 | MAILBOXES                               | 62.00      | EACH |
| 637017 | MAILBOX SUPPORTS (SINGLE)               | 62.00      | EACH |
| 642301 | MUMBLE STRIPS IN ASPHALT SHOULDERS      | 8,382.00   | LF   |
| 642311 | MUMBLE STRIPES IN ASPHALT SHOULDERS     | 36,562.00  | LF   |
| 642402 | C.L. MUMBLE STRIPES IN ASPHALT ROADWAYS | 28,090.00  | LF   |
| 701603 | PORTABLE TRAFFIC SIGNAL SYSTEM-ACTUATED | 4.00       | WEEK |
| 719002 | THERMO.PVMT.MARK.WH(6")                 | 117,112.00 | LF   |
| 719005 | THERMO.PVMT.MARK.WH(12")                | 200.00     | LF   |
| 719102 | THERMO.PVMT.MARK.YL(6")                 | 117,322.00 | LF   |
| 719200 | THERMO.PVMT.MARK.(YIELD LINE)           | 18.00      | LF   |
| 719201 | THERMO.PVMT.MARK.(WORD)                 | 2.00       | EACH |
| 719202 | THERMO.PVMT.MARK.(ARROW)                | 2.00       | EACH |
| 721002 | RAISED PAVEMENT MARKERS-2               | 740.00     | EACH |
| 726002 | STANDARD SIGN                           | 14.00      | SQFT |
| 730499 | OMNI-DIR.BRKAWAY SIGN SUPPORT-TYPE G-1  | 1.00       | EACH |
| 804003 | REINF.STEEL-ROADWAY (GR 60)             | 7,960.00   | LB   |

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.