

ARKANSAS DEPARTMENT OF TRANSPORTATION

A90051

HWY. 412 IMPVTS. (CARROLL & MADISON COS.) (S)

FEDERAL AID PROJECT NHPP-0844(5)

THE PURPOSE OF THIS PROJECT IS TO MILL AND OVERLAY APPROXIMATELY 11.203 MILES OF HIGHWAY 412 IN CARROLL AND MADISON COUNTIES. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL OF GUARDRAIL, ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, GUARDRAIL, RUMBLE STRIPS AND STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 412

SECTIONS: 3, 4, & 5

COUNTY: CARROLL & MADISON

LENGTH: 11.203 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202132	R&D OF GUARDRAIL	3,000.00	LF
401011	TACK COAT	29,885.00	GAL
407162	MA IN ACHM SURFACE(1/2")	31,032.00	TON
407452	AB(PG76-22)ACHM SURF(1/2")	1,841.00	TON
412002	COLD MILLING ASPHALT PVMT.	297,066.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	300.00	TON
601001	MOBILIZATION	1.00	L.S.
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	1,707.00	SQFT
604041	CONST.PAVEMENT MARKINGS	269,915.00	LF
617005	GUARDRAIL (TYPE A)	2,200.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	14.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	4.00	EACH
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642001	RUMBLE STRIPS IN ASPHALT SHOULDERS	61,289.00	LF
642011	RUMBLE STRIPES IN ASPHALT SHOULDERS	39,811.00	LF
642102	CENTERLINE RUMBLE STRIPES IN ASPH. RDWYS	50,550.00	LF
719002	THERMO.PVMT.MARK.WH(6")	132,510.00	LF
719005	THERMO.PVMT.MARK.WH(12")	2,895.00	LF
719102	THERMO.PVMT.MARK.YL(6")	125,065.00	LF
719201	THERMO.PVMT.MARK.(WORD)	4.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	8.00	EACH
721002	RAISED PAVEMENT MARKERS-2	1,115.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.