

ARKANSAS DEPARTMENT OF TRANSPORTATION

BR2814

JOHNSON CREEK STR. & APPRS. (S)

FEDERAL AID PROJECT BFPO-STPB-0028(61)

THE PURPOSE OF THIS PROJECT IS TO REPLACE 1 BRIDGE AND RECONSTRUCT APPROXIMATELY 0.123 MILE OF COUNTY ROAD 49 IN GREENE COUNTY. THIS PROJECT CONSISTS OF CLEARING AND GRUBBING, REMOVAL AND DISPOSAL OF ITEMS, EARTHWORK, AGGREGATE BASE COURSE, ACHM BINDER AND SURFACE COURSES, MAINTENANCE OF TRAFFIC, MINOR DRAINAGE STRUCTURES, EROSION CONTROL ITEMS, ONE QUADRUPLE R.C. BOX CULVERT (TOTAL SPAN 51.83'), AND MISC. ITEMS

ROUTES: CR 49

COUNTY: GREENE

LENGTH: 0.123 mile in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

201011	CLEARING	4.00	STA
201111	GRUBBING	7.00	STA
202096	R&D OF PIPE CULVERTS	3.00	EACH
202191	R&D OF SIGNS	2.00	EACH
205011	REMV.EXIST.BR.STR.(SITE 1)	1.00	L.S.
210213	UNCLASSIFIED EXCAVATION	9,417.00	CUYD
210611	COMPACTED EMBANKMENT	3,072.00	CUYD
303117	AGGR.BASE COURSE(CLASS 7)	968.00	TON
401011	TACK COAT	211.00	GAL
406161	M.A. IN ACHM BINDER(1")	367.00	TON
406402	A.B.(PG64-22)ACHM BINDER(1")	18.00	TON
407162	MA IN ACHM SURFACE(1/2")	182.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	11.00	TON
412002	COLD MILLING ASPHALT PVMT.	222.00	SQYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	168.00	SQFT
604013	BARRICADES	32.00	LF
604023	TRAFFIC DRUMS	25.00	EACH
606703	18" SIDE DRAIN	135.00	LF
606704	24" SIDE DRAIN	65.00	LF
611008	4" PIPE UNDERDRAINS	200.00	LF
611013	UNDERDRAIN OUTLET PROTECTORS	4.00	EACH
620001	LIME	3.00	TON
620011	SEEDING	1.42	ACRE
620022	MULCH COVER	2.84	ACRE
620030	WATER	174.60	MGAL
621001	TEMPORARY SEEDING	1.42	ACRE
621021	SILT FENCE	100.00	LF
621031	SAND BAG DITCH CHECKS	198.00	BAG
621071	SEDIMENT BASIN	444.00	CUYD
621101	OBLITERATION OF SEDIMENT BASIN	444.00	CUYD
621111	SEDIMENT REMOVAL & DISPOSAL	512.80	CUYD
621151	ROCK DITCH CHECKS	27.00	CUYD
621169	FILTER SOCK (18")	280.00	LF
624001	SOLID SODDING	61.00	SQYD

635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
718101	REFL.PAINT PVMT.MRK.YL(4")	1,300.00	LF
726002	STANDARD SIGN	12.00	SQFT
729003	CHANNEL POST SIGN SUPPORT-C	4.00	EACH
801101	UNCLASS.EXCAV.FOR STRS-RDWY.	160.00	CUYD
802012	CLASS S CONCRETE-ROADWAY	493.21	CUYD
804003	REINF.STEEL-ROADWAY (GR 60)	61,845.00	LB
816003	FILTER BLANKET	65.00	SQYD
816111	DUMPED RIPRAP	33.00	CUYD

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE December 21, 2026.