

ARKANSAS DEPARTMENT OF TRANSPORTATION

C22005

GROCE CREEK STR. & APPRS. (WILMAR) (S)

STATE AID CITY JOB (CODE 9971)

THE PURPOSE OF THIS PROJECT IS TO REPLACE ONE BRIDGE STRUCTURE AND CONSTRUCT APPROACHES ON 0.043 MILE OF 7TH STREET IN WILMAR IN DREW COUNTY. THIS PROJECT CONSISTS OF CLEARING AND GRUBBING, EARTHWORK, AGGREGATE BASE COURSE, ACHM SURFACE COURSE, MAINTENANCE OF TRAFFIC, EROSION CONTROL ITEMS, PAVEMENT MARKING, ONE TRIPLE R.C. BOX CULVERT (TOTAL SPAN 35.33'), AND MISC. ITEMS.

ROUTES: 7TH ST.

COUNTY: DREW

LENGTH: 0.043 mile in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

201012	CLEARING	3.00	STA
201111	GRUBBING	3.00	STA
202132	R&D OF GUARDRAIL	78.00	LF
202191	R&D OF SIGNS	6.00	EACH
205011	REMV.EXIST.BR.STR.(SITE 1)	1.00	L.S.
210210	UNCLASSIFIED EXCAVATION	1,898.00	CUYD
210601	COMPACTED EMBANKMENT	89.00	CUYD
303107	AGGR.BASE COURSE(CLASS 7)	214.00	TON
401011	TACK COAT	50.00	GAL
407162	MA IN ACHM SURFACE(1/2")	149.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	9.00	TON
412001	COLD MILLING ASPHALT PVMT.	311.00	SQYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	337.00	SQFT
604013	BARRICADES	32.00	LF
605002	CONC.DITCH PAVING(TYPE B)	89.00	SQYD
611008	4" PIPE UNDERDRAINS	200.00	LF
611013	UNDERDRAIN OUTLET PROTECTORS	4.00	EACH
620001	LIME	1.00	TON
620011	SEEDING	0.42	ACRE
620022	MULCH COVER	0.84	ACRE
620030	WATER	52.90	MGAL
621001	TEMPORARY SEEDING	0.42	ACRE
621021	SILT FENCE	375.00	LF
621031	SAND BAG DITCH CHECKS	132.00	BAG
621111	SEDIMENT REMOVAL & DISPOSAL	32.00	CUYD
621151	ROCK DITCH CHECKS	36.00	CUYD
621169	FILTER SOCK (18")	1,600.00	LF
623001	SECOND SEEDING APPLICATION	0.42	ACRE
624001	SOLID SODDING	120.00	SQYD
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
718001	REFL.PAINT PVMT.MRK.WH(4")	450.00	LF
718101	REFL.PAINT PVMT.MRK.YL(4")	285.00	LF
726002	STANDARD SIGN	12.00	SQFT
729003	CHANNEL POST SIGN SUPPORT-C	4.00	EACH
801101	UNCLASS.EXCAV.FOR STRS-RDWY.	79.00	CUYD

802012	CLASS S CONCRETE-ROADWAY	179.29	CUYD
804003	REINF.STEEL-ROADWAY (GR 60)	25,825.00	LB

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHIN TWO HUNDRED SEVENTEEN (217) CALENDAR DAYS.