

ARKANSAS DEPARTMENT OF TRANSPORTATION

C73017

COMMUNITY DR. PHASE 2 (BEEBE) (S)

STATE AID CITY JOB (CODE 9971)

THE PURPOSE OF THIS PROJECT IS TO CONSTRUCT 0.331 MILE OF CITY STREET IN WHITE COUNTY. THIS PROJECT CONSISTS OF CLEARING AND GRUBBING, REMOVAL AND DISPOSAL OF ITEMS, EARTH WORK, AGGREGATE BASE COURSE, ACHM SURFACE COURSE, MAINTENANCE OF TRAFFIC, MINOR DRAINAGE STRUCTURES, EROSION CONTROL ITEMS, AND MISC. ITEMS.

ROUTES: VARIOUS

COUNTY: WHITE

LENGTH: 0.331 mile in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

201011	CLEARING	1.00	STA
201111	GRUBBING	18.00	STA
202003	R&D OF CURB AND GUTTER	95.00	LF
210210	UNCLASSIFIED EXCAVATION	2,192.00	CUYD
210601	COMPACTED EMBANKMENT	2,103.00	CUYD
210702	SOIL STABILIZATION	285.00	TON
303107	AGGR.BASE COURSE(CLASS 7)	4,143.00	TON
401001	PRIME COAT	2,650.00	GAL
401011	TACK COAT	7.00	GAL
407162	MA IN ACHM SURFACE(1/2")	748.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	47.00	TON
412001	COLD MILLING ASPHALT PVMT.	205.00	SQYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	43.00	SQFT
604013	BARRICADES	48.00	LF
604023	TRAFFIC DRUMS	25.00	EACH
605766	22" X 14" R.C.ARCH PIPE CLVT.(CL.5)	86.00	LF
605881	22"X14" FES R.C.ARCH PIPE CLVT.	4.00	EACH
620001	LIME	5.00	TON
620011	SEEDING	2.42	ACRE
620022	MULCH COVER	4.84	ACRE
620030	WATER	161.50	MGAL
621001	TEMPORARY SEEDING	1.09	ACRE
621021	SILT FENCE	150.00	LF
621031	SAND BAG DITCH CHECKS	550.00	BAG
621111	SEDIMENT REMOVAL & DISPOSAL	48.00	CUYD
621151	ROCK DITCH CHECKS	63.00	CUYD
624001	SOLID SODDING	44.00	SQYD
634201	CC CURB & GUTTER-A (1'6")	68.00	LF
634404	CC CURB & GUTTER (TYPE SPEC.)	83.00	LF
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
726002	STANDARD SIGN	54.25	SQFT
729001	CHANNEL POST SIGN SUPPORT-A	1.00	EACH
729003	CHANNEL POST SIGN SUPPORT-C	8.00	EACH

18" PIPE CULVERT ALTERNATE - BID ONE ITEM ONLY

605604	18" R.C.PIPE CULVERTS(CL.5)	80.00	LF
605688	18" ZC(GALV)C.ST.PIPE CLVT.-16G	92.00	LF
605705	18" AL.C.C.ST.PIPE CLVT.-16G	92.00	LF
605722	18" P.P.M.C.C.ST.PIPE CLVT.-16G	92.00	LF

18" FLARED END SECTION ALTERNATE - BID ONE ITEM ONLY

605856	18" FES R.C.PIPE CLVT.	4.00	EACH
605857	18" FES C.ST.PIPE CLVT.	4.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHIN ONE HUNDRED FORTY-SIX (146) CALENDAR DAYS.