

ARKANSAS DEPARTMENT OF TRANSPORTATION

CB0401

N. FLINT CREEK STR. & APPRS. (SPRINGTOWN) (S)

FEDERAL AID PROJECT BFPO-STPB-0004(81)

THE PURPOSE OF THIS PROJECT IS TO CONSTRUCT A QUINT. 12' X 8' R.C. BOX CULVERT AND APPROACHES ON 0.138 MILE OF BREDEHOEFT ROAD IN THE CITY OF SPRINGTOWN IN BENTON COUNTY. THIS PROJECT CONSISTS OF CLEARING AND GRUBBING, EARTHWORK, AGGREGATE BASE COURSE, ACHM SURFACE COURSE, MAINTENANCE OF TRAFFIC, MINOR DRAINAGE STRUCTURES, EROSION CONTROL ITEMS, ONE QUINTUPLE R.C. BOX CULVERT (TOTAL SPAN 63.83'), AND MISC. ITEMS.

ROUTES: BREDEHOEFT RD.

COUNTY: BENTON

LENGTH: 0.138 mile in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

201012	CLEARING	9.00	STA
201111	GRUBBING	9.00	STA
202120	R&D OF LOW WATER SLAB	1.00	EACH
202922	REMOV. AND RELOCATION OF SIGN	1.00	EACH
210210	UNCLASSIFIED EXCAVATION	1,597.00	CUYD
210601	COMPACTED EMBANKMENT	2,190.00	CUYD
210702	SOIL STABILIZATION	25.00	TON
303107	AGGR.BASE COURSE(CLASS 7)	1,449.00	TON
407162	MA IN ACHM SURFACE(1/2")	287.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	18.00	TON
601001	MOBILIZATION	1.00	L.S.
602011	FURNISHING FIELD OFFICE	1.00	EACH
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	202.00	SQFT
604013	BARRICADES	32.00	LF
604023	TRAFFIC DRUMS	58.00	EACH
606703	18" SIDE DRAIN	60.00	LF
611008	4" PIPE UNDERDRAINS	200.00	LF
611013	UNDERDRAIN OUTLET PROTECTORS	4.00	EACH
620001	LIME	4.00	TON
620011	SEEDING	1.86	ACRE
620022	MULCH COVER	4.22	ACRE
620030	WATER	238.50	MGAL
621001	TEMPORARY SEEDING	2.36	ACRE
621021	SILT FENCE	500.00	LF
621031	SAND BAG DITCH CHECKS	132.00	BAG
621111	SEDIMENT REMOVAL & DISPOSAL	342.00	CUYD
621151	ROCK DITCH CHECKS	51.00	CUYD
621169	FILTER SOCK (18")	2,023.00	LF
623001	SECOND SEEDING APPLICATION	1.86	ACRE
624001	SOLID SODDING	59.00	SQYD
626003	EROSION CONTROL MATTING-3	107.00	SQYD
634201	CC CURB & GUTTER-A (1'6")	308.00	LF
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
726002	STANDARD SIGN	12.00	SQFT
729003	CHANNEL POST SIGN SUPPORT-C	4.00	EACH

801101	UNCLASS.EXCAV.FOR STRS-RDWY.	170.00	CUYD
802011	CLASS S CONCRETE-ROADWAY	395.20	CUYD
804003	REINF.STEEL-ROADWAY (GR 60)	52,996.00	LB

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHIN TWO HUNDRED NINETY-NINE (299) CALENDAR DAYS.