

ARKANSAS DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS

Internet bids for the construction of the following jobs will be received by the Arkansas Department of Transportation at the **STATE HIGHWAY BUILDING** located at **10324 INTERSTATE 30**, southwest of **LITTLE ROCK, ARKANSAS**, until **ten o'clock a.m., (10:00 a.m.) and until one thirty p.m., (1:30 p.m.)**, **May 20, 2026**. Bids will be posted on the Department's website at <http://www.ardot.gov/divisions/program-management/construction-contract-development/construction-contractors/currently-advertised-projects> once the downloading process has been completed.

BIDS FOR THE FOLLOWING PROJECTS ARE DUE AT 10:00 A.M.

JOB NO.	JOB NAME
020802	HWYS. 15/31 Y-INTERS. SAFETY IMPVTS. (S)
A40052	I-49 – SCHOOL AVE. (FAYETTEVILLE) (S)
A70042	HWY. 275 – FORDYCE (S)
A00095	POINSETT CO. LINE – HWY. 158 (S)
C59009	DES ARC OVERLAY (S)
FA5310	UNION VALLEY RD. SURFACING (S)
SA0367	HWY. 201 – HWY. 126 (OVERLAY) (S)
SA0770	CO. RD. 22 – SOUTH (RESEAL) (S)
SA1669	CRAIGHEAD CO. RESEAL (S)
SA3736	STAMPS C.L. – LEWISVILLE C.L. (LEVEL & SEAL) (S)
SA3860	HWY. 228 – NORTH (SEAL & SURFACING) (S)
SA4141	HWY. 108 – CO. RD. 12 (SURFACING) (S)
SA4750	HWY. 158 – CO. RD. 474 (OVERLAY) (S)
SA4840	HWY. 79 – NORTH (OVERLAY) (S)
SA5453	HWY. 1 – HWY. 39 (RESEAL) (S)
SA6347	HWY. 80 – WALDRON CITY LIMITS (OVERLAY) (S)

BIDS FOR THE FOLLOWING PROJECTS ARE DUE AT 1:30 P.M.

JOB NO.	JOB NAME
A10052	HWY. 49 – EAST (S)
A30044	TEXAS STATE LINE – EAST (S)
A60058	I-30 – GRANT CO. LINE (S)
C73017	COMMUNITY DR. PHASE 2 (BEEBE) (S)
SA0253	ASHLEY CO. OVERLAY NO. 7 (S)
SA0449	HWY. 102 – FALLING SPRINGS RD. (OVERLAY) (S)
SA1363	CLEVELAND CO. LEVEL & RESEAL (S)
SA1670	HWY. 135 – WEST (OVERLAY) (S)
SA3280	PLEASANT PLAINS CITY LIMITS – WEST (OVERLAY) (S)
SA3354	HWY. 177 – NORTH (LEVEL & RESEAL) (S)
SA3859	PORTIA CITY LIMITS – SOUTH (SURFACING) (S)
SA4749	HWY. 61 – CO. RD. 599 (LEVEL & RESEAL) (S)
SA5142	HWY. 374 – SOUTH (OVERLAY) (S)
SA5352	HWY. 324 – WEST (SURFACING) (S)
SA6651	SEVIER CO. RESEAL NO. 19 (S)

Plans, Proposal Documents, and Specifications may be purchased in the Program Management Division at the address noted above during regular business hours until 4:30 the day before the time established for opening of Proposals.

To become an eligible bidder, prospective bidders must be registered to bid in Arkansas with Bid Express. Prospective bidders must also contact the Program Management Division at (501) 569-2261 during regular business hours (or via email at pmd@ardot.gov) between the date the project is advertised and 4:30 p.m. on the day prior to the scheduled bid opening to request to become eligible to bid specific projects. Only prequalified contractors or their authorized representative may request to become an eligible bidder.

Questions pertaining to projects during the advertisement period should be addressed to the Program Management Division at pmd@ardot.gov. The deadline to submit a question is the Wednesday prior to the scheduled letting date. A question submitted after the close of business on the Wednesday prior to the scheduled letting date may not receive a response.

In order to have a bid considered, contractors must furnish a proposal guaranty consisting of either a bidder's bond or a certified or cashier's check in the amount of five percent (5%) of the total amount bid. In order for a bond to be acceptable to the Department, the company issuing the bond must be named in the Department of Treasury Listing of companies holding Certificates of Authority as acceptable sureties on Federal Bonds and as acceptable reinsuring companies. The Underwriting Limitation of the bonding company shall be adhered to. Any excess (between the face amount of the Bond and the Underwriting Limitation) shall be protected by reinsurance provided by an acceptable reinsuring company.

A current directory of certified DBE firms may be obtained on the Department's web site at <https://www.ardot.gov/divisions/equal-employment-opportunity-disadvantaged-business-enterprise/dbe> or may be requested by calling the Department's EEO-DBE Section at (501) 569-2259 or the Program Management Division, Construction Contract Development Section at (501) 569-2261.

It is suggested that successful bidders utilize to the fullest extent practicable the facilities and services of the local offices of the Arkansas Department of Workforce Services to meet their manpower requirements.

These contracts are subject to normal prequalification, licensing and bonding requirements, applicable labor laws, non-discrimination provisions, wage rate laws and other Federal laws including the Fair Labor Standards Acts of 1938. The Work Hours Act of 1962 and Title VI of the Civil Rights Act of 1964 also apply.

The Arkansas Department of Transportation (ARDOT) complies with all civil rights provisions of federal statutes and related authorities that prohibit discrimination in programs and activities receiving federal financial assistance. Therefore, ARDOT does not discriminate on the basis of race, sex, color, age, national origin, religion (not applicable as a protected group under the FMCSA Title VI Program), or disability in the admission, access to and treatment in ARDOT's programs and activities, as well as ARDOT's hiring or employment practices. Complaints of alleged discrimination and inquiries regarding ARDOT's nondiscrimination policies may be directed to the Civil Rights Division, P. O. Box 2261, Little Rock, AR 72203, (501) 569-2298, (Voice/TTY 711), or the following email address: Civil.Rights@ardot.gov

Free language assistance may be available upon request.

This notice is available from the ADA/504/Title VI Coordinator in large print, on audiotape, and in Braille.

The Department reserves the right to reject any or all bids and to waive any formalities.

**BY AUTHORITY OF
ARKANSAS STATE HIGHWAY COMMISSION**

Philip Taldo, Chairman

NOTICE TO ALL BIDDERS

TO REPORT BID RIGGING ACTIVITIES CALL:

1-800-424-9071

The United States Department of Transportation (DOT) operates the above toll-free "hotline" Monday through Friday, 8:00 a.m. to 5:00 p.m. eastern time. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the "hotline" to report such activities.

The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A10052

HWY. 49 – EAST (S)

FEDERAL AID PROJECT NHPP-0048(45)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 4.776 MILES OF HIGHWAY 79 IN LEE AND MONROE COUNTIES. THIS PROJECT CONSISTS OF AGGREGATE BASE COURSE, ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, RUMBLE STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 79
SECTIONS: 14 & 15

COUNTY: LEE & MONROE
LENGTH: 4.776 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303117	AGGR.BASE COURSE(CLASS 7)	504.00	TON
401011	TACK COAT	16,461.00	GAL
407161	MA IN ACHM SURFACE(3/8")	4,985.00	TON
407431	AB(PG64-22)ACHM SURF(3/8")	341.00	TON
412002	COLD MILLING ASPHALT PVMT.	522.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	100.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	361.00	SQFT
604041	CONST.PAVEMENT MARKINGS	73,107.00	LF
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642011	RUMBLE STRIPES IN ASPHALT SHOULDERS	50,266.00	LF
642102	CENTERLINE RUMBLE STRIPES IN ASPH. RDWYS	25,132.00	LF
719002	THERMO.PVMT.MARK.WH(6")	50,435.00	LF
719102	THERMO.PVMT.MARK.YL(6")	22,144.00	LF
721002	RAISED PAVEMENT MARKERS-2	318.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

020802

HWYS. 15/31 Y-INTERS. SAFETY IMPVTS. (S)

FEDERAL AID PROJECT HSIP-0035(72)

THE PURPOSE OF THIS PROJECT IS TO IMPROVE THE INTERSECTION AT HIGHWAYS 15 AND 31 WITH CHANNELIZATION IN JEFFERSON COUNTY. THIS PROJECT CONSISTS OF CLEARING AND GRUBBING, REMOVAL AND DISPOSAL ITEMS, FLOWABLE SELECT MATERIAL, EARTHWORK, AGGREGATE BASE COURSE, ACHM BINDER AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, MINOR DRAINAGE, EROSION CONTROL, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 15 & 31

SECTIONS: 8 & 1

COUNTY: JEFFERSON

LENGTH: 0.298 mile in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

201011	CLEARING	4.00	STA
201111	GRUBBING	4.00	STA
202047	R&D OF CONCRETE ISLANDS	44.00	SQYD
202096	R&D OF PIPE CULVERTS	4.00	EACH
202097	R&D OF BOX CULVERTS	1.00	EACH
202200	R&D OF MAILBOXES	1.00	EACH
206021	FLOWABLE SELECT MATERIAL	28.00	CUYD
210213	UNCLASSIFIED EXCAVATION	1,270.00	CUYD
210611	COMPACTED EMBANKMENT	7,254.00	CUYD
210702	SOIL STABILIZATION	75.00	TON
303117	AGGR.BASE COURSE(CLASS 7)	5,176.00	TON
401011	TACK COAT	818.00	GAL
406161	M.A. IN ACHM BINDER(1")	364.00	TON
406402	A.B.(PG64-22)ACHM BINDER(1")	19.00	TON
407162	MA IN ACHM SURFACE(1/2")	1,792.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	94.00	TON
412002	COLD MILLING ASPHALT PVMT.	744.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	8.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	392.00	SQFT
604013	BARRICADES	64.00	LF
604023	TRAFFIC DRUMS	52.00	EACH
604031	FURN.&INSTL.PRCST.CONC.BARR.	519.00	LF
604041	CONST.PAVEMENT MARKINGS	23,169.00	LF
604083	VERTICAL PANELS	52.00	EACH
606703	18" SIDE DRAIN	68.00	LF
620001	LIME	4.00	TON
620011	SEEDING	2.07	ACRE
620022	MULCH COVER	4.14	ACRE
620030	WATER	254.10	MGAL
621001	TEMPORARY SEEDING	2.07	ACRE
621021	SILT FENCE	2,620.00	LF
621111	SEDIMENT REMOVAL & DISPOSAL	120.00	CUYD

621151	ROCK DITCH CHECKS	69.00	CUYD
623001	SECOND SEEDING APPLICATION	2.07	ACRE
624001	SOLID SODDING	65.00	SQYD
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
718002	REFL.PAINT PVMT.MRK.WH(6")	3,420.00	LF
718005	REFL.PAINT PVMT.MRK.WH(12")	55.00	LF
718102	REFL.PAINT PVMT.MRK.YL(6")	4,046.00	LF
718105	REFL.PAINT PVMT.MRK.YL(12")	232.00	LF
721002	RAISED PAVEMENT MARKERS-2	26.00	EACH
731071	TEMP. IMPACT ATTEN. BARR.	1.00	EACH
731072	TEMP. IMPACT ATTEN. BARRIER (REPAIR)	1.00	EACH
801101	UNCLASS.EXCAV.FOR STRS-RDWY.	45.00	CUYD
802012	CLASS S CONCRETE-ROADWAY	19.90	CUYD
804003	REINF.STEEL-ROADWAY (GR 60)	1,965.00	LB

24" PIPE CULVERTS ALTERNATE - BID ONE ITEM ONLY

605606	24" R.C.PIPE CULVERTS(CL.3)	122.00	LF
605691	24" ASPH.C.C.ST.PIPE CLVT.-16G	122.00	LF
605706	24" AL.C.C.ST.PIPE CLVT.-16G	122.00	LF
605725	24" P.P.M.C.C.ST.PIPE CLVT.-16G	122.00	LF
605835	24" POLYPROPYLENE PIPE	122.00	LF
605842	24" HIGH DENSITY POLYETHYLENE PIPE	122.00	LF
605848	24" PVC PIPE	122.00	LF

36" PIPE CULVERTS ALTERNATE - BID ONE ITEM ONLY

605618	36" R.C.PIPE CULVERTS(CL.4)	72.00	LF
605694	36" ASPH.C.C.ST.PIPE CLVT.-14G	72.00	LF
605708	36" AL.C.C.ST.PIPE CLVT.-14G	72.00	LF
605729	36" P.P.M.C.C.ST.PIPE CLVT.-14G	72.00	LF
605837	36" POLYPROPYLENE PIPE	72.00	LF
605844	36" HIGH DENSITY POLYETHYLENE PIPE	72.00	LF
605850	36" PVC PIPE	72.00	LF

24" FLARED END SECTIONS ALTERNATE - BID ONE ITEM ONLY

605858	24" FES R.C.PIPE CLVT.	2.00	EACH
605859	24" FES C.ST.PIPE CLVT.	2.00	EACH

36" FLARED END SECTIONS ALTERNATE - BID ONE ITEM ONLY

605862	36" FES R.C.PIPE CLVT.	2.00	EACH
605863	36" FES C.ST.PIPE CLVT.	2.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHIN ONE HUNDRED FORTY (140) CALENDAR DAYS.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A30044

TEXAS STATE LINE – EAST (S)

FEDERAL AID PROJECT NHPP-0046(56)

THE PURPOSE OF THIS PROJECT IS TO PERFORM PATCHING AND RE-SEAL JOINTS ON APPROXIMATELY 1.111 MILES OF HIGHWAY 151 IN MILLER COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL OF CONCRETE PAVEMENT FOR PATCHING, CONTINUOUSLY REINFORCED CONCRETE PAVEMENT, PORTLAND CEMENT CONCRETE PAVEMENT PATCHING, JOINT REHABILITATION, MAINTENANCE OF TRAFFIC, RUMBLE STRIPS, CRACK ROUT AND SEAL, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 151

SECTIONS: 0

COUNTY: MILLER

LENGTH: 1.111 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

415011	ACHM PATCH.EXIST.RDWY.	100.00	TON
507002	R & D OF CONCRETE PAVEMENT FOR PATCHING	562.00	SQYD
507013	R&D C.R.CONC.PVMT.FOR PATCH	1,524.00	SQYD
507232	P.C.C.P. PATCH-12"	562.00	SQYD
507310	CONT. R.C. PAVEMENT PATCHING (12" U.T.)	1,524.00	SQYD
509001	JOINT REHAB. (TYPE A)	1,192.00	LF
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	1,209.00	SQFT
604023	TRAFFIC DRUMS	300.00	EACH
604041	CONST.PAVEMENT MARKINGS	4,262.00	LF
604071	ADVANCE WARNING ARROW PANEL	48.00	DAY
604078	PORT.CHANGEABLE MESSAGE SIGN	8.00	WEEK
604160	MOBILE SPEED NOTIFICATION SYSTEM SPECIAL	1.00	EACH
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642002	RUMBLE STRIPS IN P.C.C.SHOULDERS	84.00	LF
719502	ENHANCED THERMO. PVMT. MRK. WH (6")	18,902.00	LF
719505	ENHANCED THERMO. PVMT. MRK. WH (12")	2,602.00	LF
719602	ENHANCED THERMO. PVMT. MRK. YL (6")	17,268.00	LF
721002	RAISED PAVEMENT MARKERS-2	499.00	EACH
802012	CLASS S CONCRETE-ROADWAY	9.34	CUYD
804003	REINF.STEEL-ROADWAY (GR 60)	210.00	LB
916027	CRACK ROUT AND SEAL	26,496.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A40052

I-49 – SCHOOL AVE. (FAYETTEVILLE) (S)

FEDERAL AID PROJECT NHPP-9142(59)

THE PURPOSE OF THIS PROJECT IS TO MILL AND OVERLAY APPROXIMATELY 1.513 MILES OF HIGHWAY 180 IN WASHINGTON COUNTY. THIS PROJECT CONSISTS OF ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 180

SECTIONS: 0

COUNTY: WASHINGTON

LENGTH: 1.513 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401011	TACK COAT	10,416.00	GAL
407162	MA IN ACHM SURFACE(1/2")	6,059.00	TON
407452	AB(PG76-22)ACHM SURF(1/2")	387.00	TON
412002	COLD MILLING ASPHALT PVMT.	49,505.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	500.00	TON
601001	MOBILIZATION	1.00	L.S.
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	892.00	SQFT
604023	TRAFFIC DRUMS	100.00	EACH
604041	CONST.PAVEMENT MARKINGS	26,000.00	LF
604045	CONST.PAVEMENT MARKINGS (WORD)	8.00	EACH
604046	CONST.PAVEMENT MARKINGS (ARROW)	10.00	EACH
604051	REMOVABLE CONST.PVMT.MRK.	2,160.00	LF
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
719002	THERMO.PVMT.MARK.WH(6")	4,980.00	LF
719006	THERMO.PVMT.MARK.WH(24")	540.00	LF
719102	THERMO.PVMT.MARK.YL(6")	19,540.00	LF
719201	THERMO.PVMT.MARK.(WORD)	8.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	10.00	EACH
721002	RAISED PAVEMENT MARKERS-2	890.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A60058

I-30 – GRANT CO. LINE (S)

FEDERAL AID PROJECT NHPP-0030(36)

THE PURPOSE OF THIS PROJECT IS TO MILL, OVERLAY, AND PLACE ULTRATHIN BONDED WEARING COURSE ON APPROXIMATELY 10.115 MILES OF HIGHWAY 270 IN HOT SPRING COUNTY. THIS PROJECT CONSISTS OF AGGREGATE BASE COURSE, ACHM SURFACE COURSE, ULTRATHIN BONDED WEARING COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, RUMBLE STRIPS, LOOP WIRING, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 270

SECTIONS: 8

COUNTY: HOT SPRING

LENGTH: 10.115 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303117	AGGR.BASE COURSE(CLASS 7)	728.00	TON
401011	TACK COAT	34,949.00	GAL
407162	MA IN ACHM SURFACE(1/2")	18,839.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	1,160.00	TON
407905	ULTRATHIN BONDED WEARING CRS (5/8"-TY B)	2,083.00	TON
412002	COLD MILLING ASPHALT PVMT.	154,004.00	SQYD
414011	ASPH.CONC.PATCH-MAINT.	255.00	TON
415011	ACHM PATCH.EXIST.RDWY.	200.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	728.00	SQFT
604041	CONST.PAVEMENT MARKINGS	218,236.00	LF
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642001	RUMBLE STRIPS IN ASPHALT SHOULDERS	65,894.00	LF
704036	LOOP WIRING CLASS III (1C/16 A.W.G.)	1,856.00	LF
719002	THERMO.PVMT.MARK.WH(6")	108,818.00	LF
719003	THERMO.PVMT.MARK.WH(8")	568.00	LF
719006	THERMO.PVMT.MARK.WH(24")	213.00	LF
719102	THERMO.PVMT.MARK.YL(6")	109,418.00	LF
719201	THERMO.PVMT.MARK.(WORD)	5.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	5.00	EACH
721002	RAISED PAVEMENT MARKERS-2	729.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A70042

HWY. 275 – FORDYCE (S)

FEDERAL AID PROJECT STPR-0720(1)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY AND PLACE ULTRATHIN BONDED WEARING COURSE ON APPROXIMATELY 13.680 MILES OF HIGHWAY 274 IN CALHOUN AND DALLAS COUNTIES. THIS PROJECT CONSISTS OF AGGREGATE BASE COURSE, ACHM SURFACE COURSE, ULTRATHIN BONDED WEARING COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, APPROACH GUTTERS, MAINTENANCE OF TRAFFIC, GUARDRAIL, RUMBLE STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 274
SECTIONS: 3 & 4

COUNTY: CALHOUN & DALLAS
LENGTH: 13.68 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303117	AGGR.BASE COURSE(CLASS 7)	1,040.00	TON
401011	TACK COAT	24,762.00	GAL
407161	MA IN ACHM SURFACE(3/8")	19,320.00	TON
407431	AB(PG64-22)ACHM SURF(3/8")	16.00	TON
407441	AB(PG70-22)ACHM SURF(3/8")	1,327.00	TON
407905	ULTRATHIN BONDED WEARING CRS (5/8"-TY B)	5,672.00	TON
412002	COLD MILLING ASPHALT PVMT.	26,667.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	332.00	TON
504264	APPROACH GUTTERS	33.44	CUYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	1,004.00	SQFT
604023	TRAFFIC DRUMS	135.00	EACH
604041	CONST.PAVEMENT MARKINGS	292,212.00	LF
617005	GUARDRAIL (TYPE A)	1,800.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	16.00	EACH
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642011	RUMBLE STRIPES IN ASPHALT SHOULDERS	135,664.00	LF
642102	CENTERLINE RUMBLE STRIPES IN ASPH. RDWYS	67,832.00	LF
701603	PORTABLE TRAFFIC SIGNAL SYSTEM-ACTUATED	10.00	WEEK
718002	REFL.PAINT PVMT.MRK.WH(6")	145,604.00	LF
718102	REFL.PAINT PVMT.MRK.YL(6")	146,608.00	LF
718203	REFL.PAINT PVMT.MRK.(RR EMB.)	3.00	EACH
721002	RAISED PAVEMENT MARKERS-2	924.00	EACH
804003	REINF.STEEL-ROADWAY (GR 60)	2,368.00	LB

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A00095

POINSETT CO. LINE – HWY. 158 (S)

FEDERAL AID PROJECT STPR-0016(105)

THE PURPOSE OF THIS PROJECT IS TO PLACE ULTRATHIN BONDED WEARING COURSE ON APPROXIMATELY 4.003 MILES OF HIGHWAY 135 IN CRAIGHEAD COUNTY. THIS PROJECT CONSISTS OF ACHM SURFACE COURSE, ULTRATHIN BONDED WEARING COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, RUMBLE STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 135

SECTIONS: 2

COUNTY: CRAIGHEAD

LENGTH: 4.003 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401011	TACK COAT	12,862.00	GAL
407161	MA IN ACHM SURFACE(3/8")	3,907.00	TON
407441	AB(PG70-22)ACHM SURF(3/8")	254.00	TON
407905	ULTRATHIN BONDED WEARING CRS (5/8"-TY B)	2,984.00	TON
412002	COLD MILLING ASPHALT PVMT.	1,293.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	20.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	594.00	SQFT
604041	CONST.PAVEMENT MARKINGS	85,114.00	LF
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642011	RUMBLE STRIPES IN ASPHALT SHOULDERS	38,338.00	LF
642102	CENTERLINE RUMBLE STRIPES IN ASPH. RDWYS	21,278.00	LF
718002	REFL.PAINT PVMT.MRK.WH(6")	42,557.00	LF
718004	REFL.PAINT PVMT.MRK.WH(10")	180.00	LF
718102	REFL.PAINT PVMT.MRK.YL(6")	42,557.00	LF
721002	RAISED PAVEMENT MARKERS-2	267.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

C59009

DES ARC OVERLAY (S)

STATE AID CITY JOB (CODE 9971)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 1.64 MILES OF VARIOUS CITY STREETS IN THE CITY OF DES ARC IN PRAIRIE COUNTY. THIS PROJECT CONSISTS OF AGGREGATE BASE COURSE, ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, AND MISC. ITEMS.

ROUTES: VARIOUS

COUNTY: PRAIRIE

LENGTH: 1.64 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303107	AGGR.BASE COURSE(CLASS 7)	217.00	TON
401011	TACK COAT	2,527.00	GAL
407161	MA IN ACHM SURFACE(3/8")	2,525.00	TON
407431	AB(PG64-22)ACHM SURF(3/8")	161.00	TON
412002	COLD MILLING ASPHALT PVMT.	215.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	220.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	216.00	SQFT

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

C73017

COMMUNITY DR. PHASE 2 (BEEBE) (S)

STATE AID CITY JOB (CODE 9971)

THE PURPOSE OF THIS PROJECT IS TO CONSTRUCT 0.331 MILE OF CITY STREET IN WHITE COUNTY. THIS PROJECT CONSISTS OF CLEARING AND GRUBBING, REMOVAL AND DISPOSAL OF ITEMS, EARTH WORK, AGGREGATE BASE COURSE, ACHM SURFACE COURSE, MAINTENANCE OF TRAFFIC, MINOR DRAINAGE STRUCTURES, EROSION CONTROL ITEMS, AND MISC. ITEMS.

ROUTES: VARIOUS

COUNTY: WHITE

LENGTH: 0.331 mile in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

201011	CLEARING	1.00	STA
201111	GRUBBING	18.00	STA
202003	R&D OF CURB AND GUTTER	95.00	LF
210210	UNCLASSIFIED EXCAVATION	2,192.00	CUYD
210601	COMPACTED EMBANKMENT	2,103.00	CUYD
210702	SOIL STABILIZATION	285.00	TON
303107	AGGR.BASE COURSE(CLASS 7)	4,143.00	TON
401001	PRIME COAT	2,650.00	GAL
401011	TACK COAT	7.00	GAL
407162	MA IN ACHM SURFACE(1/2")	748.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	47.00	TON
412001	COLD MILLING ASPHALT PVMT.	205.00	SQYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	43.00	SQFT
604013	BARRICADES	48.00	LF
604023	TRAFFIC DRUMS	25.00	EACH
605766	22" X 14" R.C.ARCH PIPE CLVT.(CL.5)	86.00	LF
605881	22"X14" FES R.C.ARCH PIPE CLVT.	4.00	EACH
620001	LIME	5.00	TON
620011	SEEDING	2.42	ACRE
620022	MULCH COVER	4.84	ACRE
620030	WATER	161.50	MGAL
621001	TEMPORARY SEEDING	1.09	ACRE
621021	SILT FENCE	150.00	LF
621031	SAND BAG DITCH CHECKS	550.00	BAG
621111	SEDIMENT REMOVAL & DISPOSAL	48.00	CUYD
621151	ROCK DITCH CHECKS	63.00	CUYD
624001	SOLID SODDING	44.00	SQYD
634201	CC CURB & GUTTER-A (1'6")	68.00	LF
634404	CC CURB & GUTTER (TYPE SPEC.)	83.00	LF
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
726002	STANDARD SIGN	54.25	SQFT
729001	CHANNEL POST SIGN SUPPORT-A	1.00	EACH
729003	CHANNEL POST SIGN SUPPORT-C	8.00	EACH

18" PIPE CULVERT ALTERNATE - BID ONE ITEM ONLY

605604	18" R.C.PIPE CULVERTS(CL.5)	80.00	LF
605688	18" ZC(GALV)C.ST.PIPE CLVT.-16G	92.00	LF
605705	18" AL.C.C.ST.PIPE CLVT.-16G	92.00	LF
605722	18" P.P.M.C.C.ST.PIPE CLVT.-16G	92.00	LF

18" FLARED END SECTION ALTERNATE - BID ONE ITEM ONLY

605856	18" FES R.C.PIPE CLVT.	4.00	EACH
605857	18" FES C.ST.PIPE CLVT.	4.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHIN ONE HUNDRED FORTY-SIX (146) CALENDAR DAYS.

ARKANSAS DEPARTMENT OF TRANSPORTATION

FA5310

UNION VALLEY RD. SURFACING (S)

FEDERAL AID PROJECT STPF-0053(47)

THE PURPOSE OF THIS PROJECT IS TO SURFACE APPROXIMATELY 5.28 MILES OF UNION VALLEY RD. IN PERRY COUNTY. THIS PROJECT CONSISTS OF AGGREGATE BASE COURSE, AGGREGATE SURFACE COURSE, RECONSTRUCTED BASE COURSE, ACHM SURFACE COURSE, MAINTENANCE OF TRAFFIC, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: UNION VALLEY RD.

COUNTY: PERRY

LENGTH: 5.28 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303117	AGGR.BASE COURSE(CLASS 7)	4,193.00	TON
303308	AGGREGATE SURFACE COURSE (CLASS D-8)	2,274.00	TON
305001	RECONSTRUCTED BASE COURSE	279.00	STA
407162	MA IN ACHM SURFACE(1/2")	10,041.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	675.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	152.00	SQFT
604023	TRAFFIC DRUMS	50.00	EACH
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
718001	REFL.PAINT PVMT.MRK.WH(4")	55,706.00	LF
718101	REFL.PAINT PVMT.MRK.YL(4")	55,706.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA0253

ASHLEY CO. OVERLAY NO. 7 (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 2.10 MILES OF CO. RDS. 72, 73, AND 491 IN ASHLEY COUNTY. THIS PROJECT CONSISTS OF ACHM SURFACE COURSE, ACHM PATCHING, PAVEMENT MARKING, MAINTENANCE OF TRAFFIC AND MISC. ITEMS.

ROUTES: CRS 72, 73 & 491

COUNTY: ASHLEY

LENGTH: 2.10 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401012	TACK COAT	2,506.00	GAL
407161	MA IN ACHM SURFACE(3/8")	2,186.00	TON
407431	AB(PG64-22)ACHM SURF(3/8")	152.00	TON
415011	ACHM PATCH.EXIST.RDWY.	40.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	280.00	SQFT
718101	REFL.PAINT PVMT.MRK.YL(4")	10,560.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA0367

HWY. 201 – HWY. 126 (OVERLAY) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 3.00 MILES OF COUNTY ROAD 57 AND APPROXIMATELY 0.30 MILE OF COUNTY ROAD 618 IN BAXTER COUNTY. THIS PROJECT CONSISTS OF ACHM SURFACE COURSE, ACHM PATCHING, PAVEMENT MARKING, MAINTENANCE OF TRAFFIC, AND MISC ITEMS.

ROUTES: CRS 57 & 618

COUNTY: BAXTER

LENGTH: 3.30 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401011	TACK COAT	3,826.00	GAL
407162	MA IN ACHM SURFACE(1/2")	4,690.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	299.00	TON
415011	ACHM PATCH.EXIST.RDWY.	50.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	228.00	SQFT
718101	REFL.PAINT PVMT.MRK.YL(4")	34,848.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA0449

HWY. 102 – FALLING SPRINGS RD. (OVERLAY) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 3.02 MILES OF W. MOUNTAIN RD. AND CARLTON DR. IN BENTON COUNTY. THIS PROJECT CONSISTS OF AGGREGATE BASE COURSE, ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: W. MOUNTAIN RD. & CARLTON DR.

COUNTY: BENTON

LENGTH: 3.02 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303117	AGGR.BASE COURSE(CLASS 7)	479.00	TON
401011	TACK COAT	4,342.00	GAL
407162	MA IN ACHM SURFACE(1/2")	4,833.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	309.00	TON
412002	COLD MILLING ASPHALT PVMT.	609.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	40.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	208.00	SQFT
718001	REFL.PAINT PVMT.MRK.WH(4")	32,208.00	LF
718101	REFL.PAINT PVMT.MRK.YL(4")	32,208.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA0770

CO. RD. 22 – SOUTH (RESEAL) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO RESEAL APPROXIMATELY 1.00 MILE OF COUNTY ROAD 187 AND APPROXIMATELY 0.85 MILE OF COUNTY ROAD 24 IN CALHOUN COUNTY. THIS PROJECT CONSISTS OF ASPHALT SURFACE TREATMENT, ACHM SURFACE COURSE, MAINTENANCE OF TRAFFIC, AND MISC. ITEMS.

ROUTES: CRS 187 & 24

COUNTY: CALHOUN

LENGTH: 1.85 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401011	TACK COAT	300.00	GAL
402112	MINERAL AGGR.IN A.S.T.(CL2)	422.00	TON
402214	PLY.MOD.CAT.EMLS.ASPH.(CRS2P)(SLD.PLY.)	9,639.00	GAL
407161	MA IN ACHM SURFACE(3/8")	187.00	TON
407431	AB(PG64-22)ACHM SURF(3/8")	13.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	222.00	SQFT

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE October 16, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA1363

CLEVELAND CO. LEVEL & RESEAL (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO LEVEL AND SEAL APPROXIMATELY 1.70 MILES OF BANKS RD. & 1.75 MILES OF HARRELSON RD. IN CLEVELAND COUNTY. THIS PROJECT CONSISTS OF FOG SEAL, ASPHALT SURFACE TREATMENT, ACHM SURFACE COURSE, MAINTENANCE OF TRAFFIC, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: BANKS RD. & HARRELSON RD.

COUNTY: CLEVELAND

LENGTH: 3.45 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303117	AGGR.BASE COURSE(CLASS 7)	20.00	TON
401005	FOG SEAL (TYPE 2)	4,048.00	GAL
401011	TACK COAT	1,830.00	GAL
402112	MINERAL AGGR.IN A.S.T.(CL2)	708.00	TON
402214	PLY.MOD.CAT.EMLS.ASPH.(CRS2P)(SLD.PLY.)	16,192.00	GAL
407161	MA IN ACHM SURFACE(3/8")	1,141.00	TON
407431	AB(PG64-22)ACHM SURF(3/8")	79.00	TON
415011	ACHM PATCH.EXIST.RDWY.	70.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	347.00	SQFT
718101	REFL.PAINT PVMT.MRK.YL(4")	36,432.00	LF
726002	STANDARD SIGN	48.00	SQFT
729003	CHANNEL POST SIGN SUPPORT-C	10.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE October 16, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA1669

CRAIGHEAD CO. RESEAL (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO RESEAL APPROXIMATELY 2.99 MILES OF CO. RD. 324 AND 3.12 MILES OF CO. RD. 534 IN CRAIGHEAD COUNTY. THIS PROJECT CONSISTS OF FOG SEAL, REJUVENATING MASS CRACK TREATMENT, PAVEMENT MARKING, MAINTENANCE OF TRAFFIC AND MISC. ITEMS.

ROUTES: CRS 324 & 534

COUNTY: CRAIGHEAD

LENGTH: 6.11 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401005	FOG SEAL (TYPE 2)	7,709.00	GAL
402114	MINERAL AGGR.IN A.S.T.(CL4)	964.00	TON
402501	REJUVINATING EMULSIFIED ASPH (CMS-1PC)	23,127.00	GAL
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	432.00	SQFT
718101	REFL.PAINT PVMT.MRK.YL(4")	65,049.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE October 16, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA1670

HWY. 135 – WEST (OVERLAY) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 4.54 MILES OF COUNTY ROAD 928 IN CRAIGHEAD COUNTY. THIS PROJECT CONSISTS OF ULTRATHIN BONDED WEARING COURSE, COLD MILLING, MAINTENANCE OF TRAFFIC, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: CR 928

COUNTY: CRAIGHEAD

LENGTH: 4.54 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

407904	ULTRATHIN BONDED WEARING CRS (3/4"-TY C)	2,361.00	TON
412001	COLD MILLING ASPHALT PVMT.	700.00	SQYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	350.00	SQFT
718101	REFL.PAINT PVMT.MRK.YL(4")	48,576.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION
SA3280
PLEASANT PLAINS CITY LIMITS – WEST (OVERLAY) (S)
STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 2.94 MILES OF WISH ST. IN INDEPENDENCE COUNTY. THIS PROJECT CONSISTS OF AGGREGATE BASE COURSE, ACHM SURFACE COURSE, COLD MILLING, ACHM PATCHING, PAVEMENT MARKING, MAINTENANCE OF TRAFFIC AND MISC. ITEMS.

ROUTES: WISH ST.

COUNTY: INDEPENDENCE

LENGTH: 2.94 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303117	AGGR.BASE COURSE(CLASS 7)	464.00	TON
401011	TACK COAT	3,595.00	GAL
407162	MA IN ACHM SURFACE(1/2")	4,137.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	259.00	TON
412001	COLD MILLING ASPHALT PVMT.	1,037.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	80.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	288.00	SQFT
718101	REFL.PAINT PVMT.MRK.YL(4")	31,046.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA3354

HWY. 177 – NORTH (LEVEL & RESEAL) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO LEVEL AND RESEAL 3.38 MILES OF DOLPH RD. IN IZARD COUNTY. THIS PROJECT CONSISTS OF ACHM SURFACE COURSE, ASPHALT SURFACE TREATMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, AND MISC. ITEMS.

ROUTES: DOLPH RD.

COUNTY: IZARD

LENGTH: 3.38 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401011	TACK COAT	300.00	GAL
402112	MINERAL AGGR.IN A.S.T.(CL2)	694.00	TON
402214	PLY.MOD.CAT.EMLS.ASPH.(CRS2P)(SLD.PLY.)	15,863.00	GAL
407161	MA IN ACHM SURFACE(3/8")	187.00	TON
407431	AB(PG64-22)ACHM SURF(3/8")	13.00	TON
415011	ACHM PATCH.EXIST.RDWY.	40.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	164.00	SQFT

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE October 16, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA3736

STAMPS C.L. – LEWISVILLE C.L. (LEVEL & SEAL) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO LEVEL AND SEAL APPROXIMATELY 4.15 MILES OF CO. RD. 28 IN LAFAYETTE COUNTY. THIS PROJECT CONSISTS OF FOG SEAL, ASPHALT SURFACE TREATMENT, ACHM SURFACE COURSE, MAINTENANCE OF TRAFFIC, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: CR 28

COUNTY: LAFAYETTE

LENGTH: 4.15 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401005	FOG SEAL (TYPE 2)	5,110.00	GAL
401011	TACK COAT	762.00	GAL
402111	MINERAL AGGR.IN A.S.T.(CL1)	894.00	TON
402214	PLY.MOD.CAT.EMLS.ASPH.(CRS2P)(SLD.PLY.)	20,439.00	GAL
407161	MA IN ACHM SURFACE(3/8")	477.00	TON
407431	AB(PG64-22)ACHM SURF(3/8")	31.00	TON
415011	ACHM PATCH.EXIST.RDWY.	60.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	452.00	SQFT
718101	REFL.PAINT PVMT.MRK.YL(4")	34,205.00	LF
726002	STANDARD SIGN	96.00	SQFT
729003	CHANNEL POST SIGN SUPPORT-C	16.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE October 16, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA3859

PORTIA CITY LIMITS – SOUTH (SURFACING) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO SURFACE APPROXIMATELY 1.00 MILE OF COUNTY ROAD 504 IN LAWRENCE COUNTY. THIS PROJECT CONSISTS OF AGGREGATE BASE COURSE, RECONSTRUCTED BASE COURSE, ACHM SURFACE COURSE, MAINTENANCE OF TRAFFIC, AND MISC. ITEMS.

ROUTES: CR 504

COUNTY: LAWRENCE

LENGTH: 1.00 mile in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303117	AGGR.BASE COURSE(CLASS 7)	222.00	TON
305001	RECONSTRUCTED BASE COURSE	48.00	STA
401011	TACK COAT	109.00	GAL
407162	MA IN ACHM SURFACE(1/2")	1,239.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	73.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	196.00	SQFT

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA3860

HWY. 228 – NORTH (SEAL & SURFACING) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO SEAL APPROXIMATELY 0.70 MILE AND SURFACE 0.80 MILE OF COUNTY ROAD 529 IN LAWRENCE COUNTY. THIS PROJECT CONSISTS OF RECONSTRUCTED BASE COURSE, ASPHALT SURFACE TREATMENT, MAINTENANCE OF TRAFFIC, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: CR 529

COUNTY: LAWRENCE

LENGTH: 1.50 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

305001	RECONSTRUCTED BASE COURSE	43.00	STA
401001	PRIME COAT	3,942.00	GAL
401011	TACK COAT	270.00	GAL
402112	MINERAL AGGR.IN A.S.T.(CL2)	449.00	TON
402214	PLY.MOD.CAT.EMLS.ASPH.(CRS2P)(SLD.PLY.)	10,325.00	GAL
407161	MA IN ACHM SURFACE(3/8")	169.00	TON
407431	AB(PG64-22)ACHM SURF(3/8")	11.00	TON
415011	ACHM PATCH.EXIST.RDWY.	70.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	132.00	SQFT
718101	REFL.PAINT PVMT.MRK.YL(4")	15,840.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE October 16, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA4141

HWY. 108 – CO. RD. 12 (SURFACING) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO SURFACE APPROXIMATELY 1.00 MILE OF CO. RD. 51 IN LITTLE RIVER COUNTY. THIS PROJECT CONSISTS OF AGGREGATE BASE COURSE, ACHM SURFACE COURSE, PAVEMENT MARKING, MAINTENANCE OF TRAFFIC AND MISC. ITEMS.

ROUTES: CR 51

COUNTY: LITTLE RIVER

LENGTH: 1.00 mile in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303117	AGGR.BASE COURSE(CLASS 7)	292.00	TON
407162	MA IN ACHM SURFACE(1/2")	1,832.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	117.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	132.00	SQFT
718101	REFL.PAINT PVMT.MRK.YL(4")	10,560.00	LF
726002	STANDARD SIGN	12.00	SQFT
729003	CHANNEL POST SIGN SUPPORT-C	4.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA4749

HWY. 61 – CO. RD. 599 (LEVEL & RESEAL) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO LEVEL AND RESEAL APPROXIMATELY 2.00 MILES OF CO. RD. 474 IN MISSISSIPPI COUNTY. THIS PROJECT CONSISTS OF AGGREGATE BASE COURSE, FOG SEAL, ASPHALT SURFACE TREATMENT, ACHM SURFACE COURSE, MAINTENANCE OF TRAFFIC, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: CR 474

COUNTY: MISSISSIPPI

LENGTH: 2.00 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303117	AGGR.BASE COURSE(CLASS 7)	317.00	TON
401005	FOG SEAL (TYPE 2)	2,816.00	GAL
401011	TACK COAT	210.00	GAL
402112	MINERAL AGGR.IN A.S.T.(CL2)	493.00	TON
402204	PLY.MOD.CAT.EMLS.ASPH.(CRS2P)(SLD.PLY.)	11,264.00	GAL
407161	MA IN ACHM SURFACE(3/8")	131.00	TON
407431	AB(PG64-22)ACHM SURF(3/8")	9.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	184.00	SQFT
718001	REFL.PAINT PVMT.MRK.WH(4")	21,120.00	LF
718101	REFL.PAINT PVMT.MRK.YL(4")	4,752.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE October 16, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA4750

HWY. 158 – CO. RD. 474 (OVERLAY) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 2.99 MILES OF COUNTY ROAD 599 IN MISSISSIPPI COUNTY. THIS PROJECT CONSISTS OF AGGREGATE BASE COURSE, ACHM SURFACE COURSE, ACHM PATCHING, PAVEMENT MARKING, MAINTENANCE OF TRAFFIC AND MISC. ITEMS.

ROUTES: CR 599

COUNTY: MISSISSIPPI

LENGTH: 2.99 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303117	AGGR.BASE COURSE(CLASS 7)	474.00	TON
401011	TACK COAT	3,996.00	GAL
407162	MA IN ACHM SURFACE(1/2")	4,962.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	294.00	TON
412002	COLD MILLING ASPHALT PVMT.	456.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	70.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	176.00	SQFT
718001	REFL.PAINT PVMT.MRK.WH(4")	31,574.00	LF
718101	REFL.PAINT PVMT.MRK.YL(4")	5,842.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA4840

HWY. 79 – NORTH (OVERLAY) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 3.10 MILES OF BETHLEHEM RD. IN MONROE COUNTY. THIS PROJECT CONSISTS OF AGGREGATE BASE COURSE, ACHM SURFACE COURSE, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: BETHLEHEM RD.

COUNTY: MONROE

LENGTH: 3.10 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303117	AGGR.BASE COURSE(CLASS 7)	655.00	TON
401011	TACK COAT	3,666.00	GAL
407162	MA IN ACHM SURFACE(1/2")	4,363.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	274.00	TON
415011	ACHM PATCH.EXIST.RDWY.	20.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	178.00	SQFT
718101	REFL.PAINT PVMT.MRK.YL(4")	17,265.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA5142

HWY. 374 – SOUTH (OVERLAY) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 1.33 MILES OF MCELROY GAP ROAD IN NEWTON COUNTY. THIS PROJECT CONSISTS OF ACHM SURFACE COURSE, AGGREGATE BASE COURSE, ACHM PATCHING, PAVEMENT MARKING, MAINTENANCE OF TRAFFIC, AND MISC ITEMS.

ROUTES: MCELROY GAP RD.

COUNTY: NEWTON

LENGTH: 1.33 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303107	AGGR.BASE COURSE(CLASS 7)	211.00	TON
401011	TACK COAT	1,575.00	GAL
407162	MA IN ACHM SURFACE(1/2")	1,871.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	119.00	TON
412002	COLD MILLING ASPHALT PVMT.	350.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	30.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	152.00	SQFT
718101	REFL.PAINT PVMT.MRK.YL(4")	14,256.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA5352

HWY. 324 – WEST (SURFACING) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO SURFACE APPROXIMATELY 1.70 MILES OF BLUE JAY HOLLOW RD. IN PERRY COUNTY. THIS PROJECT CONSISTS OF RECONSTRUCTED BASE COURSE, DOUBLE ASPHALT SURFACE TREATMENT, PAVEMENT MARKING, MAINTENANCE OF TRAFFIC, AND MISC. ITEMS.

ROUTES: BLUE JAY HOLLOW RD.

COUNTY: PERRY

LENGTH: 1.70 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

305001	RECONSTRUCTED BASE COURSE	90.00	STA
401001	PRIME COAT	8,378.00	GAL
402112	MINERAL AGGR.IN A.S.T.(CL2)	648.00	TON
402204	PLY.MOD.CAT.EMLS.ASPH.(CRS2P)(SLD.PLY.)	14,960.00	GAL
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	132.00	SQFT
718101	REFL.PAINT PVMT.MRK.YL(4")	17,952.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE October 16, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA5453

HWY. 1 – HWY. 39 (RESEAL) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO LEVEL AND SEAL APPROXIMATELY 5.00 MILES OF COUNTY ROAD 600 IN PHILLIPS COUNTY. THIS PROJECT CONSISTS OF ASPHALT SURFACE TREATMENT, ACHM SURFACE COURSE, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: CR 600

COUNTY: PHILLIPS

LENGTH: 5.00 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401011	TACK COAT	600.00	GAL
402112	MINERAL AGGR.IN A.S.T.(CL2)	1,131.00	TON
402214	PLY.MOD.CAT.EMLS.ASPH.(CRS2P)(SLD.PLY.)	25,857.00	GAL
407161	MA IN ACHM SURFACE(3/8")	374.00	TON
407431	AB(PG64-22)ACHM SURF(3/8")	26.00	TON
415011	ACHM PATCH.EXIST.RDWY.	50.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	132.00	SQFT
718001	REFL.PAINT PVMT.MRK.WH(4")	52,800.00	LF
718101	REFL.PAINT PVMT.MRK.YL(4")	12,353.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE October 16, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA6347

HWY. 80 – WALDRON CITY LIMITS (OVERLAY) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 1.57 MILES OF SWEET GUM LN. IN SCOTT COUNTY. THIS PROJECT CONSISTS OF STONE BACKFILL, AGGREGATE BASE COURSE, ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, GEOTEXTILE FABRIC (TYPE SPECIAL), PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: SWEET GUM LN.

COUNTY: SCOTT

LENGTH: 1.57 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

207011	STONE BACKFILL	50.00	TON
303117	AGGR.BASE COURSE(CLASS 7)	249.00	TON
401002	PRIME COAT	22.00	GAL
401011	TACK COAT	2,814.00	GAL
407162	MA IN ACHM SURFACE(1/2")	2,787.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	178.00	TON
412002	COLD MILLING ASPHALT PVMT.	444.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	400.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	162.00	SQFT
625031	GEOTEXTILE FABRIC (TYPE SPECIAL)	55.00	SQYD
718101	REFL.PAINT PVMT.MRK.YL(4")	16,590.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA6651

SEVIER CO. RESEAL NO. 19 (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO SURFACE APPROXIMATELY 3.79 MILES OF BEAR CREEK CUTOFF & APPROXIMATELY 2.75 MILES OF DOG TOWN RD. IN SEVIER COUNTY. THIS PROJECT CONSISTS OF ASPHALT SURFACE TREATMENT, PAVEMENT MARKING, MAINTENANCE OF TRAFFIC, AND MISC. ITEMS.

ROUTES: BEAR CREEK CUTOFF & DOG TOWN RD.

COUNTY: SEVIER

LENGTH: 6.54 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

402111	MINERAL AGGR.IN A.S.T.(CL1)	1,334.00	TON
402214	PLY.MOD.CAT.EMLS.ASPH.(CRS2P)(SLD.PLY.)	38,113.00	GAL
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	500.00	SQFT
718101	REFL.PAINT PVMT.MRK.YL(4")	68,662.00	LF
721002	RAISED PAVEMENT MARKERS-2	251.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE October 16, 2026.