

ARKANSAS DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS

Internet bids for the construction of the following jobs will be received by the Arkansas Department of Transportation at the **STATE HIGHWAY BUILDING** located at **10324 INTERSTATE 30**, southwest of **LITTLE ROCK, ARKANSAS**, until ten o'clock a.m., (10:00 a.m.) and until one thirty p.m., (1:30 p.m.), **November 4, 2026**. Bids will be posted on the Department's website at <http://www.ardot.gov/divisions/program-management/construction-contract-development/construction-contractors/currently-advertised-projects> once the downloading process has been completed.

BIDS FOR THE FOLLOWING PROJECTS ARE DUE AT 10:00 A.M.

JOB NO.	JOB NAME
A10059	HWY. 49 – HWY. 44 (S)
040904	CLEAR CREEK RD. – I-40 (PHASE 1) (F)
A40062	HWY. 8 – SOUTH (S)
050439	HWY. 25 STR. & APPRS. (INDEPENDENCE CO.) (S)
A50052	STONE CO. LINE – HWY. 25 (S)
061922	HWYS. 7 & 70B PED. IMPVTS. (GARLAND CO.) (S)
A70050	HWY. 67 – HWY. 51 (S)
A80050	HWY. 95 – HWY. 124 (S)
A90050	MISSOURI STATE LINE – HWY. 62 (S)
A00103	MONETTE – MISSISSIPPI CO. LINE (S)

BIDS FOR THE FOLLOWING PROJECTS ARE DUE AT 1:30 P.M.

JOB NO.	JOB NAME
110812	HWY. 49 MISSISSIPPI RIVER BRIDGE REHAB. (S)
A20044	HWY. 165 – HWY. 152 (S)
A30049	HWY. 355 – HWY. 278 (S)
A50033	HWY. 67B – HWY. 13 (S)
A60066	HWY. 367 – HWY. 365 (S)
A70049	OUACHITA RIVER – NORTH (S)
A90051	HWY. 412 IMPVTS. (CARROLL & MADISON COS.) (S)
101141	HWYS. 61/140 INTERS. IMPVTS. (OSCEOLA) (S)
BR4401	WAR EAGLE CREEK STR. & APPRS. (S)
FA0314	HWY. 341 SOUTHEAST – STONE CO. LINE (PHASE 2) (S)

Plans, Proposal Documents, and Specifications may be purchased in the Program Management Division at the address noted above during regular business hours until 4:30 the day before the time established for opening of Proposals.

To become an eligible bidder, prospective bidders must be registered to bid in Arkansas with Bid Express. Prospective bidders must also contact the Program Management Division at (501) 569-2261 during regular business hours (or via email at pmd@ardot.gov) between the date the project is advertised and 4:30 p.m. on the day prior to the scheduled bid opening to request to become eligible to bid specific projects. Only prequalified contractors or their authorized representative may request to become an eligible bidder.

Questions pertaining to projects during the advertisement period should be addressed to the Program Management Division at pmd@ardot.gov. The deadline to submit a question is the Wednesday prior to the scheduled letting date. A question submitted after the close of business on the Wednesday prior to the scheduled letting date may not receive a response.

In order to have a bid considered, contractors must furnish a proposal guaranty consisting of either a bidder's bond or a certified or cashier's check in the amount of five percent (5%) of the total amount bid. In order for a bond to be acceptable to the Department, the company issuing the bond must be named in the Department of Treasury Listing of companies holding Certificates of Authority as acceptable sureties on Federal Bonds and as acceptable reinsuring companies. The Underwriting Limitation of the bonding company shall be adhered to. Any excess (between the face amount of the Bond and the Underwriting Limitation) shall be protected by reinsurance provided by an acceptable reinsuring company.

A current directory of certified DBE firms may be obtained on the Department's web site at <https://www.ardot.gov/divisions/equal-employment-opportunity-disadvantaged-business-enterprise/dbe> or may be requested by calling the Department's EEO-DBE Section at (501) 569-2259 or the Program Management Division, Construction Contract Development Section at (501) 569-2261.

It is suggested that successful bidders utilize to the fullest extent practicable the facilities and services of the local offices of the Arkansas Department of Workforce Services to meet their manpower requirements.

These contracts are subject to normal prequalification, licensing and bonding requirements, applicable labor laws, non-discrimination provisions, wage rate laws and other Federal laws including the Fair Labor Standards Acts of 1938. The Work Hours Act of 1962 and Title VI of the Civil Rights Act of 1964 also apply.

The Arkansas Department of Transportation (ARDOT) complies with all civil rights provisions of federal statutes and related authorities that prohibit discrimination in programs and activities receiving federal financial assistance. Therefore, ARDOT does not discriminate on the basis of race, sex, color, age, national origin, religion (not applicable as a protected group under the FMCSA Title VI Program), or disability in the admission, access to and treatment in ARDOT's programs and activities, as well as ARDOT's hiring or employment practices. Complaints of alleged discrimination and inquiries regarding ARDOT's nondiscrimination policies may be directed to the Civil Rights Division, P. O. Box 2261, Little Rock, AR 72203, (501) 569-2298, (Voice/TTY 711), or the following email address: Civil.Rights@ardot.gov

Free language assistance may be available upon request.

This notice is available from the ADA/504/Title VI Coordinator in large print, on audiotape, and in Braille.

The Department reserves the right to reject any or all bids and to waive any formalities.

BY AUTHORITY OF

ARKANSAS STATE HIGHWAY COMMISSION

Philip Taldo, Chairman

NOTICE TO ALL BIDDERS

TO REPORT BID RIGGING ACTIVITIES CALL:

1-800-424-9071

The United States Department of Transportation (DOT) operates the above toll-free "hotline" Monday through Friday, 8:00 a.m. to 5:00 p.m. eastern time. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the "hotline" to report such activities.

The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

ARKANSAS DEPARTMENT OF TRANSPORTATION

110812

HWY. 49 MISSISSIPPI RIVER BRIDGE REHAB. (S)

FEDERAL AID PROJECT NHPP-PRTT-HIPBIP-0054(31)

THE PURPOSE OF THIS PROJECT IS TO REHABILITATE THE MISSISSIPPI RIVER BRIDGE INCLUDING DECK REPLACEMENT AND POLYMER OVERLAY ON HIGHWAY 49 IN PHILLIPS COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL ITEMS, STONE BACKFILL, TRENCHING AND SHOULDER PREPARATION, AGGREGATE BASE COURSE, PORTLAND CEMENT CONCRETE BASE, ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, APPROACH SLABS AND GUTTERS, PORTLAND CEMENT CONCRETE PAVEMENT PATCHING, MAINTENANCE OF TRAFFIC, GUARDRAIL, GEOTEXTILE FABRIC, TRAFFIC SIGNAL ITEMS, MODIFICATION OF EXISTING BRIDGE STRUCTURE, STEEL REPAIR, LIGHTWEIGHT CONCRETE, BRIDGE JACKING, AND MISC. ITEMS.

ROUTES: 49

SECTIONS: 11

COUNTY: PHILLIPS

LENGTH: 1.163 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202042	R&D OF CONCRETE PAVEMENT	32.00	SQYD
202053	R&D OF APPR.SLAB & GUTTERS	2.00	EACH
202132	R&D OF GUARDRAIL	1,604.00	LF
202794	REMOVAL & DISPOSAL OF CONDUIT & CABLE	1.00	L.S.
202795	REMOVAL & DISPOSAL OF ITS EQUIPMENT	1.00	L.S.
202796	REMOVAL & DISPOSAL NAVIGATION LIGHTING	1.00	L.S.
202797	REMOVAL AND DISP OF OBSTRUCTION LIGHTING	1.00	L.S.
207011	STONE BACKFILL	50.00	TON
215011	TRENCH.AND SHOULDER PREP.	5.00	STA
303117	AGGR.BASE COURSE(CLASS 7)	83.00	TON
309510	P.C.CONCRETE BASE-10"	117.00	SQYD
401011	TACK COAT	513.00	GAL
407162	MA IN ACHM SURFACE(1/2")	538.00	TON
407452	AB(PG76-22)ACHM SURF(1/2")	34.00	TON
412002	COLD MILLING ASPHALT PVMT.	4,930.00	SQYD
414011	ASPH.CONC.PATCH-MAINT.	5.00	TON
415011	ACHM PATCH.EXIST.RDWY.	25.00	TON
504031	APPROACH SLABS	94.80	CUYD
504264	APPROACH GUTTERS	18.84	CUYD
507229	P.C.C.P. PATCH-9"	32.00	SQYD
601001	MOBILIZATION	1.00	L.S.
602011	FURNISHING FIELD OFFICE	1.00	EACH
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
603012	TRAFFIC CONTROL SUPERVISOR	1.00	L.S.
604003	SIGNS	612.00	SQFT
604010	CONST PROJ INFO SIGN UPDATE	4.00	EACH
604013	BARRICADES	80.00	LF
604023	TRAFFIC DRUMS	31.00	EACH
604031	FURN.&INSTL.PRCST.CONC.BARR.	5,266.00	LF
604036	RELO.PRECAST CONCRETE BARRIER	8,466.00	LF
604041	CONST.PAVEMENT MARKINGS	25,297.00	LF
604051	REMOVABLE CONST.PVMT.MRK.	8,822.00	LF

604061	REMOVAL OF PERM.PVMT.MRK.	800.00	LF
604083	VERTICAL PANELS	158.00	EACH
604094	MOTORIST ASSISTANCE PATROL	1.00	L.S.
604098	WRECKER SERVICE	1.00	L.S.
604100	PORTABLE CAMERA TRAILER	2.00	EACH
604103	DEVICE RELOCATION	4.00	EACH
604106	FURN. & INSTL. VARIABLE MESSAGE SIGN	1.00	EACH
604111	VMSS MOBILIZATION	1.00	L.S.
604112	VMSS OPERATION	36.00	MNTH
604115	WARNING SIGN WITH FLASHING BEACON	6.00	EACH
604161	FURNISH & INSTALL BARRIER (SPECIAL	240.00	LF
604162	RELOCATE PRECAST BARRIER (SPECIAL)	240.00	LF
617005	GUARDRAIL (TYPE A)	1,450.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	2.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	2.00	EACH
620001	LIME	1.00	TON
620011	SEEDING	0.50	ACRE
620022	MULCH COVER	1.00	ACRE
620030	WATER	61.20	MGAL
621001	TEMPORARY SEEDING	0.50	ACRE
621111	SEDIMENT REMOVAL & DISPOSAL	12.00	CUYD
621151	ROCK DITCH CHECKS	18.00	CUYD
621168	FILTER SOCK (12")	1,584.00	LF
621173	WATTLE (20")	54.00	LF
623001	SECOND SEEDING APPLICATION	0.50	ACRE
625009	GEOTEXTILE FABRIC (TYPE 9)	33.00	SQYD
701252	EQUIPMENT CABINET, TYPE B	3.00	EACH
701603	PORTABLE TRAFFIC SIGNAL SYSTEM-ACTUATED	156.00	WEEK
701722	ETHERNET SWITCH, T100 HARDENED (8-PORT)	7.00	EACH
701751	E-NET CABLE (EXTERIOR CAT 5E)	1,340.00	LF
702094	CELLULAR MODEM	7.00	EACH
702405	TRAFFIC TIMER - COUNTDOWN	156.00	WEEK
704410	ROAD WEATHER INFORMATION SYSTEM	2.00	EACH
704411	PTZ CAMERA SYSTEM	16.00	EACH
708251	ELEC. COND.-IN-CONDUIT(3C/8 AWG EGC)	8,260.00	LF
709034	GALVANIZED STEEL CONDUIT (2")	8,260.00	LF
719002	THERMO.PVMT.MARK.WH(6")	13,015.00	LF
719102	THERMO.PVMT.MARK.YL(6")	12,282.00	LF
719201	THERMO.PVMT.MARK.(WORD)	2.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	4.00	EACH
721002	RAISED PAVEMENT MARKERS-2	98.00	EACH
724401	BRIDGE POST MOUNTED SIGN SUPPORT	2.00	EACH
725011	G.SIGN-ROADSIDE MOUNTED(D.A.L)	215.00	SQFT
728031	BARRIER WALL DELINEATOR	2,080.00	EACH
731071	TEMP. IMPACT ATTEN. BARR.	8.00	EACH
731072	TEMP. IMPACT ATTEN. BARRIER (REPAIR)	16.00	EACH
731075	TEMP. IMPACT ATTENUATION BARRIER (RELO)	64.00	EACH
800101	TEMPORARY FALSEWORK (SITE NO. 1)	1.00	L.S.
800201	BRIDGE JACKING (SITE NO. 1)	1.00	L.S.
802112	CLASS S CONCRETE-BRIDGE	11.80	CUYD
802122	CLASS S(AE) CONCRETE-BRIDGE	2.50	CUYD
802207	LIGHTWEIGHT AGGREGATE CONCRETE (AE)	2,552.20	CUYD
803004	CLASS 2 PROTECTIVE SURFACE TREATMENT	2,309.80	SQYD
804004	REINFORCING STEEL-ROADWAY (GRADE 60)	12,536.00	LB

804015	LCCR RE-STEEL-BRIDGE (GRADE 100)	413,880.00	LB
804023	EPOXY COAT.REINF.STEEL-GR 60	115,180.00	LB
807230	STR STEEL IN GIRDER SPANS (A709 GR36)	33,630.00	LB
807234	STR.ST.PL.GRD.SPN(A709,GR50W)	3,720.00	LB
807244	STR STEEL IN TRUSS SPANS (A709 GR36)	267,350.00	LB
807245	STR STEEL IN TRUSS SPANS (A709 GR50W)	3,870.00	LB
807281	REPAIR TYPE A: FLOOR BEAM TOP FLANGE	1.00	EACH
807282	REPAIR TYPE B: FLOOR BEAM BOTTOM FLANGE	11.00	EACH
807283	REPAIR TYPE C: FLOOR BEAM WEB	10.00	EACH
807284	REPAIR TYPE D: FLOOR BEAM STIFFENER	48.00	EACH
807285	REPAIR E: STRINGER PIN AND HANGER	9.00	EACH
807286	REPAIR F: RIVET REPLACEMENTS	550.00	EACH
807287	REPAIR G: STRINGER CONNECT ANGLE	2.00	EACH
807288	REPAIR H: CROSS BEAM REPLACEMENT	51.00	EACH
807400	CRACK ARREST HOLE	1.00	EACH
808002	ELASTOMERIC BEARINGS	5,722.00	CUIN
810030	PREFORMED SILICONE JOINT	596.00	LF
820012	CL&PAINT EXST.STR.STEEL-TY 2	6,484.00	TON
820071	DISP.OF HAZ.WASTE-SITE 1	1.00	L.S.
821001	MOD.EXISTING BR.STR(BR NO. 02899)	1.00	L.S.
821072	SHORING (SITE NO. 1)	1.00	L.S.
821300	SHORING TYPE 1: MAIN TRUSS SPAN	1.00	L.S.
821301	SHORING 2: MAIN TRUSS WIND LOCK	1.00	L.S.
821302	SHORING 3: MAIN TRUSS STRINGER	1.00	L.S.
821303	SHORING 4: APPROACH SPAN FLOOR BEAM	1.00	L.S.
821304	SHORING 5: APPROACH SPAN WIND LOCK	1.00	L.S.
822011	BRIDGE DECK REPAIR FOR POLYMER OVERLAYS	2,923.90	SQFT
822020	POLYMER OVERLAY	16,167.00	SQYD
901003	NAVIGATION LIGHTING SYSTEM	1.00	L.S.
901216	ITS JUNCTION BOX (24X24X8)	22.00	EACH
901600	OBSTRUCTION LIGHTING SYSTEM	1.00	L.S.
901601	RADIO INTERCONNECT BROADBAND SHORT RANGE	13.00	EACH
901603	TERMINAL SERVER	1.00	EACH
901604	VIDEO MANAGEMENT SYSTEM INTEGRATION	1.00	L.S.

THIS PROPOSAL CONTAINS THE JOB SPECIAL PROVISION "SITE USE (A+C METHOD)-CALENDAR DAY CONTRACT" FOR BIDDING IN WHICH THE BIDDER WILL DETERMINE THE NUMBER OF CALENDAR DAYS TO COMPLETE THE PROJECT.

THE NUMBER OF TRAINEES REQUIRED FOR THIS PROJECT IS 3.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A10059

HWY. 49 – HWY. 44 (S)

FEDERAL AID PROJECT STPR-0054(38)

THE PURPOSE OF THIS PROJECT IS TO PLACE CHIP SEAL AND FOG SEAL APPROXIMATELY 9.670 MILES OF HIGHWAY 85 IN PHILLIPS COUNTY. THIS PROJECT CONSISTS OF EARTHWORK, TRENCHING AND SHOULDER PREPARATION, AGGREGATE BASE COURSE, FOG SEAL, ASPHALT SURFACE TREATMENT, ACHM BINDER AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, APPROACH GUTTERS, MAINTENANCE OF TRAFFIC, GUARDRAIL, EROSION CONTROL, RUMBLE STRIPS AND STRIPES, LOOP WIRING, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 85

SECTIONS: 1

COUNTY: PHILLIPS

LENGTH: 9.67 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

210213	UNCLASSIFIED EXCAVATION	2.00	CUYD
215011	TRENCH.AND SHOULDER PREP.	482.00	STA
303117	AGGR.BASE COURSE(CLASS 7)	5,067.00	TON
401005	FOG SEAL (TYPE 2)	18,081.00	GAL
401011	TACK COAT	11,923.00	GAL
402111	MINERAL AGGR.IN A.S.T.(CL1)	2,782.00	TON
402202	POLY.MOD.CAT.EMULS.ASPH(CRS2P)	55,634.00	GAL
406161	M.A. IN ACHM BINDER(1")	7,610.00	TON
406412	A.B.(PG70-22)ACHM BINDER(1")	342.00	TON
407162	MA IN ACHM SURFACE(1/2")	6,341.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	376.00	TON
412002	COLD MILLING ASPHALT PVMT.	444.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	300.00	TON
504264	APPROACH GUTTERS	25.20	CUYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	1,008.00	SQFT
604023	TRAFFIC DRUMS	20.00	EACH
604041	CONST.PAVEMENT MARKINGS	180,150.00	LF
604061	REMOVAL OF PERM.PVMT.MRK.	522.00	LF
617005	GUARDRAIL (TYPE A)	325.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	4.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	4.00	EACH
620011	SEEDING	0.01	ACRE
620022	MULCH COVER	0.01	ACRE
620030	WATER	10.00	MGAL
621021	SILT FENCE	1,000.00	LF
621031	SAND BAG DITCH CHECKS	20.00	BAG
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642001	RUMBLE STRIPS IN ASPHALT SHOULDERS	2,585.00	LF
642011	RUMBLE STRIPES IN ASPHALT SHOULDERS	79,107.00	LF
701603	PORTABLE TRAFFIC SIGNAL SYSTEM-ACTUATED	6.00	WEEK
704036	LOOP WIRING CLASS III (1C/16 A.W.G.)	210.00	LF
719002	THERMO.PVMT.MARK.WH(6")	96,308.00	LF
719006	THERMO.PVMT.MARK.WH(24")	20.00	LF

719102	THERMO.PVMT.MARK.YL(6")	41,350.00	LF
719201	THERMO.PVMT.MARK.(WORD)	2.00	EACH
721002	RAISED PAVEMENT MARKERS-2	602.00	EACH
804003	REINF.STEEL-ROADWAY (GR 60)	2,892.00	LB

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A20044

HWY. 165 – HWY. 152 (S)

FEDERAL AID PROJECT STPR-0001(103)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 23.707 MILES OF HIGHWAY 130 IN ARKANSAS COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL OF GUARDRAIL, TRENCHING AND SHOULDER PREPARATION, AGGREGATE BASE COURSE, ACHM BINDER AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, APPROACH GUTTERS, MAINTENANCE OF TRAFFIC, GUARDRAIL, EROSION CONTROL, RUMBLE STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 130

SECTIONS: 6

COUNTY: ARKANSAS

LENGTH: 23.707 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202132	R&D OF GUARDRAIL	1,866.00	LF
215011	TRENCH.AND SHOULDER PREP.	1,196.00	STA
303117	AGGR.BASE COURSE(CLASS 7)	9,472.00	TON
401011	TACK COAT	33,076.00	GAL
406161	M.A. IN ACHM BINDER(1")	12,090.00	TON
406412	A.B.(PG70-22)ACHM BINDER(1")	610.00	TON
407162	MA IN ACHM SURFACE(1/2")	41,909.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	2,533.00	TON
412002	COLD MILLING ASPHALT PVMT.	8,446.00	SQYD
414011	ASPH.CONC.PATCH-MAINT.	625.00	TON
415011	ACHM PATCH.EXIST.RDWY.	800.00	TON
504264	APPROACH GUTTERS	48.54	CUYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	4,139.00	SQFT
604010	CONST PROJ INFO SIGN UPDATE	2.00	EACH
604023	TRAFFIC DRUMS	80.00	EACH
604041	CONST.PAVEMENT MARKINGS	413,168.00	LF
604051	REMOVABLE CONST.PVMT.MRK.	5,599.00	LF
604083	VERTICAL PANELS	80.00	EACH
617005	GUARDRAIL (TYPE A)	3,382.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	26.00	EACH
620001	LIME	23.00	TON
620011	SEEDING	11.50	ACRE
620022	MULCH COVER	23.00	ACRE
620030	WATER	1,407.60	MGAL
621001	TEMPORARY SEEDING	11.50	ACRE
621021	SILT FENCE	2,500.00	LF
621031	SAND BAG DITCH CHECKS	700.00	BAG
621111	SEDIMENT REMOVAL & DISPOSAL	93.00	CUYD
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642011	RUMBLE STRIPES IN ASPHALT SHOULDERS	179,022.00	LF
642102	CENTERLINE RUMBLE STRIPES IN ASPH. RDWYS	111,888.00	LF
701603	PORTABLE TRAFFIC SIGNAL SYSTEM-ACTUATED	21.00	WEEK

718004	REFL.PAINT PVMT.MRK.WH(10")	130.00	LF
718104	REFL.PAINT PVMT.MRK.YL(10")	202.00	LF
719002	THERMO.PVMT.MARK.WH(6")	251,328.00	LF
719006	THERMO.PVMT.MARK.WH(24")	110.00	LF
719102	THERMO.PVMT.MARK.YL(6")	161,840.00	LF
721002	RAISED PAVEMENT MARKERS-2	1,578.00	EACH
734011	BRIDGE END TERMINAL	2.00	EACH
804003	REINF.STEEL-ROADWAY (GR 60)	3,306.00	LB

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.

THE NUMBER OF TRAINEES REQUIRED FOR THIS PROJECT IS 1.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A30049

HWY. 355 – HWY. 278 (S)

FEDERAL AID PROJECT STPR-2931(5)

THE PURPOSE OF THIS PROJECT IS TO MILL AND OVERLAY APPROXIMATELY 18.474 MILES OF HIGHWAY 73 IN HEMPSTEAD AND HOWARD COUNTIES. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL OF GUARDRAIL, AGGREGATE BASE COURSE, ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, GUARDRAIL, EROSION CONTROL, RUMBLE STRIPS, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 73

SECTIONS: 0, 1, & 2

COUNTY: HEMPSTEAD & HOWARD

LENGTH: 18.474 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202132	R&D OF GUARDRAIL	1,736.00	LF
303117	AGGR.BASE COURSE(CLASS 7)	2,380.00	TON
401011	TACK COAT	45,382.00	GAL
407162	MA IN ACHM SURFACE(1/2")	40,816.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	2,467.00	TON
412002	COLD MILLING ASPHALT PVMT.	287,386.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	300.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	2,189.00	SQFT
604023	TRAFFIC DRUMS	46.00	EACH
604041	CONST.PAVEMENT MARKINGS	482,297.00	LF
617005	GUARDRAIL (TYPE A)	1,600.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	16.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	8.00	EACH
621021	SILT FENCE	3,600.00	LF
621111	SEDIMENT REMOVAL & DISPOSAL	133.00	CUYD
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642001	RUMBLE STRIPS IN ASPHALT SHOULDERS	187,969.00	LF
701603	PORTABLE TRAFFIC SIGNAL SYSTEM-ACTUATED	8.00	WEEK
718002	REFL.PAINT PVMT.MRK.WH(6")	195,487.00	LF
718102	REFL.PAINT PVMT.MRK.YL(6")	195,487.00	LF
721002	RAISED PAVEMENT MARKERS-2	1,225.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.

ARKANSAS DEPARTMENT OF TRANSPORTATION

040904

CLEAR CREEK RD. – I-40 (PHASE 1) (F)

FEDERAL AID PROJECT CPFCDs-NHPP-40-1(268)

THE PURPOSE OF THIS PROJECT IS TO CONSTRUCT GRADING AND STRUCTURES OF A FOUR - LANE INTERSTATE FACILITY, INCLUDING IMPROVEMENTS TO THE INTERSTATE 40 AND 49 INTERCHANGE IN CRAWFORD COUNTY. THIS PROJECT CONSISTS OF CLEARING AND GRUBBING, REMOVAL AND DISPOSAL ITEMS, STONE BACKFILL, EARTHWORK, SELECT GRANULAR BACKFILL, ROCK FILL, TRENCHING AND SHOULDER PREPARATION, AGGREGATE BASE COURSE, CEMENT IN CEMENT STABILIZED CRUSHED STONE BASE COURSE, PROCESSING CEMENT STABILIZED CRUSHED STONE BASE COURSE, ACHM BASE, BINDER, AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, APPROACH SLABS AND GUTTERS, MAINTENANCE OF TRAFFIC, CONCRETE DITCH PAVING, MINOR DRAINAGE, EROSION CONTROL, PAVEMENT MARKING, ITS ITEMS, ILLUMINATION ITEMS, SIGN ITEMS, CONSTRUCT TWO CONTINUOUS PLATE GIRDER BRIDGES (TOTAL LENGTH 1031.95'), CONSTRUCT FIVE RC BOX CULVERTS (TOTAL LENGTH 296.14'), AND MISC. ITEMS.

ROUTES: 549

SECTIONS: 6

COUNTY: CRAWFORD

LENGTH: 5.028 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

201011	CLEARING	282.00	STA
201111	GRUBBING	282.00	STA
202011	R&D OF FENCE	27,005.00	LF
202017	R&D OF GATES	11.00	EACH
202062	R&D OF CONCRETE DRIVEWAYS	1,834.00	SQYD
202082	R&D OF FOUNDATIONS	3.00	SQYD
202096	R&D OF PIPE CULVERTS	26.00	EACH
202097	R&D OF BOX CULVERTS	4.00	EACH
202132	R&D OF GUARDRAIL	510.00	LF
202154	REMOVAL AND DISPOSAL OF WRSF	2,114.00	LF
202156	R&D OF OVERHEAD SIGN STRUCTURE	1.00	EACH
202171	R&D OF BUILDINGS	9.00	EACH
202191	R&D OF SIGNS	43.00	EACH
207011	STONE BACKFILL	16,315.00	TON
210213	UNCLASSIFIED EXCAVATION	452,452.00	CUYD
210433	SELECT GRANULAR BACKFILL	7,827.00	CUYD
210611	COMPACTED EMBANKMENT	1,851,230.00	CUYD
210631	ROCK FILL	209,405.00	CUYD
210672	REMOVING AND REPLACING TOPSOIL	26,932.00	CUYD
210702	SOIL STABILIZATION	2,500.00	TON
215011	TRENCH.AND SHOULDER PREP.	167.00	STA
303117	AGGR.BASE COURSE(CLASS 7)	53,393.00	TON
308021	AGGR.CMNT.STAB.CRSHD.STN.BS.CRS.	13,366.00	TON
308203	CEMENT IN CMNT.STAB.CRSHD.STN.BS	557.00	TON
308204	PROCESS.CMNT.STAB.CRSHD.STN.BS.	39,779.00	SQYD
401011	TACK COAT	6,744.00	GAL
405161	M.A. IN ACHM BASE COURSE(1.5")	8,689.00	TON
405412	A.B.(PG70-22)ACHM BASE(1.5")	308.00	TON
405422	A.B.(PG76-22)ACHM BASE(1.5")	45.00	TON

406161	M.A. IN ACHM BINDER(1")	12,673.00	TON
406412	A.B.(PG70-22)ACHM BINDER(1")	514.00	TON
406422	A.B.(PG76-22)ACHM BINDER(1")	42.00	TON
407162	MA IN ACHM SURFACE(1/2")	13,246.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	552.00	TON
407452	AB(PG76-22)ACHM SURF(1/2")	190.00	TON
412002	COLD MILLING ASPHALT PVMT.	817.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	50.00	TON
501209	P.C.C.PAVEMENT-9"	35,156.00	SQYD
504031	APPROACH SLABS	775.70	CUYD
504264	APPROACH GUTTERS	88.60	CUYD
505011	P.C.CONCRETE DRIVEWAY	303.00	SQYD
506001	P.C.CONCRETE CORRUGATIONS	163.00	SQYD
601001	MOBILIZATION	1.00	L.S.
602002	FURNISHING FIELD LAB.	1.00	EACH
602011	FURNISHING FIELD OFFICE	1.00	EACH
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
603024	24" TEMPORARY CULVERT	861.00	LF
603048	48" TEMPORARY CULVERT	296.00	LF
604003	SIGNS	1,593.00	SQFT
604005	SIGNS LEFT IN PLACE	20.00	SQFT
604010	CONST PROJ INFO SIGN UPDATE	3.00	EACH
604013	BARRICADES	64.00	LF
604015	BARRICADES LEFT IN PLACE	48.00	LF
604023	TRAFFIC DRUMS	217.00	EACH
604031	FURN.&INSTL.PRCST.CONC.BARR.	14,257.00	LF
604033	FURN,INSTL,&LIP PRCST.CON.BAR.	640.00	LF
604036	RELO.PRECAST CONCRETE BARRIER	22,587.00	LF
604041	CONST.PAVEMENT MARKINGS	56,147.00	LF
604051	REMOVABLE CONST.PVMT.MRK.	121,392.00	LF
604061	REMOVAL OF PERM.PVMT.MRK.	3,222.00	LF
604078	PORT.CHANGEABLE MESSAGE SIGN	156.00	WEEK
604096	PORT.CONSTRUCTION LIGHTING	90.00	DAY
604101	AWIS MOBILIZATION	1.00	L.S.
604102	AWIS OPERATION	36.00	MNTH
604103	DEVICE RELOCATION	60.00	EACH
604104	FURN. & INSTL. CLSD. CIRCT. TV. SYS.	3.00	EACH
604106	FURN. & INSTL. VARIABLE MESSAGE SIGN	3.00	EACH
604107	FURN. & INSTL.VEHICLE DETECTION SYSTEM	12.00	EACH
604160	MOBILE SPEED NOTIFICATION SYSTEM SPECIAL	1.00	EACH
605012	CONC.DITCH PAVING(TYPE B)	5,747.00	SQYD
605601	18" R.C.PIPE CULVERTS(CL.3)	134.00	LF
605606	24" R.C.PIPE CULVERTS(CL.3)	1,714.00	LF
605611	30" R.C.PIPE CULVERTS(CL.3)	928.00	LF
605616	36" R.C.PIPE CULVERTS(CL.3)	198.00	LF
605858	24" FES R.C.PIPE CLVT.	24.00	EACH
605860	30" FES R.C.PIPE CLVT.	12.00	EACH
605862	36" FES R.C.PIPE CLVT.	2.00	EACH
606002	CULVERT CLEAN OUT	7.00	EACH
606701	12" SIDE DRAIN	524.00	LF
606703	18" SIDE DRAIN	284.00	LF
606704	24" SIDE DRAIN	560.00	LF
606994	SELECTED PIPE BEDDING	5,209.00	CUYD
609126	DROP INLETS (TYPE N2)	5.00	EACH

609127	DROP INLETS (TYPE N3)	8.00	EACH
609136	DROP INLETS (TYPE RM)	14.00	EACH
609138	DROP INLETS (TYPE ST)	2.00	EACH
609142	DROP INLETS (TYPE TM)	15.00	EACH
611008	4" PIPE UNDERDRAINS	24,386.00	LF
611013	UNDERDRAIN OUTLET PROTECTORS	112.00	EACH
611034	UNDERDRAIN VIDEO INSPECTION	4,942.00	LF
611104	FLUSHING UNDERDRAIN	4,942.00	LF
614001	CONCRETE SPILLWAY (TYPE A)	13.00	EACH
617005	GUARDRAIL (TYPE A)	11,042.00	LF
617105	TERMINAL ANCHOR POSTS (TYPE 1)	7.00	EACH
617312	GUARDRAIL TERMINAL (TYPE 2)	17.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	14.00	EACH
618351	WIRE ROPE SAFETY FENCE	1,512.00	LF
618353	WIRE ROPE SAFETY FENCE MAINT. MATERIALS	1.00	L.S.
618354	WIRE ROPE SAFETY FENCE (POST REPAIR)	50.00	EACH
619025	WIRE FENCE (TYPE A)	49,590.00	LF
620001	LIME	598.00	TON
620011	SEEDING	298.83	ACRE
620022	MULCH COVER	1,223.29	ACRE
620030	WATER	49,382.60	MGAL
621001	TEMPORARY SEEDING	924.46	ACRE
621021	SILT FENCE	56,990.00	LF
621031	SAND BAG DITCH CHECKS	6,886.00	BAG
621041	DIVERSION DITCH	7,232.00	LF
621071	SEDIMENT BASIN	5,533.00	CUYD
621101	OBLITERATION OF SEDIMENT BASIN	5,533.00	CUYD
621111	SEDIMENT REMOVAL & DISPOSAL	8,224.00	CUYD
621131	PIPE FOR SLOPE DRAINS	1,615.00	LF
621151	ROCK DITCH CHECKS	801.00	CUYD
621168	FILTER SOCK (12")	1,450.00	LF
621173	WATTLE (20")	25,977.00	LF
621181	TRIANGULAR SILT DIKE	3,230.00	LF
623001	SECOND SEEDING APPLICATION	298.83	ACRE
624001	SOLID SODDING	3,397.00	SQYD
625008	GEOTEXTILE FABRIC (TYPE 8)	75,948.00	SQYD
625010	GEOTEXTILE FABRIC (TYPE 10)	101,554.00	SQYD
625031	GEOTEXTILE FABRIC (TYPE SPECIAL)	39,779.00	SQYD
631048	CONC.BARR.WALL(MEDIAN TYPE SPEC.)	101.00	LF
631173	CONC.BARR.WALL(SIDE TYPE A)	3,007.00	LF
631177	CONC.BARR.WALL(SIDE TYPE E)	51.00	LF
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
636001	BRIDGE CONSTRUCTION CONTROL	1.00	L.S.
637001	MAILBOXES	10.00	EACH
637017	MAILBOX SUPPORTS (SINGLE)	10.00	EACH
642001	RUMBLE STRIPS IN ASPHALT SHOULDERS	8,003.00	LF
642002	RUMBLE STRIPS IN P.C.C.SHOULDERS	484.00	LF
708440	ELEC COND (ROADWAY) (2C/3 AWG EGC)	3,621.00	LF
708441	ELEC COND (ROAD) (2C/4)	3,022.00	LF
708442	ELEC COND (ROAD) (2C/8)	4,370.00	LF
708443	ELEC COND FOR LUMN (ROAD)	504.00	LF
709007	GALVANIZED STEEL CONDUIT (4")	2,706.00	LF
710003	NON-METALLIC CONDUIT (1.5")	4,935.00	LF
710004	NON-METALLIC CONDUIT (2")	6,862.00	LF

710026	NON-METALLIC CONDUIT (4")	224.00	LF
711117	CONCRETE PULL BOX (TYPE 2 HD)	63.00	EACH
711506	FIBER OPTIC CONCRETE PULL BOX (TYP 5 HD)	4.00	EACH
711550	ITS FIBER JUNCTION BOX	10.00	EACH
714642	HIGH MAST ILL. ASMBLY(150'-6)	1.00	EACH
714680	HIGH MAST ILLUM. ASMBLY (120-6 LMNR)	3.00	EACH
714681	HIGH MAST ILLMN ASMBLY (120-6 LMN-PAD)	1.00	EACH
714682	HIGH MAST ILLMN ASMBLY (120-6 LMN-PED)	4.00	EACH
714684	HIGH MAST ILLMN ASMBLY (100-6 LUMNR)	1.00	EACH
714685	HIGH MAST SERVICE PLATFORM	4.00	EACH
714689	METAL GRATE FOR PLATFORM	886.20	SQFT
714856	RDWY ILLMN (15400 LMN, CBRA, BRKAWY, 30)	6.00	EACH
715111	PED TYPE SERV POINT ASSEMBLY (100 AMP)	5.00	EACH
718102	REFL.PAINT PVMT.MRK.YL(6")	4,278.00	LF
719502	ENHANCED THERMO. PVMT. MRK. WH (6")	18,996.00	LF
719505	ENHANCED THERMO. PVMT. MRK. WH (12")	3,066.00	LF
719602	ENHANCED THERMO. PVMT. MRK. YL (6")	16,547.00	LF
721002	RAISED PAVEMENT MARKERS-2	619.00	EACH
724022	STEEL O.H.SIGN STRUCTURE (OH-049-RAMP-100)	1.00	EACH
724023	STEEL O.H.SIGN STRUCTURE (OH-049-101)	1.00	EACH
724024	STEEL O.H.SIGN STRUCTURE (OH-049-103)	1.00	EACH
724025	STEEL O.H.SIGN STRUCTURE (OH-049-RAMP-106)	1.00	EACH
724227	STEEL CANTILEVER SIGN STR.(OC-049-104)	1.00	EACH
724228	STEEL CANTILEVER SIGN STR.(OC-049-102)	1.00	EACH
725003	G.SIGN-ROADSIDE MOUNT(DMNTBL)	142.00	SQFT
726002	STANDARD SIGN	583.00	SQFT
727004	EXIT NO.PANEL(TYPE A)	20.00	SQFT
729005	CHANNEL POST SIGN SUP-U 1	6.00	EACH
730202	BRKAWAY SIGN SUPPORT-TYPE G-2	3,149.00	LB
730499	OMNI-DIR.BRKAWAY SIGN SUPPORT-TYPE G-1	15.00	EACH
730500	OMNI-DIR.BRKAWAY SIGN SUPPORT-TYPE G-2	6.00	EACH
730502	OMNI-DIR.BRKAWAY SIGN SUPPORT-TYPE G2-1	9.00	EACH
730503	OMNI-DIR.BRKAWAY SIGN SUPPORTS-TYPE G2-2	2.00	EACH
731071	TEMP. IMPACT ATTEN. BARR.	22.00	EACH
731072	TEMP. IMPACT ATTEN. BARRIER (REPAIR)	22.00	EACH
732011	CRASH CUSHION	2.00	EACH
801001	UNCLASS.EXCAV.FOR STRS-BR	790.00	CUYD
801101	UNCLASS.EXCAV.FOR STRS-RDWY.	7,440.00	CUYD
802012	CLASS 5 CONCRETE-ROADWAY	14,815.84	CUYD
802112	CLASS 5 CONCRETE-BRIDGE	2,228.50	CUYD
802122	CLASS 5(AE) CONCRETE-BRIDGE	4,167.10	CUYD
802222	RETAINING WALL	4,693.00	SQFT
802226	TEMPORARY RETAINING WALL	9,194.00	SQFT
802229	ARCHITECTURAL FINISH	4,302.00	SQFT
802951	TEXTURED COATING FINISH	4,065.00	SQYD
803004	CLASS 2 PROTECTIVE SURFACE TREATMENT	15,879.80	SQYD
804003	REINF.STEEL-ROADWAY (GR 60)	1,704,043.00	LB
804013	REINF.STEEL-BRIDGE (GR 60)	440,990.00	LB
804023	EPOXY COAT.REINF.STEEL-GR 60	981,390.00	LB
805024	STEEL PILING (HP 14X73)	5,545.00	LF
805041	CORING DRILLED SHAFT	353.00	LF
805056	DRILLED SHAFT (54" DIAMETER)	1,405.00	LF
805084	PERMANENT STEEL CASING(60")	833.00	LF
805504	PREBORING	4,500.00	LF

805709	CROSSHOLE SONIC LOGGING (54" DIA.)	48.00	EACH
807232	STR.ST.PL.GRD.SPN(M270-GR50)	1,560,590.00	LB
807233	STR.ST.PL.GRD.SPN(M270-GR50W)	3,582,580.00	LB
807301	PAINTING STRUCTURAL STEEL	1,111.80	TON
808002	ELASTOMERIC BEARINGS	144,893.00	CUIN
809013	ARM. JT W/NEOPRENE STRIP SEAL	252.00	LF
809015	SILICONE JOINT SEALANT	171.00	LF
812004	BRIDGE NAME PLATE (TYPE D)	6.00	EACH
816003	FILTER BLANKET	14,858.00	SQYD
816111	DUMPED RIPRAP	7,476.00	CUYD
816121	CONCRETE RIPRAP	791.00	CUYD

24" PIPE CULVERTS ALTERNATE - BID ONE ITEM ONLY

605606	24" R.C.PIPE CULVERTS(CL.3)	124.00	LF
605691	24" ASPH.C.C.ST.PIPE CLVT.-16G	130.00	LF
605706	24" AL.C.C.ST.PIPE CLVT.-16G	130.00	LF
605725	24" P.P.M.C.C.ST.PIPE CLVT.-16G	130.00	LF
605842	24" HIGH DENSITY POLYETHYLENE PIPE	130.00	LF
605848	24" PVC PIPE	130.00	LF

36" PIPE CULVERTS ALTERNATE - BID ONE ITEM ONLY

605616	36" R.C.PIPE CULVERTS(CL.3)	166.00	LF
605694	36" ASPH.C.C.ST.PIPE CLVT.-14G	172.00	LF
605708	36" AL.C.C.ST.PIPE CLVT.-14G	172.00	LF
605729	36" P.P.M.C.C.ST.PIPE CLVT.-14G	172.00	LF
605844	36" HIGH DENSITY POLYETHYLENE PIPE	172.00	LF
605850	36" PVC PIPE	172.00	LF

16' GATES ALTERNATE - BID ONE ITEM ONLY

619332	16' STEEL GATES	24.00	EACH
619430	16' ALUMINUM GATES	24.00	EACH

THIS PROPOSAL CONTAINS THE JOB SPECIAL PROVISION "SITE USE (A+C METHOD)-CALENDAR DAY CONTRACT" FOR BIDDING IN WHICH THE BIDDER WILL DETERMINE THE NUMBER OF CALENDAR DAYS TO COMPLETE THE PROJECT.

THE NUMBER OF TRAINEES REQUIRED FOR THIS PROJECT IS 14.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A40062

HWY. 8 – SOUTH (S)

FEDERAL AID PROJECT STPSC-0057(35)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 11.620 MILES OF HIGHWAY 375 IN POLK COUNTY. THIS PROJECT CONSISTS OF TRENCHING AND SHOULDER PREPARATION, ACHM BINDER AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, EROSION CONTROL, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 375

SECTIONS: 1

COUNTY: POLK

LENGTH: 11.62 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

215011	TRENCH.AND SHOULDER PREP.	227.00	STA
303117	AGGR.BASE COURSE(CLASS 7)	2,704.00	TON
401011	TACK COAT	19,298.00	GAL
406161	M.A. IN ACHM BINDER(1")	2,238.00	TON
406412	A.B.(PG70-22)ACHM BINDER(1")	115.00	TON
407162	MA IN ACHM SURFACE(1/2")	23,875.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	1,470.00	TON
412002	COLD MILLING ASPHALT PVMT.	2,388.00	SQYD
414011	ASPH.CONC.PATCH-MAINT.	300.00	TON
415011	ACHM PATCH.EXIST.RDWY.	1,000.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	901.00	SQFT
604041	CONST.PAVEMENT MARKINGS	250,000.00	LF
621031	SAND BAG DITCH CHECKS	475.00	BAG
621169	FILTER SOCK (18")	500.00	LF
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
637001	MAILBOXES	25.00	EACH
637017	MAILBOX SUPPORTS (SINGLE)	25.00	EACH
718002	REFL.PAINT PVMT.MRK.WH(6")	123,000.00	LF
718006	REFL.PAINT PVMT.MRK.WH(24")	30.00	LF
718102	REFL.PAINT PVMT.MRK.YL(6")	123,000.00	LF
721002	RAISED PAVEMENT MARKERS-2	770.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.

ARKANSAS DEPARTMENT OF TRANSPORTATION

050439

HWY. 25 STR. & APPRS. (INDEPENDENCE CO.) (S)

FEDERAL AID PROJECT NHPP-0032(44)

THE PURPOSE OF THIS PROJECT IS TO REPLACE ONE BRIDGE ON HIGHWAY 25 IN INDEPENDENCE COUNTY. THIS PROJECT CONSISTS OF CLEARING AND GRUBBING, REMOVAL AND DISPOSAL ITEMS, EARTHWORK, AGGREGATE BASE COURSE, ACHM BINDER, AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, APPROACH SLAB AND GUTTERS, MAINTENANCE OF TRAFFIC, GUARDRAIL, EROSION CONTROL, RUMBLE STRIPES, CONSTRUCT ONE BRIDGE NO. 07721 (196.00'), AND MISC. ITEMS.

ROUTES: 25

SECTIONS: 5

COUNTY: INDEPENDENCE

LENGTH: 0.434 mile in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

201011	CLEARING	24.00	STA
201111	GRUBBING	24.00	STA
202011	R&D OF FENCE	3,276.00	LF
202017	R&D OF GATES	8.00	EACH
202062	R&D OF CONCRETE DRIVEWAYS	47.00	SQYD
202096	R&D OF PIPE CULVERTS	5.00	EACH
202132	R&D OF GUARDRAIL	450.00	LF
205011	REMOV.EXIST.BR.STR.(SITE 1)	1.00	L.S.
210213	UNCLASSIFIED EXCAVATION	6,839.00	CUYD
210611	COMPACTED EMBANKMENT	30,684.00	CUYD
210702	SOIL STABILIZATION	100.00	TON
303117	AGGR.BASE COURSE(CLASS 7)	7,284.00	TON
401011	TACK COAT	1,412.00	GAL
406161	M.A. IN ACHM BINDER(1")	2,312.00	TON
406412	A.B.(PG70-22)ACHM BINDER(1")	114.00	TON
407162	MA IN ACHM SURFACE(1/2")	1,985.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	124.00	TON
412002	COLD MILLING ASPHALT PVMT.	489.00	SQYD
414011	ASPH.CONC.PATCH-MAINT.	10.00	TON
415011	ACHM PATCH.EXIST.RDWY.	10.00	TON
504031	APPROACH SLABS	150.40	CUYD
504264	APPROACH GUTTERS	16.80	CUYD
505011	P.C.CONCRETE DRIVEWAY	88.73	SQYD
601001	MOBILIZATION	1.00	L.S.
602011	FURNISHING FIELD OFFICE	1.00	EACH
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	472.00	SQFT
604013	BARRICADES	32.00	LF
604023	TRAFFIC DRUMS	60.00	EACH
604031	FURN.&INSTL.PRCST.CONC.BARR.	1,092.00	LF
604036	RELO.PRECAST CONCRETE BARRIER	426.00	LF
604041	CONST.PAVEMENT MARKINGS	10,040.00	LF
604051	REMOVABLE CONST.PVMT.MRK.	784.00	LF
604083	VERTICAL PANELS	22.00	EACH

605012	CONC.DITCH PAVING(TYPE B)	160.00	SQYD
606703	18" SIDE DRAIN	250.00	LF
606994	SELECTED PIPE BEDDING	20.00	CUYD
611008	4" PIPE UNDERDRAINS	500.00	LF
611013	UNDERDRAIN OUTLET PROTECTORS	2.00	EACH
617005	GUARDRAIL (TYPE A)	450.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	4.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	4.00	EACH
619027	WIRE FENCE (TYPE C)	3,280.00	LF
619332	16' STEEL GATES	8.00	EACH
620001	LIME	9.00	TON
620011	SEEDING	4.73	ACRE
620022	MULCH COVER	22.02	ACRE
620030	WATER	836.10	MGAL
621001	TEMPORARY SEEDING	17.29	ACRE
621021	SILT FENCE	5,876.00	LF
621111	SEDIMENT REMOVAL & DISPOSAL	260.00	CUYD
621151	ROCK DITCH CHECKS	66.00	CUYD
621169	FILTER SOCK (18")	351.00	LF
621173	WATTLE (20")	180.00	LF
623001	SECOND SEEDING APPLICATION	4.73	ACRE
624001	SOLID SODDING	71.00	SQYD
626003	EROSION CONTROL MATTING-3	471.00	SQYD
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
636001	BRIDGE CONSTRUCTION CONTROL	1.00	L.S.
637001	MAILBOXES	2.00	EACH
637017	MAILBOX SUPPORTS (SINGLE)	2.00	EACH
642102	CENTERLINE RUMBLE STRIPES IN ASPH. RDWYS	2,046.00	LF
719002	THERMO.PVMT.MARK.WH(6")	4,884.00	LF
719102	THERMO.PVMT.MARK.YL(6")	4,880.00	LF
721002	RAISED PAVEMENT MARKERS-2	31.00	EACH
731071	TEMP. IMPACT ATTEN. BARR.	3.00	EACH
731072	TEMP. IMPACT ATTEN. BARRIER (REPAIR)	3.00	EACH
801001	UNCLASS.EXCAV.FOR STRS-BR	475.00	CUYD
802112	CLASS 5 CONCRETE-BRIDGE	276.90	CUYD
802122	CLASS S(AE) CONCRETE-BRIDGE	359.70	CUYD
802599	PRESTRESSED CONC. BEAMS (TYPE III)	967.50	LF
803004	CLASS 2 PROTECTIVE SURFACE TREATMENT	1,052.60	SQYD
804003	REINF.STEEL-ROADWAY (GR 60)	19,160.00	LB
804013	REINF.STEEL-BRIDGE (GR 60)	45,030.00	LB
804023	EPOXY COAT.REINF.STEEL-GR 60	82,920.00	LB
805022	STEEL PILING (HP 12X53)	470.00	LF
805504	PREBORING	318.00	LF
808002	ELASTOMERIC BEARINGS	9,653.00	CUIN
812004	BRIDGE NAME PLATE (TYPE D)	1.00	EACH
816003	FILTER BLANKET	919.00	SQYD
816111	DUMPED RIPRAP	580.00	CUYD

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHIN FIVE HUNDRED TWENTY (520) CALENDAR DAYS.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A50033

HWY. 67B – HWY. 13 (S)

FEDERAL AID PROJECT STPF-0073(94)

THE PURPOSE OF THIS PROJECT IS TO MILL AND OVERLAY AND PLACE ULTRATHIN BONDED WEARING COURSE ON APPROXIMATELY 5.952 MILES OF HIGHWAY 367 IN WHITE COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL OF GUARDRAIL, AGGREGATE BASE COURSE, ACHM BINDER AND SURFACE COURSES, ULTRATHIN BONDED WEARING COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, GUARDRAIL, EROSION CONTROL, RUMBLE STRIPES, LOOP WIRING, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 367

SECTIONS: 15

COUNTY: WHITE

LENGTH: 5.952 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202132	R&D OF GUARDRAIL	1,450.00	LF
303117	AGGR.BASE COURSE(CLASS 7)	327.00	TON
401011	TACK COAT	7,506.00	GAL
406161	M.A. IN ACHM BINDER(1")	124.00	TON
406412	A.B.(PG70-22)ACHM BINDER(1")	6.00	TON
407162	MA IN ACHM SURFACE(1/2")	7,717.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	458.00	TON
407904	ULTRATHIN BONDED WEARING CRS (3/4"-TY C)	2,040.00	TON
412002	COLD MILLING ASPHALT PVMT.	68,694.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	500.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	1,244.00	SQFT
604023	TRAFFIC DRUMS	36.00	EACH
604041	CONST.PAVEMENT MARKINGS	130,333.00	LF
604045	CONST.PAVEMENT MARKINGS (WORD)	4.00	EACH
604046	CONST.PAVEMENT MARKINGS (ARROW)	4.00	EACH
604061	REMOVAL OF PERM.PVMT.MRK.	1,525.00	LF
617005	GUARDRAIL (TYPE A)	1,450.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	12.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	12.00	EACH
621021	SILT FENCE	500.00	LF
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642102	CENTERLINE RUMBLE STRIPES IN ASPH. RDWYS	16,603.00	LF
701603	PORTABLE TRAFFIC SIGNAL SYSTEM-ACTUATED	12.00	WEEK
704036	LOOP WIRING CLASS III (1C/16 A.W.G.)	964.00	LF
719002	THERMO.PVMT.MARK.WH(6")	61,685.00	LF
719006	THERMO.PVMT.MARK.WH(24")	156.00	LF
719102	THERMO.PVMT.MARK.YL(6")	68,492.00	LF
719201	THERMO.PVMT.MARK.(WORD)	4.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	4.00	EACH
721002	RAISED PAVEMENT MARKERS-2	483.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A50052

STONE CO. LINE – HWY. 25 (S)

FEDERAL AID PROJECT STPR-0032(45)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 5.996 MILES OF HIGHWAY 14 IN INDEPENDENCE COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL OF CONCRETE ISLANDS, AGGREGATE BASE COURSE, ACHM BINDER AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 14

SECTIONS: 8

COUNTY: INDEPENDENCE

LENGTH: 5.996 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202047	R&D OF CONCRETE ISLANDS	630.00	SQYD
303117	AGGR.BASE COURSE(CLASS 7)	2,944.00	TON
401011	TACK COAT	12,222.00	GAL
406161	M.A. IN ACHM BINDER(1")	227.00	TON
406412	A.B.(PG70-22)ACHM BINDER(1")	11.00	TON
407161	MA IN ACHM SURFACE(3/8")	12,870.00	TON
407441	AB(PG70-22)ACHM SURF(3/8")	822.00	TON
412002	COLD MILLING ASPHALT PVMT.	17,793.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	250.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	456.00	SQFT
604041	CONST.PAVEMENT MARKINGS	63,318.00	LF
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
719002	THERMO.PVMT.MARK.WH(6")	63,912.00	LF
719005	THERMO.PVMT.MARK.WH(12")	535.00	LF
719006	THERMO.PVMT.MARK.WH(24")	15.00	LF
719102	THERMO.PVMT.MARK.YL(6")	63,318.00	LF
719200	THERMO.PVMT.MARK.(YIELD LINE)	30.00	LF
719201	THERMO.PVMT.MARK.(WORD)	2.00	EACH
721002	RAISED PAVEMENT MARKERS-2	441.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.

ARKANSAS DEPARTMENT OF TRANSPORTATION

061922

HWYS. 7 & 70B PED. IMPVTS. (GARLAND CO.) (S)

FEDERAL AID PROJECT VRU-9210(58) & HSIP-9210(58)

THE PURPOSE OF THIS PROJECT IS TO IMPROVE ADA COMPLIANCE AND SAFETY FOR PEDESTRIANS ON HIGHWAYS 7 AND 70B IN GARLAND COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL ITEMS, EARTHWORK, PORTLAND CEMENT CONCRETE PAVEMENT, ACHM BASE, BINDER, AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, MINOR DRAINAGE, EROSION CONTROL, TRAFFIC SIGNAL ITEMS, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 7 & 70B

SECTIONS: 9 & 9B

COUNTY: GARLAND

LENGTH: 2.80 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

201301	CLEARING & GRUBBING TREES	1.00	EACH
202001	R&D OF CURB	159.00	LF
202003	R&D OF CURB AND GUTTER	2,274.00	LF
202047	R&D OF CONCRETE ISLANDS	37.00	SQYD
202062	R&D OF CONCRETE DRIVEWAYS	183.00	SQYD
202072	R&D OF WALKS	1,143.00	SQYD
202084	R&D OF SIGN FOUNDATIONS	1.00	EACH
202093	R&D OF DROP INLETS	2.00	EACH
202096	R&D OF PIPE CULVERTS	1.00	EACH
202191	R&D OF SIGNS	15.00	EACH
202911	R&D OF BOLLARDS	2.00	EACH
210213	UNCLASSIFIED EXCAVATION	625.00	CUYD
210611	COMPACTED EMBANKMENT	481.00	CUYD
309505	P.C.CONCRETE BASE-5"	679.00	SQYD
401011	TACK COAT	436.00	GAL
405161	M.A. IN ACHM BASE COURSE(1.5")	136.00	TON
405412	A.B.(PG70-22)ACHM BASE(1.5")	7.00	TON
406161	M.A. IN ACHM BINDER(1")	67.00	TON
406412	A.B.(PG70-22)ACHM BINDER(1")	4.00	TON
407162	MA IN ACHM SURFACE(1/2")	472.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	3.00	TON
407452	AB(PG76-22)ACHM SURF(1/2")	28.00	TON
412002	COLD MILLING ASPHALT PVMT.	4,049.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	50.00	TON
505011	P.C.CONCRETE DRIVEWAY	220.44	SQYD
601001	MOBILIZATION	1.00	L.S.
602011	FURNISHING FIELD OFFICE	1.00	EACH
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	2,084.00	SQFT
604013	BARRICADES	128.00	LF
604023	TRAFFIC DRUMS	95.00	EACH
604026	TRAFFIC CONE	60.00	EACH
604051	REMOVABLE CONST.PVMT.MRK.	80.00	LF
604055	REMOVAL OF CONST.PVMT.MRK.	80.00	LF

604061	REMOVAL OF PERM.PVMT.MRK.	4,375.00	LF
604083	VERTICAL PANELS	277.00	EACH
605601	18" R.C.PIPES CULVERTS(CL.3)	3.00	LF
605606	24" R.C.PIPES CULVERTS(CL.3)	17.00	LF
606994	SELECTED PIPE BEDDING	5.00	CUYD
609134	DROP INLETS (TYPE MO)	1.00	EACH
609138	DROP INLETS (TYPE ST)	1.00	EACH
609144	DROP INLETS (TYPE SPECIAL)	1.00	EACH
609146	DROP INLET (TYPE SPECIAL-1)	1.00	EACH
609311	DROP INLET EXTENSIONS (4')	1.00	EACH
620001	LIME	1.00	TON
620011	SEEDING	0.50	ACRE
620022	MULCH COVER	1.00	ACRE
620030	WATER	65.60	MGAL
621001	TEMPORARY SEEDING	0.50	ACRE
621021	SILT FENCE	1,000.00	LF
621031	SAND BAG DITCH CHECKS	220.00	BAG
621111	SEDIMENT REMOVAL & DISPOSAL	56.00	CUYD
621168	FILTER SOCK (12")	240.00	LF
623001	SECOND SEEDING APPLICATION	0.50	ACRE
624001	SOLID SODDING	350.00	SQYD
632011	CONCRETE ISLAND	527.00	SQYD
633011	CONCRETE WALKS	535.00	SQYD
634201	CC CURB & GUTTER-A (1'6")	2,802.00	LF
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
640021	MODIFYING DROP INLETS	7.00	EACH
641020	WHEELCHAIR RAMPS (TYPE 3)	143.00	SQYD
641021	WHEELCHAIR RAMPS (TYPE 4)	130.00	SQYD
641022	WHEELCHAIR RAMPS (TYPE 5)	103.00	SQYD
641023	WHEELCHAIR RAMPS (TYPE 6)	99.00	SQYD
641500	SURFACE-APPLIED DETECT. WARNING PANELS	831.00	SQFT
701227	SYS.LOCAL CNTRL.TS 2-TY.2,E-NET(8 PHASE)	3.00	EACH
701401	TRAF.SIG.CNTRL.(MOD.)	7.00	EACH
701722	ETHERNET SWITCH, T100 HARDENED (8-PORT)	3.00	EACH
701751	E-NET CABLE (EXTERIOR CAT 5E)	345.00	LF
702094	CELLULAR MODEM	3.00	EACH
702304	LOCAL RADIO (E-NET 5.8) WITH ANTENNA	3.00	EACH
703030	RECTANGULAR RAPID FLASHING BEACON (RRFB)	3.00	EACH
703031	RRFB - AC	14.00	EACH
704432	LED BLANK OUT SIGN	4.00	EACH
706039	TRAF.SIG.HEAD,LED,(3SEC.,1WAY)	15.00	EACH
707006	CENTRAL CONTROL UNIT	10.00	EACH
707007	POLE MOUNTED ASSEMBLY	67.00	EACH
707012	PED.SIG.HEAD RELOCATION	9.00	EACH
707015	COUNTDOWN PED.SIG.HEAD,LED	22.00	EACH
707022	EMBED LED PED ACTIVATED CROSSWALK SIGN	6.00	EACH
707220	PASSIVE PED DETECTION	2.00	EACH
707225	IN-ROAD LIGHTING	1.00	EACH
708007	TRAFFIC SIGNAL CABLE (5C/12)	12,675.00	LF
708008	TRAFFIC SIGNAL CABLE (5C/14)	9,420.00	LF
708038	TRAFFIC SIGNAL CABLE (20C/14)	1,170.00	LF
708207	ELEC.COND.-IN-CONDUIT(1C/8 AWG, EGC)	8,120.00	LF
708211	ELEC.COND.-IN-CONDUIT(1C/12 AWG,EGC)	750.00	LF
708217	ELEC.COND.-IN-CONDUIT(2C/6 AWG)	215.00	LF

708219	ELEC.COND.-IN-CONDUIT(2C/8 AWG)	1,550.00	LF
708221	ELEC.COND.-IN-CONDUIT (2C/10 AWG)	1,890.00	LF
708451	ELECT.COND. FOR LUMINAIRES	840.00	LF
709004	GALV. STEEL CONDUIT (2")	300.00	LF
710004	NON-METALLIC CONDUIT (2")	1,850.00	LF
710005	NON-METALLIC CONDUIT (3")	4,075.00	LF
711004	CONCRETE PULL BOX (TYPE 2)	27.00	EACH
711005	CONCRETE PULL BOX (TYPE 3)	1.00	EACH
711105	CONCRETE PULL BOX (TYPE 2 HD)	33.00	EACH
711106	CONCRETE PULL BOX (TYPE 3 HD)	5.00	EACH
714018	T.S.M.ARM & POLE W/FND(18)	1.00	EACH
714030	T.S.M.ARM & POLE W/FND(30)	1.00	EACH
714032	T.S.M.ARM & POLE W/FND(32)	1.00	EACH
714036	T.S.M.ARM & POLE W/FND(36)	1.00	EACH
714042	T.S.M.ARM & POLE W/FND(42)	1.00	EACH
714724	LED LUMINAIRE ASSEMBLY	3.00	EACH
715011	TRAFFIC SIGNAL PED. POLE W/ FND	50.00	EACH
715106	SERVICE PT.ASMBLY.(6 CIRCUITS)	3.00	EACH
715120	PEDESTAL TY SERV POINT ASSEM (6 CIRUIT)	5.00	EACH
715704	REMOV.L.TRAFFIC SIG.EQUIPMENT	1.00	L.S.
718004	REFL.PAINT PVMT.MRK.WH(10")	270.00	LF
718104	REFL.PAINT PVMT.MRK.YL(10")	570.00	LF
719002	THERMO.PVMT.MARK.WH(6")	815.00	LF
719003	THERMO.PVMT.MARK.WH(8")	195.00	LF
719005	THERMO.PVMT.MARK.WH(12")	162.00	LF
719006	THERMO.PVMT.MARK.WH(24")	4,795.00	LF
719102	THERMO.PVMT.MARK.YL(6")	755.00	LF
719200	THERMO.PVMT.MARK.(YIELD LINE)	220.00	LF
719699	PREFORMED THERMO PAVEMENT MARKING SYSTEM	72.00	SQYD
726002	STANDARD SIGN	211.00	SQFT
729005	CHANNEL POST SIGN SUP-U 1	18.00	EACH
729006	CHANNEL POST SIGN SUP-U 2	2.00	EACH
733005	VIDEO DETECTOR ROTATION	13.00	EACH
733010	360-DEGREE CAMERA	2.00	EACH
733030	VIDEO CABLE	815.00	LF
733035	VIDEO CABLE (EXTERIOR CAT 5E)	280.00	LF
905504	LED RDWY ILLMN (17714 COBRA, TBS, 20)	3.00	EACH
905505	LED RDWY ILLMN (16800, COBRA, TBS, 30)	2.00	EACH
905506	LED RDWY ILLMN (17714, COBRA, TBS, 30)	7.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHIN THREE HUNDRED SEVENTY (370) CALENDAR DAYS.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A60066

HWY. 367 – HWY. 365 (S)

FEDERAL AID PROJECT STPLC-0060(83)

THE PURPOSE OF THIS PROJECT IS TO MILL AND OVERLAY APPROXIMATELY 5.078 MILES OF HIGHWAY 338 IN PULASKI COUNTY. THIS PROJECT CONSISTS OF EARTHWORK, AGGREGATE BASE COURSE, HIMOD ASPHALT SURFACE COURSE, ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, RADAR DETECTION SYSTEM, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 338

SECTIONS: 2

COUNTY: PULASKI

LENGTH: 5.078 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

210702	SOIL STABILIZATION	5,177.00	TON
303117	AGGR.BASE COURSE(CLASS 7)	718.00	TON
401011	TACK COAT	9,552.00	GAL
407153	MA IN HIMOD SURF (1/2")	2,235.00	TON
407162	MA IN ACHM SURFACE(1/2")	10,362.00	TON
407452	AB(PG76-22)ACHM SURF(1/2")	626.00	TON
407455	AB IN HIMOD SURF (1/2")	143.00	TON
412002	COLD MILLING ASPHALT PVMT.	94,665.00	SQYD
414011	ASPH.CONC.PATCH-MAINT.	127.00	TON
415011	ACHM PATCH.EXIST.RDWY.	250.00	TON
601001	MOBILIZATION	1.00	L.S.
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	760.00	SQFT
604023	TRAFFIC DRUMS	211.00	EACH
604041	CONST.PAVEMENT MARKINGS	107,247.00	LF
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
701401	TRAF.SIG.CNTRL.(MOD.)	1.00	EACH
701603	PORTABLE TRAFFIC SIGNAL SYSTEM-ACTUATED	8.00	WEEK
719002	THERMO.PVMT.MARK.WH(6")	53,623.00	LF
719003	THERMO.PVMT.MARK.WH(8")	1,695.00	LF
719102	THERMO.PVMT.MARK.YL(6")	53,623.00	LF
719201	THERMO.PVMT.MARK.(WORD)	3.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	3.00	EACH
719210	THERMO.PVMT.MARK.(YIELD LINE)	55.00	LF
721002	RAISED PAVEMENT MARKERS-2	403.00	EACH
733035	VIDEO CABLE (EXTERIOR CAT 5E)	175.00	LF
733052	ADVANCED RADAR DETECTOR	3.00	EACH
733054	RADAR CABINET INTERFACE	1.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A70049

OUACHITA RIVER – NORTH (S)

FEDERAL AID PROJECT NHPP-0007(37)

THE PURPOSE OF THIS PROJECT IS TO MILL AND OVERLAY APPROXIMATELY 3.373 MILES OF HIGHWAY 167 IN CALHOUN COUNTY. THIS PROJECT CONSISTS OF FOG SEAL, ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, MAINTENANCE OF TRAFFIC, RUMBLE STRIPS AND STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 167

SECTIONS: 3

COUNTY: CALHOUN

LENGTH: 3.373 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401005	FOG SEAL (TYPE 2)	4,454.00	GAL
401011	TACK COAT	9,699.00	GAL
407162	MA IN ACHM SURFACE(1/2")	10,061.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	608.00	TON
412002	COLD MILLING ASPHALT PVMT.	96,991.00	SQYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	231.00	SQFT
604041	CONST.PAVEMENT MARKINGS	166,000.00	LF
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642001	RUMBLE STRIPS IN ASPHALT SHOULDERS	35,629.00	LF
642102	CENTERLINE RUMBLE STRIPES IN ASPH. RDWYS	17,814.00	LF
719002	THERMO.PVMT.MARK.WH(6")	46,032.00	LF
719102	THERMO.PVMT.MARK.YL(6")	36,818.00	LF
721002	RAISED PAVEMENT MARKERS-2	690.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A70050

HWY. 67 – HWY. 51 (S)

FEDERAL AID PROJECT STPR-0010(67)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 12.433 MILES OF HIGHWAY 182 IN CLARK COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL OF GUARDRAIL, TRENCHING AND SHOULDER PREPARATION, ACHM BINDER AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, GUARDRAIL, EROSION CONTROL, RUMBLE STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 182

SECTIONS: 0

COUNTY: CLARK

LENGTH: 12.433 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202132	R&D OF GUARDRAIL	312.00	LF
215011	TRENCH.AND SHOULDER PREP.	655.00	STA
303117	AGGR.BASE COURSE(CLASS 7)	2,626.00	TON
401011	TACK COAT	37,282.00	GAL
406161	M.A. IN ACHM BINDER(1")	6,117.00	TON
406412	A.B.(PG70-22)ACHM BINDER(1")	302.00	TON
407162	MA IN ACHM SURFACE(1/2")	29,884.00	TON
407442	AB(PG70-22)ACHM SURF(1/2")	1,806.00	TON
412002	COLD MILLING ASPHALT PVMT.	1,161.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	100.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	927.00	SQFT
604041	CONST.PAVEMENT MARKINGS	256,941.00	LF
604083	VERTICAL PANELS	106.00	EACH
611008	4" PIPE UNDERDRAINS	16,000.00	LF
611013	UNDERDRAIN OUTLET PROTECTORS	66.00	EACH
617005	GUARDRAIL (TYPE A)	375.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	4.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	4.00	EACH
621031	SAND BAG DITCH CHECKS	200.00	BAG
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
637001	MAILBOXES	26.00	EACH
637017	MAILBOX SUPPORTS (SINGLE)	26.00	EACH
642011	RUMBLE STRIPES IN ASPHALT SHOULDERS	100,650.00	LF
719002	THERMO.PVMT.MARK.WH(6")	131,504.00	LF
719102	THERMO.PVMT.MARK.YL(6")	115,437.00	LF
721002	RAISED PAVEMENT MARKERS-2	822.00	EACH
726002	STANDARD SIGN	123.00	SQFT
729003	CHANNEL POST SIGN SUPPORT-C	25.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A80050

HWY. 95 – HWY. 124 (S)

FEDERAL AID PROJECT NHPP-0071(52)

THE PURPOSE OF THIS PROJECT IS TO MILL AND OVERLAY AND PLACE ULTRATHIN BONDED WEARING COURSE ON APPROXIMATELY 13.159 MILES OF HIGHWAY 65 IN VAN BUREN COUNTY. THIS PROJECT CONSISTS OF AGGREGATE SURFACE COURSE, ACHM SURFACE COURSE, ULTRATHIN BONDED WEARING COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, RUMBLE STRIPS, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 65

SECTIONS: 8

COUNTY: VAN BUREN

LENGTH: 13.159 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303308	AGGREGATE SURFACE COURSE (CLASS D-8)	400.00	TON
401011	TACK COAT	23,047.00	GAL
407162	MA IN ACHM SURFACE(1/2")	23,753.00	TON
407452	AB(PG76-22)ACHM SURF(1/2")	1,463.00	TON
407904	ULTRATHIN BONDED WEARING CRS (3/4"-TY C)	11,331.00	TON
412002	COLD MILLING ASPHALT PVMT.	232,375.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	400.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	791.00	SQFT
604041	CONST.PAVEMENT MARKINGS	313,484.00	LF
604045	CONST.PAVEMENT MARKINGS (WORD)	13.00	EACH
604046	CONST.PAVEMENT MARKINGS (ARROW)	11.00	EACH
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642001	RUMBLE STRIPS IN ASPHALT SHOULDERS	101,587.00	LF
719002	THERMO.PVMT.MARK.WH(6")	138,673.00	LF
719006	THERMO.PVMT.MARK.WH(24")	1,230.00	LF
719102	THERMO.PVMT.MARK.YL(6")	174,811.00	LF
719201	THERMO.PVMT.MARK.(WORD)	13.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	11.00	EACH
719210	THERMO.PVMT.MARK.(YIELD LINE)	18.00	LF
721002	RAISED PAVEMENT MARKERS-2	5,247.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A90050

MISSOURI STATE LINE – HWY. 62 (S)

FEDERAL AID PROJECT STPR-HRRR-0003(59)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 10.552 MILES OF HIGHWAY 101 IN BAXTER COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL ITEMS, EARTHWORK, TRENCHING AND SHOULDER PREPARATION, AGGREGATE BASE COURSE, ACHM BINDER AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, APPROACH GUTTERS, MAINTENANCE OF TRAFFIC, MINOR DRAINAGE STRUCTURES, GUARDRAIL, EROSION CONTROL, MUMBLE STRIPS AND STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 101

SECTIONS: 1

COUNTY: BAXTER

LENGTH: 10.552 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202049	R&D OF PIPE CULVERTS	735.00	LF
202093	R&D OF DROP INLETS	1.00	EACH
202097	R&D OF BOX CULVERTS	3.00	EACH
202132	R&D OF GUARDRAIL	750.00	LF
210213	UNCLASSIFIED EXCAVATION	15.00	CUYD
210611	COMPACTED EMBANKMENT	60.00	CUYD
215011	TRENCH.AND SHOULDER PREP.	471.00	STA
303117	AGGR.BASE COURSE(CLASS 7)	692.00	TON
401011	TACK COAT	29,357.00	GAL
406161	M.A. IN ACHM BINDER(1")	3,302.00	TON
406412	A.B.(PG70-22)ACHM BINDER(1")	152.00	TON
407161	MA IN ACHM SURFACE(3/8")	19,797.00	TON
407441	AB(PG70-22)ACHM SURF(3/8")	1,286.00	TON
412002	COLD MILLING ASPHALT PVMT.	1,701.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	160.00	TON
504264	APPROACH GUTTERS	88.92	CUYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	1,149.00	SQFT
604023	TRAFFIC DRUMS	202.00	EACH
604041	CONST.PAVEMENT MARKINGS	475,922.00	LF
604045	CONST.PAVEMENT MARKINGS (WORD)	2.00	EACH
604046	CONST.PAVEMENT MARKINGS (ARROW)	2.00	EACH
604049	TUBULAR MARKERS	11.00	EACH
604055	REMOVAL OF CONST.PVMT.MRK.	7,054.00	LF
604061	REMOVAL OF PERM.PVMT.MRK.	14,108.00	LF
605609	24" R.C.PIPE CULVERTS(CL.5)	872.00	LF
605858	24" FES R.C.PIPE CLVT.	41.00	EACH
609015	DROP INLETS (TYPE E)	1.00	EACH
615020	PVMT.REPAIR O/CLVT.(CONCRETE)	138.60	CUYD
617005	GUARDRAIL (TYPE A)	450.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	4.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	4.00	EACH
620001	LIME	2.00	TON

620011	SEEDING	1.08	ACRE
620022	MULCH COVER	1.86	ACRE
620030	WATER	130.30	MGAL
621001	TEMPORARY SEEDING	0.78	ACRE
621021	SILT FENCE	2,350.00	LF
621173	WATTLE (20")	2,250.00	LF
623001	SECOND SEEDING APPLICATION	1.08	ACRE
624001	SOLID SODDING	328.00	SQYD
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
637001	MAILBOXES	62.00	EACH
637017	MAILBOX SUPPORTS (SINGLE)	62.00	EACH
642301	MUMBLE STRIPS IN ASPHALT SHOULDERS	8,382.00	LF
642311	MUMBLE STRIPES IN ASPHALT SHOULDERS	36,562.00	LF
642402	C.L. MUMBLE STRIPES IN ASPHALT ROADWAYS	28,090.00	LF
701603	PORTABLE TRAFFIC SIGNAL SYSTEM-ACTUATED	4.00	WEEK
719002	THERMO.PVMT.MARK.WH(6")	117,112.00	LF
719005	THERMO.PVMT.MARK.WH(12")	200.00	LF
719102	THERMO.PVMT.MARK.YL(6")	117,322.00	LF
719200	THERMO.PVMT.MARK.(YIELD LINE)	18.00	LF
719201	THERMO.PVMT.MARK.(WORD)	2.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	2.00	EACH
721002	RAISED PAVEMENT MARKERS-2	740.00	EACH
726002	STANDARD SIGN	14.00	SQFT
730499	OMNI-DIR.BRKAWAY SIGN SUPPORT-TYPE G-1	1.00	EACH
804003	REINF.STEEL-ROADWAY (GR 60)	7,960.00	LB

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A90051

HWY. 412 IMPVTS. (CARROLL & MADISON COS.) (S)

FEDERAL AID PROJECT NHPP-0844(5)

THE PURPOSE OF THIS PROJECT IS TO MILL AND OVERLAY APPROXIMATELY 11.203 MILES OF HIGHWAY 412 IN CARROLL AND MADISON COUNTIES. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL OF GUARDRAIL, ACHM SURFACE COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, GUARDRAIL, RUMBLE STRIPS AND STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 412

SECTIONS: 3, 4, & 5

COUNTY: CARROLL & MADISON

LENGTH: 11.203 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202132	R&D OF GUARDRAIL	3,000.00	LF
401011	TACK COAT	29,885.00	GAL
407162	MA IN ACHM SURFACE(1/2")	31,032.00	TON
407452	AB(PG76-22)ACHM SURF(1/2")	1,841.00	TON
412002	COLD MILLING ASPHALT PVMT.	297,066.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	300.00	TON
601001	MOBILIZATION	1.00	L.S.
603010	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	1,707.00	SQFT
604041	CONST.PAVEMENT MARKINGS	269,915.00	LF
617005	GUARDRAIL (TYPE A)	2,200.00	LF
617312	GUARDRAIL TERMINAL (TYPE 2)	14.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	4.00	EACH
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642001	RUMBLE STRIPS IN ASPHALT SHOULDERS	61,289.00	LF
642011	RUMBLE STRIPES IN ASPHALT SHOULDERS	39,811.00	LF
642102	CENTERLINE RUMBLE STRIPES IN ASPH. RDWYS	50,550.00	LF
719002	THERMO.PVMT.MARK.WH(6")	132,510.00	LF
719005	THERMO.PVMT.MARK.WH(12")	2,895.00	LF
719102	THERMO.PVMT.MARK.YL(6")	125,065.00	LF
719201	THERMO.PVMT.MARK.(WORD)	4.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	8.00	EACH
721002	RAISED PAVEMENT MARKERS-2	1,115.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.

ARKANSAS DEPARTMENT OF TRANSPORTATION

101141

HWYS. 61/140 INTERS. IMPVTS. (OSCEOLA) (S)

FEDERAL AID PROJECT STPSC-9326(7) & 9030

THE PURPOSE OF THIS PROJECT IS TO IMPROVE THE INTERSECTION ON HIGHWAYS 61 AND 140 IN MISSISSIPPI COUNTY. THIS PROJECT CONSISTS OF REMOVAL AND DISPOSAL ITEMS, STONE BACKFILL, EARTHWORK, AGGREGATE BASE COURSE, ACHM BASE, BINDER, AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, PORTLAND CEMENT CONCRETE DRIVEWAY, MAINTENANCE OF TRAFFIC, CONCRETE DITCH PAVING, MINOR DRAINAGE, EROSION CONTROL, CONCRETE ISLAND, WALKS, AND CURB, WHEELCHAIR RAMPS, TRAFFIC SIGNAL ITEMS, PAVEMENT MARKINGS, AND MISC. ITEMS.

ROUTES: 61 & 140

SECTIONS: 2 & 2

COUNTY: MISSISSIPPI

LENGTH: 0.263 mile in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

202001	R&D OF CURB	990.00	LF
202003	R&D OF CURB AND GUTTER	330.00	LF
202042	R&D OF CONCRETE PAVEMENT	316.00	SQYD
202047	R&D OF CONCRETE ISLANDS	418.00	SQYD
202062	R&D OF CONCRETE DRIVEWAYS	1,846.00	SQYD
202072	R&D OF WALKS	11.00	SQYD
202093	R&D OF DROP INLETS	1.00	EACH
202096	R&D OF PIPE CULVERTS	11.00	EACH
202099	R&D OF HEADWALLS	1.00	EACH
207011	STONE BACKFILL	45.00	TON
210213	UNCLASSIFIED EXCAVATION	669.00	CUYD
210611	COMPACTED EMBANKMENT	2,646.00	CUYD
210702	SOIL STABILIZATION	100.00	TON
303117	AGGR.BASE COURSE(CLASS 7)	201.00	TON
309505	P.C.CONCRETE BASE-5"	300.00	SQYD
401011	TACK COAT	1,861.00	GAL
405161	M.A. IN ACHM BASE COURSE(1.5")	606.00	TON
405412	A.B.(PG70-22)ACHM BASE(1.5")	24.00	TON
406161	M.A. IN ACHM BINDER(1")	356.00	TON
406412	A.B.(PG70-22)ACHM BINDER(1")	15.00	TON
407162	MA IN ACHM SURFACE(1/2")	2,997.00	TON
407452	AB(PG76-22)ACHM SURF(1/2")	171.00	TON
412002	COLD MILLING ASPHALT PVMT.	4,490.00	SQYD
414011	ASPH.CONC.PATCH-MAINT.	25.00	TON
505011	P.C.CONCRETE DRIVEWAY	1,088.54	SQYD
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	530.00	SQFT
604013	BARRICADES	36.00	LF
604023	TRAFFIC DRUMS	55.00	EACH
604026	TRAFFIC CONE	180.00	EACH
604031	FURN.&INSTL.PRCST.CONC.BARR.	133.00	LF
604036	RELO.PRECAST CONCRETE BARRIER	93.00	LF

604041	CONST.PAVEMENT MARKINGS	16,502.00	LF
604045	CONST.PAVEMENT MARKINGS (WORD)	7.00	EACH
604046	CONST.PAVEMENT MARKINGS (ARROW)	7.00	EACH
604055	REMOVAL OF CONST.PVMT.MRK.	8,109.00	LF
604056	REMOVAL OF CONST.PVMT.MRK(WORD)	3.00	EACH
604057	REMOVAL OF CONST.PVMT.MRK(ARROW)	3.00	EACH
604083	VERTICAL PANELS	32.00	EACH
605012	CONC.DITCH PAVING(TYPE B)	16.00	SQYD
606737	36"X23" SIDE DRAIN	68.00	LF
606994	SELECTED PIPE BEDDING	150.00	CUYD
609013	DROP INLETS (TYPE C)	5.00	EACH
609134	DROP INLETS (TYPE MO)	10.00	EACH
609144	DROP INLETS (TYPE SPECIAL)	6.00	EACH
611008	4" PIPE UNDERDRAINS	750.00	LF
611013	UNDERDRAIN OUTLET PROTECTORS	3.00	EACH
620001	LIME	2.00	TON
620011	SEEDING	0.96	ACRE
620022	MULCH COVER	2.00	ACRE
620030	WATER	126.70	MGAL
621001	TEMPORARY SEEDING	1.04	ACRE
621021	SILT FENCE	2,355.00	LF
621031	SAND BAG DITCH CHECKS	264.00	BAG
621071	SEDIMENT BASIN	100.00	CUYD
621101	OBLITERATION OF SEDIMENT BASIN	100.00	CUYD
621111	SEDIMENT REMOVAL & DISPOSAL	300.00	CUYD
621151	ROCK DITCH CHECKS	27.00	CUYD
621168	FILTER SOCK (12")	2,490.00	LF
623001	SECOND SEEDING APPLICATION	0.96	ACRE
624001	SOLID SODDING	613.00	SQYD
632011	CONCRETE ISLAND	290.00	SQYD
633011	CONCRETE WALKS	894.00	SQYD
634201	CC CURB & GUTTER-A (1'6")	2,408.00	LF
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
640021	MODIFYING DROP INLETS	1.00	EACH
641020	WHEELCHAIR RAMPS (TYPE 3)	29.00	SQYD
701029	ACTUATED CNTRL.TS 2-TY.2(8 PHASE)	2.00	EACH
706039	TRAF.SIG.HEAD,LED,(3SEC.,1WAY)	18.00	EACH
706043	TRAF.SIG.HEAD,LED,(4SEC.,1WAY)	8.00	EACH
707006	CENTRAL CONTROL UNIT	1.00	EACH
707007	POLE MOUNTED ASSEMBLY	4.00	EACH
707015	COUNTDOWN PED.SIG.HEAD,LED	4.00	EACH
708007	TRAFFIC SIGNAL CABLE (5C/12)	921.00	LF
708008	TRAFFIC SIGNAL CABLE (5C/14)	1,701.00	LF
708012	TRAFFIC SIGNAL CABLE (7C/14)	1,840.00	LF
708038	TRAFFIC SIGNAL CABLE (20C/14)	576.00	LF
708207	ELEC.COND.-IN-CONDUIT(1C/8 AWG, EGC)	682.00	LF
708211	ELEC.COND.-IN-CONDUIT(1C/12 AWG,EGC)	381.00	LF
708217	ELEC.COND.-IN-CONDUIT(2C/6 AWG)	103.00	LF
708451	ELECT.COND. FOR LUMINAIRES	1,277.00	LF
709004	GALV. STEEL CONDUIT (2")	64.00	LF
709005	GALV. STEEL CONDUIT (3")	30.00	LF
710004	NON-METALLIC CONDUIT (2")	66.00	LF
710005	NON-METALLIC CONDUIT (3")	618.00	LF
711004	CONCRETE PULL BOX (TYPE 2)	4.00	EACH

711104	CONCRETE PULL BOX (TYPE 1 HD)	1.00	EACH
711105	CONCRETE PULL BOX (TYPE 2 HD)	4.00	EACH
713013	SPAN WIRE ASSEMBLY	1.00	EACH
713023	UTILITY POLE - TEMP SPAN WIRE POLE	1.00	EACH
714003	T.S.M.ARM & POLE W/FND(0)	1.00	EACH
714040	T.S.M.ARM & POLE W/FND(40)	1.00	EACH
714042	T.S.M.ARM & POLE W/FND(42)	1.00	EACH
714046	T.S.M.ARM & POLE W/FND(46)	1.00	EACH
714066	T.S.M.ARM & POLE W/FND(66)	1.00	EACH
714724	LED LUMINAIRE ASSEMBLY	6.00	EACH
715011	TRAFFIC SIGNAL PED. POLE W/ FND	2.00	EACH
715102	SERVICE PT.ASMBLY.(2 CIRCUITS)	1.00	EACH
715704	REMOV.L.TRAFFIC SIG.EQUIPMENT	1.00	L.S.
716245	TREATED WOOD POLE (CLASS 2, 45')	3.00	EACH
718004	REFL.PAINT PVMT.MRK.WH(10")	357.00	LF
718104	REFL.PAINT PVMT.MRK.YL(10")	635.00	LF
719002	THERMO.PVMT.MARK.WH(6")	3,186.00	LF
719006	THERMO.PVMT.MARK.WH(24")	424.00	LF
719102	THERMO.PVMT.MARK.YL(6")	4,822.00	LF
719201	THERMO.PVMT.MARK.(WORD)	4.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	4.00	EACH
721002	RAISED PAVEMENT MARKERS-2	49.00	EACH
731071	TEMP. IMPACT ATTEN. BARR.	1.00	EACH
731072	TEMP. IMPACT ATTEN. BARRIER (REPAIR)	2.00	EACH
731075	TEMP. IMPACT ATTENUATION BARRIER (RELO)	1.00	EACH
733008	VIDEO DETECTOR (IP)	5.00	EACH
733009	HYBRID VIDEO/RADAR DETECTOR	3.00	EACH
733035	VIDEO CABLE (EXTERIOR CAT 5E)	1,793.00	LF
733042	VIDEO MONITOR (CLR)	2.00	EACH
733105	CENTRAL CONTROL UNIT (8 CHANNEL)	2.00	EACH
801101	UNCLASS.EXCAV.FOR STRS-RDWY.	13.00	CUYD
802012	CLASS S CONCRETE-ROADWAY	20.31	CUYD
804003	REINF.STEEL-ROADWAY (GR 60)	2,675.00	LB

18" PIPE CULVERTS ALTERNATE - BID ONE ITEM ONLY

605601	18" R.C.PIPE CULVERTS(CL.3)	304.00	LF
605723	18" S.L.P.P.M.C.C.ST.PIPE	304.00	LF
605903	18" S.S.R.P.P.M.C.C.S.P.	304.00	LF

24" PIPE CULVERTS ALTERNATE - BID ONE ITEM ONLY

605606	24" R.C.PIPE CULVERTS(CL.3)	226.00	LF
605726	24" S.L.P.P.M.C.C.ST.PIPE	226.00	LF
605904	24" S.S.R.P.P.M.C.C.S.P.	226.00	LF

48" PIPE CULVERTS ALTERNATE - BID ONE ITEM ONLY

605626	48" R.C.PIPE CULVERTS(CL.3)	18.00	LF
605734	48" S.L.P.P.M.C.C.ST.PIPE	18.00	LF
605908	48" S.S.R.P.P.M.C.C.S.P.	18.00	LF

36" X 23" PIPE CULVERTS ALTERNATE - BID ONE ITEM ONLY

605760	36" X 23" R.C.ARCH PIPE CLVT.(CL.3)	908.00	LF
605824	35"X24" S.L.P.P.M.C.C.ST.ARCH PIPE	908.00	LF
605919	35"X24" S.S.R.P.P.M.C.C.S.P.	908.00	LF

18" FLARED END SECTIONS ALTERNATE - BID ONE ITEM ONLY

605856	18" FES R.C.PIPES CLVT.	5.00	EACH
605857	18" FES C.ST.PIPES CLVT.	5.00	EACH

24" FLARED END SECTIONS ALTERNATE - BID ONE ITEM ONLY

605858	24" FES R.C.PIPES CLVT.	2.00	EACH
605859	24" FES C.ST.PIPES CLVT.	2.00	EACH

48" FLARED END SECTIONS ALTERNATE - BID ONE ITEM ONLY

605866	48" FES R.C.PIPES CLVT.	1.00	EACH
605867	48" FES C.ST.PIPES CLVT.	1.00	EACH

36" X 23" FLARED END SECTIONS ALTERNATE - BID ONE ITEM ONLY

605885	36"X23" FES R.C.ARCH PIPE CLVT.	2.00	EACH
605886	35"X24" FES C.ST.ARCH PIPE CLVT.	2.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHIN THREE HUNDRED SIXTY (360) CALENDAR DAYS.

ARKANSAS DEPARTMENT OF TRANSPORTATION

A00103

MONETTE – MISSISSIPPI CO. LINE (S)

FEDERAL AID PROJECT NHPP-0016(113)

THE PURPOSE OF THIS PROJECT IS TO PLACE ULTRATHIN BONDED WEARING COURSE ON APPROXIMATELY 4.858 MILES OF HIGHWAY 18 IN CRAIGHEAD COUNTY. THIS PROJECT CONSISTS OF ULTRATHIN BONDED WEARING COURSE, COLD MILLING ASPHALT PAVEMENT, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, RUMBLE STRIPS AND STRIPES, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: 18

SECTIONS: 4

COUNTY: CRAIGHEAD

LENGTH: 4.858 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

407904	ULTRATHIN BONDED WEARING CRS (3/4"-TY C)	7,317.00	TON
412002	COLD MILLING ASPHALT PVMT.	2,100.00	SQYD
415011	ACHM PATCH.EXIST.RDWY.	20.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	551.00	SQFT
604041	CONST.PAVEMENT MARKINGS	116,988.00	LF
635011	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
642001	RUMBLE STRIPS IN ASPHALT SHOULDERS	35,548.00	LF
642102	CENTERLINE RUMBLE STRIPES IN ASPH. RDWYS	50,401.00	LF
719002	THERMO.PVMT.MARK.WH(6")	53,747.00	LF
719102	THERMO.PVMT.MARK.YL(6")	63,241.00	LF
719201	THERMO.PVMT.MARK.(WORD)	4.00	EACH
719202	THERMO.PVMT.MARK.(ARROW)	4.00	EACH
721002	RAISED PAVEMENT MARKERS-2	1,282.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 24, 2027.

ARKANSAS DEPARTMENT OF TRANSPORTATION

BR4401

WAR EAGLE CREEK STR. & APPRS. (S)

FEDERAL AID PROJECT STPB-0044(32)

THE PURPOSE OF THIS PROJECT IS TO REPLACE THE BRIDGE STRUCTURE ON 0.452 MILE OF COUNTY ROAD 7 SOUTH OF HUNTSVILLE IN MADISON COUNTY. THIS PROJECT CONSISTS OF CLEARING AND GRUBBING, REMOVAL AND DISPOSAL ITEMS, EARTHWORK, AGGREGATE BASE COURSE, ACHM BINDER AND SURFACE COURSES, COLD MILLING ASPHALT PAVEMENT, MAINTENANCE OF TRAFFIC, MINOR DRAINAGE STRUCTURES, ONE CONTINUOUS PLATE GIRDER UNIT BRIDGE (TOTAL SPAN 355.21'), EROSION CONTROL ITEMS, PAVEMENT MARKING, AND MISC ITEMS.

ROUTES: CR 7

COUNTY: MADISON

LENGTH: 0.452 mile in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

201011	CLEARING	14.00	STA
201111	GRUBBING	23.00	STA
202011	R&D OF FENCE	2,096.00	LF
202017	R&D OF GATES	1.00	EACH
202032	R&D OF RETAINING WALLS	117.00	LF
202034	R&D OF ROCK WALLS	72.00	LF
202096	R&D OF PIPE CULVERTS	1.00	EACH
202145	R&D OF PIPE RAILING	105.00	LF
205011	REMOV.EXIST.BR.STR.(SITE 1)	1.00	L.S.
210213	UNCLASSIFIED EXCAVATION	4,055.00	CUYD
210611	COMPACTED EMBANKMENT	27,548.00	CUYD
303117	AGGR.BASE COURSE(CLASS 7)	4,463.00	TON
401011	TACK COAT	626.00	GAL
406161	M.A. IN ACHM BINDER(1")	1,313.00	TON
406402	A.B.(PG64-22)ACHM BINDER(1")	62.00	TON
407162	MA IN ACHM SURFACE(1/2")	564.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	35.00	TON
412002	COLD MILLING ASPHALT PVMT.	667.00	SQYD
504264	APPROACH GUTTERS	15.80	CUYD
601001	MOBILIZATION	1.00	L.S.
602011	FURNISHING FIELD OFFICE	1.00	EACH
603001	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	219.00	SQFT
604013	BARRICADES	32.00	LF
604023	TRAFFIC DRUMS	50.00	EACH
605012	CONC.DITCH PAVING(TYPE B)	368.89	SQYD
606721	21"X15" SIDE DRAIN	56.00	LF
606990	SELECTED PIPE BEDDING	15.00	CUYD
617005	GUARDRAIL (TYPE A)	200.00	LF
617105	TERMINAL ANCHOR POSTS (TYPE 1)	4.00	EACH
617332	THRIE BEAM GUARDRAIL TERMINAL	4.00	EACH
619029	WIRE FENCE (TYPE D-1)	2,794.00	LF
620001	LIME	7.00	TON
620011	SEEDING	3.64	ACRE
620022	MULCH COVER	8.28	ACRE
620030	WATER	468.40	MGAL

621001	TEMPORARY SEEDING	4.64	ACRE
621021	SILT FENCE	1,764.00	LF
621031	SAND BAG DITCH CHECKS	396.00	BAG
621071	SEDIMENT BASIN	111.00	CUYD
621101	OBLITERATION OF SEDIMENT BASIN	111.00	CUYD
621111	SEDIMENT REMOVAL & DISPOSAL	385.00	CUYD
621151	ROCK DITCH CHECKS	105.00	CUYD
621169	FILTER SOCK (18")	500.00	LF
623001	SECOND SEEDING APPLICATION	3.64	ACRE
624001	SOLID SODDING	204.00	SQYD
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
636001	BRIDGE CONSTRUCTION CONTROL	1.00	L.S.
718001	REFL.PAINT PVMT.MRK.WH(4")	5,072.00	LF
718101	REFL.PAINT PVMT.MRK.YL(4")	5,072.00	LF
726002	STANDARD SIGN	18.25	SQFT
729001	CHANNEL POST SIGN SUPPORT-A	1.00	EACH
729003	CHANNEL POST SIGN SUPPORT-C	6.00	EACH
802112	CLASS 5 CONCRETE-BRIDGE	152.20	CUYD
802122	CLASS 5(AE) CONCRETE-BRIDGE	349.00	CUYD
803004	CLASS 2 PROTECTIVE SURFACE TREATMENT	1,412.90	SQYD
804003	REINF.STEEL-ROADWAY (GR 60)	860.00	LB
804013	REINF.STEEL-BRIDGE (GR 60)	25,670.00	LB
804023	EPOXY COAT.REINF.STEEL-GR 60	98,020.00	LB
805022	STEEL PILING (HP 12X53)	357.00	LF
805041	CORING DRILLED SHAFT	57.00	LF
805057	DRILLED SHAFT (60" DIAMETER)	113.00	LF
805086	PERMANENT STEEL CASING(72")	58.00	LF
805504	PREBORING	339.00	LF
805710	CROSSHOLE SONIC LOGGING (60" DIA.)	4.00	EACH
807234	STR.ST.PL.GRD.SPN(A709,GR50W)	361,150.00	LB
807301	PAINTING STRUCTURAL STEEL	43.10	TON
808002	ELASTOMERIC BEARINGS	13,008.00	CUIN
809015	SILICONE JOINT SEALANT	62.00	LF
812003	BRIDGE NAME PLATE (TYPE C)	1.00	EACH
816003	FILTER BLANKET	1,006.00	SQYD
816131	FOUNDATION PROTECTION RIPRAP	1,835.00	TON

18" PIPE CULVERTS ALTERNATE - BID ONE ITEM ONLY

605604	18" R.C.PIPE CULVERTS(CL.5)	44.00	LF
605689	18" ASPH.C.C.ST.PIPE CLVT.-16G	50.00	LF
605705	18" AL.C.C.ST.PIPE CLVT.-16G	50.00	LF
605722	18" P.P.M.C.C.ST.PIPE CLVT.-16G	50.00	LF

22" X 14" ARCH PIPE CULVERTS ALTERNATE - BID ONE ITEM ONLY

605766	22" X 14" R.C.ARCH PIPE CLVT.(CL.5)	52.00	LF
605784	21"X15" AL.C.C.ST.ARCH PIPE CLVT.-16G	56.00	LF
605797	21"X15" A.C.C.ST.ARCH PIPE-16G	56.00	LF
605809	21"X15" P.P.M.C.C.ST.ARCH PIPE-16G	56.00	LF

18" FLARED END SECTIONS ALTERNATE - BID ONE ITEM ONLY

605856	18" FES R.C.PIPE CLVT.	2.00	EACH
605857	18" FES C.ST.PIPE CLVT.	2.00	EACH

22" X 14" ARCH FLARED END SECTIONS ALTERNATE - BID ONE ITEM ONLY

605881	22"X14" FES R.C.ARCH PIPE CLVT.	2.00	EACH
605882	21"X15" FES C.ST.ARCH PIPE CLVT.	2.00	EACH

12' GATES ALTERNATE - BID ONE ITEM ONLY

619330	12' STEEL GATES	2.00	EACH
619428	12' ALUMINUM GATES	2.00	EACH

16' GATES ALTERNATE - BID ONE ITEM ONLY

619332	16' STEEL GATES	4.00	EACH
619430	16' ALUMINUM GATES	4.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHIN FIVE HUNDRED TWENTY-NINE (529) CALENDAR DAYS.

ARKANSAS DEPARTMENT OF TRANSPORTATION

FA0314

HWY. 341 SOUTHEAST – STONE CO. LINE (PHASE 2) (S)

FEDERAL AID PROJECT STPF-0003(63)

THE PURPOSE OF THIS PROJECT IS TO RECONSTRUCT APPROXIMATELY 1.525 MILES OF COUNTY ROAD 73 IN BAXTER COUNTY. THIS PROJECT CONSISTS OF CLEARING AND GRUBBING, REMOVAL AND DISPOSAL ITEMS, EARTHWORK, AGGREGATE BASE COURSE, ACHM SURFACE COURSE, MAINTENANCE OF TRAFFIC, MINOR DRAINAGE STRUCTURES, DBL. 9' X 6' X 82' THREE-SIDED CAST-IN-PLACE CULVERT (TOTAL SPAN LENGTH 28.31 FT.), EROSION CONTROL ITEMS, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: CR 73

COUNTY: BAXTER

LENGTH: 1.525 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

201011	CLEARING	81.00	STA
201111	GRUBBING	81.00	STA
202011	R&D OF FENCE	1,231.00	LF
202017	R&D OF GATES	1.00	EACH
202096	R&D OF PIPE CULVERTS	15.00	EACH
202097	R&D OF BOX CULVERTS	1.00	EACH
202922	REMOV. AND RELOCATION OF SIGN	2.00	EACH
210213	UNCLASSIFIED EXCAVATION	30,051.00	CUYD
210611	COMPACTED EMBANKMENT	19,272.00	CUYD
303117	AGGR.BASE COURSE(CLASS 7)	14,134.00	TON
401001	PRIME COAT	8,196.00	GAL
407162	MA IN ACHM SURFACE(1/2")	2,032.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	125.00	TON
601001	MOBILIZATION	1.00	L.S.
602011	FURNISHING FIELD OFFICE	1.00	EACH
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	223.00	SQFT
604023	TRAFFIC DRUMS	75.00	EACH
605012	CONC.DITCH PAVING(TYPE B)	79.00	SQYD
605601	18" R.C.PIPE CULVERTS(CL.3)	16.00	LF
606704	24" SIDE DRAIN	56.00	LF
606721	21"X15" SIDE DRAIN	30.00	LF
606723	28"X20" SIDE DRAIN	192.00	LF
606994	SELECTED PIPE BEDDING	38.00	CUYD
611008	4" PIPE UNDERDRAINS	200.00	LF
611013	UNDERDRAIN OUTLET PROTECTORS	4.00	EACH
619028	WIRE FENCE (TYPE D)	1,231.00	LF
620001	LIME	27.00	TON
620015	SPECIAL SEEDING	13.70	ACRE
620023	SPECIAL MULCH COVER	13.70	ACRE
620030	WATER	1,956.40	MGAL
621021	SILT FENCE	3,788.00	LF
621031	SAND BAG DITCH CHECKS	110.00	BAG
621041	DIVERSION DITCH	2,321.00	LF
621071	SEDIMENT BASIN	311.00	CUYD
621101	OBLITERATION OF SEDIMENT BASIN	311.00	CUYD

621111	SEDIMENT REMOVAL & DISPOSAL	928.00	CUYD
621131	PIPE FOR SLOPE DRAINS	292.00	LF
621151	ROCK DITCH CHECKS	333.00	CUYD
621169	FILTER SOCK (18")	200.00	LF
621202	SPECIAL TEMPORARY SEEDING	13.70	ACRE
623006	SPECIAL SECOND SEEDING APPLICATION	13.70	ACRE
635001	ROADWAY CONSTRUCTION CONTROL	1.00	L.S.
636001	BRIDGE CONSTRUCTION CONTROL	1.00	L.S.
718001	REFL.PAINT PVM.T.MRK.WH(4")	16,100.00	LF
718101	REFL.PAINT PVM.T.MRK.YL(4")	16,100.00	LF
726002	STANDARD SIGN	236.25	SQFT
729001	CHANNEL POST SIGN SUPPORT-A	22.00	EACH
729003	CHANNEL POST SIGN SUPPORT-C	36.00	EACH
801001	UNCLASS.EXCAV.FOR STRS-BR	210.00	CUYD
802012	CLASS S CONCRETE-ROADWAY	3.31	CUYD
802112	CLASS S CONCRETE-BRIDGE	328.31	CUYD
804003	REINF.STEEL-ROADWAY (GR 60)	168.00	LB
804013	REINF.STEEL-BRIDGE (GR 60)	47,140.00	LB
812003	BRIDGE NAME PLATE (TYPE C)	1.00	EACH
816003	FILTER BLANKET	6,668.00	SQYD
816111	DUMPED RIPRAP	3,334.00	CUYD

30" PIPE CULVERTS (CLASS IV) ALTERNATE - BID ONE ITEM ONLY

605613	30" R.C.PIPE CULVERTS(CL.4)	50.00	LF
605692	30" ASPH.C.C.ST.PIPE CLVT.-16G	56.00	LF
605707	30" AL.C.C.ST.PIPE CLVT.-16G	56.00	LF
605727	30" P.P.M.C.C.ST.PIPE CLVT.-16G	56.00	LF

30" PIPE CULVERTS (CLASS V) ALTERNATE - BID ONE ITEM ONLY

605614	30" R.C.PIPE CULVERTS(CL.5)	96.00	LF
605692	30" ASPH.C.C.ST.PIPE CLVT.-16G	108.00	LF
605707	30" AL.C.C.ST.PIPE CLVT.-16G	108.00	LF
605727	30" P.P.M.C.C.ST.PIPE CLVT.-16G	108.00	LF

42" PIPE CULVERTS ALTERNATE - BID ONE ITEM ONLY

605624	42" R.C.PIPE CULVERTS(CL.5)	96.00	LF
605695	42" ASPH.C.C.ST.PIPE CLVT.-14G	108.00	LF
605709	42" AL.C.C.ST.PIPE CLVT.-14G	108.00	LF
605731	42" P.P.M.C.C.ST.PIPE CLVT.-14G	108.00	LF

29" X 18" ARCH PIPE CULVERTS ALTERNATE - BID ONE ITEM ONLY

605775	29" X 18" R.C.ARCH PIPE CLVT.(CL.4)	130.00	LF
605786	28"X20" AL.C.C.ST.ARCH PIPE CLVT.-16G	148.00	LF
605798	28"X20" A.C.C.ST.ARCH PIPE-16G	148.00	LF
605810	28"X20" P.P.M.C.C.ST.ARCH PIPE-16G	148.00	LF

44" X 27" ARCH PIPE CULVERTS ALTERNATE - BID ONE ITEM ONLY

605768	44" X 27" R.C.ARCH PIPE CLVT.(CL.4)	100.00	LF
605788	42"X29" AL.C.C.ST.ARCH PIPE CLVT.-14G	112.00	LF
605800	42"X29" A.C.C.ST.ARCH PIPE-14G	112.00	LF
605812	42"X29" P.P.M.C.C.ST.ARCH PIPE-14G	112.00	LF

30" FLARED END SECTIONS ALTERNATE - BID ONE ITEM ONLY

605860	30" FES R.C.PIPE CLVT.	6.00	EACH
605861	30" FES C.ST.PIPE CLVT.	6.00	EACH

42" FLARED END SECTIONS ALTERNATE - BID ONE ITEM ONLY

605864	42" FES R.C.PIPE CLVT.	4.00	EACH
605865	42" FES C.ST.PIPE CLVT.	4.00	EACH

29" X 18" FLARED END SECTIONS ALTERNATE - BID ONE ITEM ONLY

605883	29"X18" FES R.C.ARCH PIPE CLVT.	6.00	EACH
605884	28"X20" FES C.ST.ARCH PIPE CLVT.	6.00	EACH

44" X 27" FLARED END SECTIONS ALTERNATE - BID ONE ITEM ONLY

605887	44"X27" FES R.C.ARCH PIPE CLVT.	2.00	EACH
605888	42"X29" FES C.ST.ARCH PIPE CLVT.	2.00	EACH

20' GATES ALTERNATE - BID ONE ITEM ONLY

619335	20' STEEL GATES	1.00	EACH
619432	20' ALUMINUM GATES	1.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT WITHIN FOUR HUNDRED TEN (410) CALENDAR DAYS.