

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA0367

HWY. 201 – HWY. 126 (OVERLAY) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO OVERLAY APPROXIMATELY 3.00 MILES OF COUNTY ROAD 57 AND APPROXIMATELY 0.30 MILE OF COUNTY ROAD 618 IN BAXTER COUNTY. THIS PROJECT CONSISTS OF ACHM SURFACE COURSE, ACHM PATCHING, PAVEMENT MARKING, MAINTENANCE OF TRAFFIC, AND MISC ITEMS.

ROUTES: CRS 57 & 618

COUNTY: BAXTER

LENGTH: 3.30 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401011	TACK COAT	3,826.00	GAL
407162	MA IN ACHM SURFACE(1/2")	4,690.00	TON
407432	AB(PG64-22)ACHM SURF(1/2")	299.00	TON
415011	ACHM PATCH.EXIST.RDWY.	50.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	228.00	SQFT
718101	REFL.PAINT PVMT.MRK.YL(4")	34,848.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE November 25, 2026.