

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA1363

CLEVELAND CO. LEVEL & RESEAL (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO LEVEL AND SEAL APPROXIMATELY 1.70 MILES OF BANKS RD. & 1.75 MILES OF HARRELSON RD. IN CLEVELAND COUNTY. THIS PROJECT CONSISTS OF FOG SEAL, ASPHALT SURFACE TREATMENT, ACHM SURFACE COURSE, MAINTENANCE OF TRAFFIC, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: BANKS RD. & HARRELSON RD.

COUNTY: CLEVELAND

LENGTH: 3.45 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

303117	AGGR.BASE COURSE(CLASS 7)	20.00	TON
401005	FOG SEAL (TYPE 2)	4,048.00	GAL
401011	TACK COAT	1,830.00	GAL
402112	MINERAL AGGR.IN A.S.T.(CL2)	708.00	TON
402214	PLY.MOD.CAT.EMLS.ASPH.(CRS2P)(SLD.PLY.)	16,192.00	GAL
407161	MA IN ACHM SURFACE(3/8")	1,141.00	TON
407431	AB(PG64-22)ACHM SURF(3/8")	79.00	TON
415011	ACHM PATCH.EXIST.RDWY.	70.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	347.00	SQFT
718101	REFL.PAINT PVMT.MRK.YL(4")	36,432.00	LF
726002	STANDARD SIGN	48.00	SQFT
729003	CHANNEL POST SIGN SUPPORT-C	10.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE October 16, 2026.