

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA5453

HWY. 1 – HWY. 39 (RESEAL) (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO LEVEL AND SEAL APPROXIMATELY 5.00 MILES OF COUNTY ROAD 600 IN PHILLIPS COUNTY. THIS PROJECT CONSISTS OF ASPHALT SURFACE TREATMENT, ACHM SURFACE COURSE, ACHM PATCHING OF EXISTING ROADWAY, MAINTENANCE OF TRAFFIC, PAVEMENT MARKING, AND MISC. ITEMS.

ROUTES: CR 600

COUNTY: PHILLIPS

LENGTH: 5.00 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

401011	TACK COAT	600.00	GAL
402112	MINERAL AGGR.IN A.S.T.(CL2)	1,131.00	TON
402214	PLY.MOD.CAT.EMLS.ASPH.(CRS2P)(SLD.PLY.)	25,857.00	GAL
407161	MA IN ACHM SURFACE(3/8")	374.00	TON
407431	AB(PG64-22)ACHM SURF(3/8")	26.00	TON
415011	ACHM PATCH.EXIST.RDWY.	50.00	TON
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	132.00	SQFT
718001	REFL.PAINT PVMT.MRK.WH(4")	52,800.00	LF
718101	REFL.PAINT PVMT.MRK.YL(4")	12,353.00	LF

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE October 16, 2026.