

ARKANSAS DEPARTMENT OF TRANSPORTATION

SA6651

SEVIER CO. RESEAL NO. 19 (S)

STATE AID COUNTY JOB (CODE 9970)

THE PURPOSE OF THIS PROJECT IS TO SURFACE APPROXIMATELY 3.79 MILES OF BEAR CREEK CUTOFF & APPROXIMATELY 2.75 MILES OF DOG TOWN RD. IN SEVIER COUNTY. THIS PROJECT CONSISTS OF ASPHALT SURFACE TREATMENT, PAVEMENT MARKING, MAINTENANCE OF TRAFFIC, AND MISC. ITEMS.

ROUTES: BEAR CREEK CUTOFF & DOG TOWN RD.

COUNTY: SEVIER

LENGTH: 6.54 miles in length.

THE FOLLOWING ITEMS AND APPROXIMATE QUANTITIES ARE INVOLVED:

402111	MINERAL AGGR.IN A.S.T.(CL1)	1,334.00	TON
402214	PLY.MOD.CAT.EMLS.ASPH.(CRS2P)(SLD.PLY.)	38,113.00	GAL
601001	MOBILIZATION	1.00	L.S.
603009	MAINTENANCE OF TRAFFIC	1.00	L.S.
604003	SIGNS	500.00	SQFT
718101	REFL.PAINT PVMT.MRK.YL(4")	68,662.00	LF
721002	RAISED PAVEMENT MARKERS-2	251.00	EACH

THE SUCCESSFUL BIDDER WILL BE REQUIRED TO COMPLETE THIS CONTRACT ON OR BEFORE October 16, 2026.